

Hydro Place. 500 Columbus Drive. P.O. Box 12400. St. John's. NL Canada A1B 4K7 t. 709.737.1400 f. 709.737.1800 www.nlh.nl.ca

August 4, 2017

The Board of Commissioners of Public Utilities Prince Charles Building 120 Torbay Road, PO Box 21040 St. John's, NL A1A 5B2

Attention: Ms. Cheryl Blundon

Director of Corporate Services and Board Secretary

Dear Ms. Blundon:

Re: The Board's Investigation and Hearing into Supply Issues and Power Outages on the Island Interconnected System – Availability of Requested Information from Hydro, August 4, 2017 Update

By letter dated May 3, 2017, the Board requested certain information from Hydro. Hydro responded by letters dated May 15, 2017, May 26, 2017 and July 5, 2017. By letters dated July 19, 2017 and July 21, 2017, the Board wrote to Hydro with questions in respect of the information filed and noting concern that certain information sought by the Board would not be available "for some time" and "that filing dates were not provided in relation to several items."

In response to the Board's questions and concerns, Hydro wishes to provide further clarity with respect to the noted items as follows:

1. No date was provided for the provision of information with respect to the commercial arrangements for the purchase of recall power and energy and use of the necessary transmission facilities. Hydro identified that first power transfer over the Labrador Island Link ("LIL") is expected in Q3, 2018. It is noted that the Board's conclusion in its May 12, 2017 letter that no immediate steps were necessary to reduce the risks to adequate and reliable supply on the Island Interconnected system as currently configured was based, in part, on Hydro's planned reliance on the availability of recall power prior to interconnection. [May 3, 2017 letter, items #8 and 14]

Mature drafts of agreements concerning the use of necessary transmission facilities for recall power have been developed and are in circulation with the parties (Hydro as the transmission user, Newfoundland Labrador System Operator as transmission service provider, and the Labrador Transmission Company and Labrador-Island Link Limited Partnership as transmission owners). The purchase arrangement for recall power is in

development. It is anticipated that these commercial arrangements will be completed and executed in 2017.

In addition, opportunities for sources of energy that can be imported through Labrador, and transmitted via the Labrador-Island Link (LIL) to serve island load have been investigated. A number of high potential opportunities have been identified, and negotiations are advanced. While the details of the agreements that are expected to result from these negotiations are confidential, they are based on commonly used templates which are publicly available, and which establish the relationship between the two parties to enable future energy transactions with minimal negotiation, other than to agree on price, quantity and timing of delivery. These agreements will serve to reduce the amount of energy produced by the Holyrood Thermal Generating Station for Island needs, and will provide some capacity to the system; however, as previously demonstrated, these agreements provide for supply that is over and above the interconnected Island system requirements as presented in the Near-Term Generation Adequacy Report.

2. A first draft of the emergency restoration plans for the LIL, which Hydro contemplates utilizing in 2018, will not be available until November 2017. [May 3, 2017 letter, item #7]

The contractor's key dates for delivery of the emergency restoration plans for the LIL are outlined below:

Item	Date
Develop, Release and Award Contract	July 31, 2017
Contract Kick-off	July 31, 2017
Complete site visits and Risk Workshop	August 2017
Delivery of Risk Severity Matrix	September 2017
Design Solutions and Presentation/Selection of Repair Approach, forming the basis of the Draft Emergency Response Plan	November 2017
Deliver Final Emergency Response Plan and Incident Response Approach	January 2018

www.eei.org/resourcesandmedia/mastercontract/Documents/contract0004.doc.

¹ Power purchase agreements are based on the "Master Power Purchase & Sale Agreement - Edison Electric Institute", which is publicly available at

3. No date was provided for the filing of information with respect to the emergency power and reserve sharing arrangements with Atlantic Canadian utilities. [May 3, 2017 letter, item #11]

As previously noted, as a part of the Interconnection Operators Agreement (IOA) executed between Hydro and Nova Scotia Power (NSPI), there are provisions whereby both parties agree to formalize arrangements to share operating reserves and to provide emergency and security energy to one another. These arrangements will be detailed in the schedules contemplated in the IOA.

Both NSPI and Hydro have been working towards finalizing the contents of the schedules. Changes recently proposed by Hydro will be discussed at the next meeting of the Interconnection Operators Committee, which is scheduled for August 30, 2017. The intent is to finalize the schedules prior to energization of the Maritime Link (ML).

4. The planning criteria applicable following interconnection will not be provided until Q4, 2018. [May 3, 2017 letter, item #17]

Hydro continues to investigate the most appropriate planning criteria for the provincial electricity system following the in-service of the LIL, the ML, and the Muskrat Falls Generating Station. Hydro recognizes the importance of the outcomes of this decision, and particularly the potential impact it will have on customers. Hydro must ensure that it provides acceptable levels of reliability for customers, while balancing the overall cost of the system to ensure rates remain as reasonable as possible. While additional investment can increase reliability for customers, such investment needs to be optimized to ensure that the cost of the investment is justified. This means that any decisions to modify planning criteria must be made prudently, with the engagement of Hydro's stakeholders and in full consideration of customer expectations, and potential system impacts.

To assist in this assessment, Hydro is developing the following:

- A new software model for generation planning, developed in PLEXOS (Plexos). This
 software is capable of modelling Hydro's electrical system with greater accuracy and
 detail. Further, the model will include representation of Hydro's bulk transmission
 system, ensuring the deliverability of Hydro's resources to meet customer
 requirements. More details about the implementation of the Plexos model are
 provided below; and
- An evaluation of the impacts of compliance with North American reliability standards. Hydro is conducting analysis to determine what reliability standards are most appropriate for Hydro's system, and what modifications (if any) would be required to adopt such standards. Hydro is conducting this analysis for both deterministic (i.e., Reserve Margin) and probabilistic (i.e., Loss of Load Expectation) reliability assessments.

Plexos is a power system simulation tool developed by Energy Exemplar. In selecting the software, Hydro engaged in several discussions with both the vendor and model users to ensure it best met Hydro's modelling requirements. A few notable benefits of this software over that currently used by Hydro are:

- Plexos is widely used in industry, and is currently used by both NSPI and New Brunswick Power (NBP). This will enable better sharing of information between Hydro and its neighboring utilities;
- The software is also used by many primarily hydro-based utilities. This indicates that the software is capable of modelling the complexities of hydro-based systems;
- The software includes modelling of the underlying bulk transmission system, ensuring resource deliverability between source and load; and
- The software is capable of hourly modelling, allowing Hydro to model its system with a greater level of detail, particularly for periods near peak.

In addition to leasing the software, Hydro has engaged Energy Exemplar to develop the base system model. As part of that implementation effort, Energy Exemplar will be on site for project kickoff and software training, then work closely with Hydro's Resource and Production Planning department to develop a comprehensive model of Hydro's interconnected system. The project kick-off meetings and training are scheduled for the week of August 28, 2017. The system model is expected to be complete by year-end 2017, with extensive model testing and refinement to come in Q1 of 2018.

Following the completion of the model, Hydro will be able to fully assess the reliability of the current system and evaluate the potential impact of compliance with North American reliability standards.

Once the above has been compiled and assessed, Hydro will make its recommendations on appropriate planning criteria to the Board in 2018, as previously noted.

Hydro proposes these activities culminate in the "Resource Adequacy" report to the Board, to be delivered November 15, 2018. This proposed report will address both near-term and long-term resource adequacy and will discuss:

- demand and energy projections in the operational (less than 3 years) and planning (3-10 years) horizons;
- asset integrity, in-service and retirement plans;
- system adequacy analysis including the identification of potential capacity or energy surplus/deficit;
- discussion of near-term resource options;
- generation expansion analysis;
- sensitivity analysis; and
- other issues as required.

To summarize, the following provides a high-level schedule for the above activities:

Item	Date
Plexos Modelling: Project Kick-off and Software Training	August 28-31, 2017
Interconnected System Model Developed	December 31, 2017
Model Testing and Refinement	January to April 2018
Assessment of Hydro's System Adequacy and Determination of Planning Criteria	May to September 2018
Analysis of results and report development	September to November 2018
Resource Adequacy Report	November 15, 2018

Note that in advance of the interconnected system model and approved planning criteria, Hydro will continue to provide its assessment of Near-term Generation Adequacy in a manner consistent with that last provided on May 15, 2017. Hydro proposes that the above-mentioned Resource Adequacy report will replace the Near-term Generation Adequacy report at that time.

5. Discussions are ongoing in relation to opportunities for near term supply from Nova Scotia Power and New Brunswick Power but are not expected to conclude until Q4, 2017. [May 3, 2017 letter, item #18]

As previously reported to the Board, NSPI and NBP were approached in late 2016 and early 2017 to discuss potential opportunities for the near term supply of energy without firm capacity to the island over the ML. Both NSPI and NBP indicated that opportunities will likely materialize to provide energy via the ML, but such arrangements were not identifiable for contract in advance. It is expected that these opportunities will materialize closer to the dates of anticipated delivery, based on what they will have available in excess of their actual requirements for their customers at the time.

Nalcor Energy Marketing (NEM) already has agreements in place with both NSPI and NBP, and while the details of these agreements are confidential, they are based on a commonly used template that is publicly available.² These agreements establish the relationship between the parties and enables future energy transactions to require minimal negotiation, other than to agree on price, quantity and timing of delivery. In addition, NEM is in negotiations with these parties to develop framework agreements to

-

² See footnote 1.

streamline further the negotiation process to enable mutually beneficial trade opportunities.

With respect to available capacity from the Maritimes, the resource adequacy in the Maritimes has been described in a publicly available Northeast Power Coordinating Council (NPCC) report, 2016 Maritimes Area Comprehensive Review of Resource Adequacy, ³ attached as Appendix "A".

6. A number of studies related to supply from the Muskrat Falls Generating Station are not scheduled to be completed until 2018 [May 3, 2017 letter, items # 6, 9, 10, 12, 13, 19, 20, 21, and 24]

Hydro has established a plan for the completion of operational studies and has staged these studies to match the anticipated in-service date of new assets. The stages are summarized as follows:

Stage I	Addition of the ML
Stage II	Addition of the Soldiers Pond Synchronous Condensers
Stage III	Addition of the LIL and Labrador Transmission Asset
Stage IV	Addition of Muskrat Falls Generation

Hydro is committed to providing updates pertaining to operational studies and submitting all completed reports upon receipt. Details relating to the plan including the forecasted timeline for the submission of all reports are provided in Appendix "B".

For further clarity, each study would cover the requested information as noted below:

Item #	Description	Study Stage
6	HVdc converter station contractors' studies and copies of any completed study	Stage IV
9	Interaction studies between the IIS and the ML completed since Preliminary Interconnection Studies dated August 2014, including with the ML in and out of service [High Power]	Stage I, II, III, IV
10	Update on study regarding additional reactive power	Stage IV
12	Frequency Controller study for the ML	Stage I, II, III, IV
13	Systems Studies to determine reserve sharing between LIL and IIS generation	Stage IV
19	Bay d'Espoir instability studies	Stage IV

³ https://www.npcc.org/Library/Resource Adequacy/2016 Maritimes Area CRRA for RCCpaf.pdf

_

Item	Description	Study Stage
#		
20	Underfrequency Load Shedding scheme post Muskrat Falls	Stage IV
21	Operational Studies regarding IIS post Muskrat Falls	Stage IV
24	Studies of the performance of the IIS with the ML in service and with it out of service (and resulting operating guidelines)	Stage III, IV

7. The requested updated post Muskrat Falls interconnection energy supply assessment, which Liberty noted in its August 2016 report (page 87) was underway with expected completion in 2016, appears to have been replaced with a proposal to provide annual generation capability updates following interconnection. [May 3, 2017 letter, item #16]

Please see Hydro's response to #4 above.

8. Hydro's reply with respect to four items was unclear requiring the Board to seek further clarification in its letter of July 19, 2017.

In Hydro's previous correspondence, the following note was included with several items:

The nature of the information provided may be subject to any response by Hydro to this recommendation and the Board's final determination on (i) Liberty's recommendations and (ii) the parties' submissions.

This note was originally provided in respect of items noted in the table below, as it was expected that further Board directives would be issued in respect of recommendations from Phase 2 Liberty Report, to which Hydro may have been required to respond. As this process did not take place before the information was requested in May 2017, Hydro was uncertain as to whether the form of information to be provided in each instance would be sufficiently defined at this stage to satisfy the Board's ultimate requirements.

Further comment in respect of each item is noted below.

Item #	Description	Reference	Hydro Comment
6	Update on studies for HVdc converter station contractors' studies and copies of any completed study	Liberty Report, page 79, Recommendation IV-2	This request was based on Liberty's recommendations that the converter station contractor should perform "transient stability studies with multiple restart attempts for HVdc OHL faults". While certain elements of this requirement may be met by the high power studies currently underway (noted above), this may not ultimately take the form requested by the Board, absent specific direction to that effect.
16	Updated Energy Supply Risk Assessment Post Muskrat Falls	Liberty Report, page 87, Recommendation V-3 and page 112, Recommendation V-3	Please see #4 and #7, above. As noted, Hydro will be putting certain planning information before the Board in the 2018 period, and following receipt of Board direction will be filing the appropriate form of "Resource Adequacy" report.
22	Update on multi-year reliability compliance program and Provincial Reliability Framework	Liberty Report, Recommendation s VI-15, page 106	Hydro provided a response to this request on July 5, 2017. As the current course of action as described in that response is unlikely to be impacted by the outcome of this proceeding, Hydro should have removed this note in its July response.
23	Status of plan for compliance with NERC	Liberty Report, page 101-102 and Recommendation VI-14, page 106	Hydro provided a response to this request on July 5, 2017. As the current course of action as described in that response is unlikely to be impacted by the outcome of this proceeding, Hydro should have removed this note in its July response.

9. A detailed Integrated Project Schedule setting out all activities required to ensure successful transition to operations (see Liberty's August 19, 2016 report, pages 93-94). To allow the Board to fully understand the nature of the necessary work and the planning for and completion of this work, Hydro should also file the associated underlying data, including the following information, regarding the transition schedule:

Ms. C. Blundon Public Utilities Board

- A listing of all scheduled activities, together with baseline start and finish dates as well as the current forecasted start and finish dates
- Indicators of the status of each task vis-à-vis the critical path
- Resources associated with each task, as and if loaded into the schedule
- Sample schedule reports being used by transition team management
- Key assumptions underlying the schedule

Please see the attached Appendix "C".

Further updates will be provided as soon as they are available.

Please advise if you have any questions with respect to the attached.

Yours truly,

NEWFOUNDLAND AND LABRADOR HYDRO

Geoffrey P. Young

Corporate Secretary & General Counsel

GPY/vc

cc:

Gerard Hayes – Newfoundland Power Paul Coxworthy – Stewart McKelvey Stirling Scales Roberta Frampton Benefiel – Grand Riverkeeper Labrador

000.


Denis Fleming- Vale Newfoundland & Labrador Limited

Dennis Browne, Q.C. – Consumer Advocate Danny Dumaresque

Larry Bartlett - Teck Resources Ltd.

NPCC 2016 MARITIMES AREA COMPREHENSIVE REVIEW OF RESOURCE ADEQUACY

Approved by RCC December 6, 2016



NEW BRUNSWICK POWER CORP. NOVA SCOTIA POWER INCORPORATED MARITIME ELECTRIC COMPANY, LIMITED NORTHERN MAINE ISA, INC. This page intentionally left blank.

EXECUTIVE SUMMARY

The 2016 Maritimes Area Comprehensive Review of Resource Adequacy, covering the period of January 2017 through December 2021, has been prepared to satisfy the compliance requirements as established by the Northeast Power Coordinating Council (NPCC). The guidelines for this review are specified in the *NPCC Regional Reliability Directory #1 Appendix D (Approved: September 30, 2015)*. This review supplants the previous Comprehensive Review that was performed in 2013 and approved by the RCC on December 3, 2013.

Table 1 provides a summary of the major assumptions and results of this review.

Table 1: Summary of Major Assumptions and Results

MAJOR ASSUMPTIONS		
Load Forecast	2016 (all jurisdictions)	
Load Shape	2011/12 (all years)	
Resource Adequacy Criterion	Loss of Load Expectation not more than 0.1 days/year	
Maritimes Required Reserve	20% of peak firm load	
Interconnection Benefits	300 MW	
Area Purchases/Sales	Sales of 200 MW and 114 MW during the 2016/17 and 2018/19 winter peak periods respectively	
Maritime Link Project	153 MW of purchases from Newfoundland to Nova Scotia is forecast for mid-2020 coincident with a planned retirement of a 153 MW Nova Scotia generator	
RESULTS		
Year Expected Number of Firm Load Disconnection days/year		
2017	0.003	
2018	0.003	
2019	0.003	
2020	0.003	
2021 0.004		

The 2017 coincident peak demand forecast for the Maritimes Area is 5,392 MW, which is 125 MW above the 5,267 MW peak demand forecast in the 2013 Comprehensive Review. This increased peak demand forecast reflects increases in electric heating loads which are not quite offset by declines in industrial loads and demand shifting programs. The average annual demand growth over the 2017–2021 study period of this review is 0.16%, which is marginally higher than the -0.05% annual demand growth forecast in the 2013 review but still essentially flat.

The reserve criterion for the Maritimes Area is 20%, and adherence to this criterion is demonstrated in Section 2.4 to comply with the NPCC resource adequacy criterion.

The NPCC resource adequacy criterion of a Loss of Load Expectation (LOLE) of not more than 0.1 days per year of firm load disconnections is not exceeded by the Maritimes Area for all years covered by this review and varies between 0.003 to 0.004 days/year for the base load forecast. The Maritimes Area is also shown to adhere to its own 20% reserve criterion in all years for the base load forecast, with minimum reserve levels varying between 40% and 44%.

Sensitivity analyses were run to determine the LOLE effects of high load growth, zero wind generation, and removing all external tie benefits. The sensitivity results are shown in Table 2 and meet the NPCC resource adequacy criterion in all years.

Table 2: Summary of LOLE Results

Year	Base Case LOLE days/year	High Load Growth LOLE days/year	Zero Wind LOLE days/year	No Tie Benefits LOLE days/year
2017	0.003	0.003	0.017	0.005
2018	0.003	0.003	0.012	0.003
2019	0.003	0.006	0.016	0.004
2020	0.003	0.010	0.019	0.004
2021	0.004	0.019	0.026	0.005

TABLE OF CONTENTS

EXECUTIVE SUMMARY	I
TABLE OF CONTENTS	III
List of Tables	IV
List of Figures	IV
1.0 INTRODUCTION	1
2.0 RESOURCE ADEQUACY CRITERION	2
2.1 Statement of Resource Adequacy Criterion	2
2.2 Emergency Operating Procedures	3
2.3 Maritimes Area Required Reserve	4
2.4 Relationship of Reserve Criterion to NPCC Reliability Criterion	4
2.5 Recent Reliability Studies	4
2.6 Load Forecast Uncertainty	5
2.7 Intra-Area Transmission Capacity Limits	6
3.1 Comparison of Forecast and Required Reserve – Base Case	8
3.2 LOLE results – High Load Growth	8
3.3 LOLE Results – Zero Wind	9
3.4 LOLE Results – No Tie Benefits	9
3.5 Contingency Plans	11
4.0 FORECAST RESOURCE CAPACITY MIX	11
4.1 Forecast Resource Capacity Mix	11
4.2 Reliability Impact of Resource Diversification Strategy	12
APPENDIX A - DESCRIPTION OF RESOURCE RELIABILITY MODEL	14
APPENDIX B - DESCRIPTION OF RELIABILITY PROGRAM	25

List of Tables

Table 1:	Summary of Major Assumptions and Results	I
Table 2:	Summary of LOLE Results	
Table 3:	Comparison of Load Forecasts	
Table 4:	LOLE days/year – Base Case with Load Forecast Uncertainty	
Table 5:	Forecast, Minimum, and Required Reserve Levels – Base Case	
Table 6:	Loads and LOLE Results – High Load Growth	
Table 7:	Capacity and LOLE Results – Zero Wind	
Table 8:	Capacity and LOLE Results – No Tie Benefits	
Table 9:	Forecast Capacity Resource Mix	
Table A-1:	Maritimes Area Load Forecast	15
	Maritimes Area Resources	
Table A-3:	Summary of Changes in Modeled Capacity	20
Table A-4:	Maritimes Area Forced Outage Rates	22
List of Figu	ıres	
Figure 1:	Comparison of Load Forecasts	2
Figure 2:	LOLE (days/year) – Base Case with Load Forecast Uncertainty	6
Figure 3:	Maritimes Area Transmission Capacity Limits (non-Firm)	7
Figure 4:	LOLE Results – All Base and Sensitivity Cases	11
Figure 5:	Forecast Capacity Resource mix	12

1.0 INTRODUCTION

The 2016 Maritimes Area Comprehensive Review of Resource Adequacy, covering the period of January 2017 through December 2021, has been prepared to satisfy the compliance requirements as established by the Northeast Power Coordinating Council (NPCC). The guidelines for this review are specified in NPCC Directory #1 Appendix D, Guidelines for Area Review of Resource Adequacy (Approved: September 30, 2015). This review supplants the previous Comprehensive Review that was performed in 2013 and approved by the RCC on December 3, 2013.

The Maritimes Area is a winter peaking area with separate jurisdictions and regulators in New Brunswick, Nova Scotia, Prince Edward Island (PEI), and Northern Maine. New Brunswick Power (NB Power) is the Reliability Coordinator for the Maritimes Area.

Table 3 and Figure 1 provide a comparison of the load forecasts in the 2016 and 2013 reviews. The coincident peak demand forecast for 2017 is 5,392 MW, which is 125 MW above the 5,267 MW forecast in the 2013 Comprehensive Review. This increased peak demand forecast reflects increases in electric heating demands which were not offset by declines in industrial loads and demand shifting programs. Demand shifting and energy efficiency programs are expected to reduce peak demand in the Maritimes Area by 100 MW to 280 MW during the Comprehensive Review period. The average annual demand growth over the period of this review is 0.16%, which is marginally higher than the 0.05% average demand growth forecast in the 2013 review but still essentially flat.

Table 3: Comparison of Load Forecasts

Winter Peak (Month of January)	2016 Review MW	2013 Review MW
2017	5,392	5,267
2017	5,406	5,253
2019	5,416	N/A
2020	5,432	N/A
2021	5,426	N/A
Five Year Period	2017–2021	2014–2018
Annual Average Growth Rate	0.16%	0.05%




Figure 1: Comparison of Load Forecasts

2.0 RESOURCE ADEQUACY CRITERION

2.1 Statement of Resource Adequacy Criterion

For planning purposes, New Brunswick, Nova Scotia, PEI and Northern Maine individually apply a capacity based criterion in determining their required reserves.

New Brunswick, Nova Scotia, and Northern Maine each plan for a reserve equal to greater of the capacity of the largest generator or 20% of the firm load. For this review, the latter criterion was applicable in all years. PEI plans for a reserve equal to 15% of its firm load. As a simplification, this review applies the 20% reserve criterion to the Maritimes Area as a whole because of the relatively small size of PEI compared to the rest of the Maritimes Area. Thermal and hydro generators are considered available at the Dependable Maximum Net Capability (DMNC) in the determination of the reserve margin.

The NPCC resource adequacy criterion (from NPCC Directory #1 Design and Operation of the Bulk Power System, Requirement 4 (Dated: September 30, 2015) states:

"R4 Each Planning Coordinator or Resource Planner shall probabilistically evaluate resource adequacy of its Planning Coordinator Area portion of the bulk power

system to demonstrate that the loss of load expectation (LOLE) of disconnecting firm load due to resource deficiencies is, on average, no more than 0.1 days per year.

R4.1 Make due allowances for demand uncertainty, scheduled outages and deratings, forced outages and deratings, assistance over interconnections with neighboring Planning Coordinator Areas, transmission transfer capabilities, and capacity and/or load relief from available operating procedures."

2.2 Emergency Operating Procedures

Although this document presents a review of resource adequacy for the interconnected Maritimes Area, each separate system remains under the exclusive control of its system operator for purposes of economic dispatch. For reliability purposes, however, reserve sharing agreements do exist and the systems operate as an Area in accordance with NPCC criteria and guidelines.

Actions taken by the Energy Coordinator/Dispatcher, when faced with a developing or sudden capacity shortage, are based upon a number of possible actions best suited to the prevailing system conditions. In practice, the corrective actions taken are one or more of the following Emergency Operation Procedures (EOP):

- 1. Synchronize and load all available hydro generators.
- 2. Bring on-line generators up to their DMNC.
- 3. Cancel economy and other external interruptible sales.
- 4. Begin start-up procedures for "cold-standby" thermal generators.
- 5. Synchronize and load combustion turbines.
- 6. Purchase capacity from Hydro-Québec.
- 7. Purchase capacity from New England.
- 8. Cut interruptible sales to industrial customers.

- 9. Maximize MVAR support (capacitor banks, synchronous condensers) if capacity shortage is causing a low voltage condition in a particular area.
- 10. Implement a 5% voltage reduction at selected substations within Nova Scotia (1–5 MW)
- 11. Appeal to the public for voluntary customer load reduction.
- 12. Disconnect customer loads as necessary to correct either a local or widespread problem.

Some or all of the above steps may be used in varying sequence to meet a capacity shortage depending on the generation pattern in effect at the time and whether or not the shortage results in localized internal system problems.

Although steps 10 and 11 are valid, the level of assistance available from these procedures is not modeled in this study.

2.3 Maritimes Area Required Reserve

The Maritimes Area employs a reserve criterion of 20% of firm load. The required installed reserve is shown in Section 3.1.

2.4 Relationship of Reserve Criterion to NPCC Reliability Criterion

To relate the Maritimes Area reserve criterion of 20% to the NPCC resource adequacy criterion as stated in Section 2.1, LOLE was evaluated with the Maritimes Area firm load scaled so that the reserve was equal to 20%. The results showed that a Maritimes Area reserve of 20% corresponds to an LOLE of approximately 0.086 days per year. At this load level, only 30 MW of additional load was required to match the NPCC LOLE resource adequacy criterion of 0.1 days per year.

The preceding demonstrates that the 20% Maritimes Area reserve criterion correlates closely with the 0.1 days/year NPCC LOLE resource adequacy criterion.

2.5 Recent Reliability Studies

Resource Planners in New Brunswick, Nova Scotia, PEI, and Northern Maine individually conduct internal reviews of their capacity requirements by comparison of generation sources with forecast loads according to the reserve criterion described previously.

The results presented in this review are based upon an evaluation conducted during the third quarter of 2016 for the period 2017 through 2021. This review supplants the previous Comprehensive Review that was performed in 2013 and approved by the RCC on December 3, 2013. Interim reviews of resource adequacy for the Maritimes Area were completed in the years 2014 and 2015 covering the years 2015–2018 and 2016–2018 respectively. The results of the interim reviews for the two overlapping years 2017 and 2018 compare well with the results of this review. The NPCC resource adequacy criterion was met in both years for all base and sensitivity cases. The same is true for this review.

2.6 Load Forecast Uncertainty

To determine load forecast uncertainty (LFU) an analysis of the historical load forecasts of the Maritimes Area utilities has shown that the standard deviation of the load forecast errors is approximately 4.6% based upon the four year lead time required to add new resources. To incorporate LFU, two additional load models were created from the base load forecast by increasing it by 4.6 and 9.2 percent (one or two standard deviations) respectively. The reliability analysis was repeated for these two load models.

It is assumed that the forecast error is approximately normally distributed around the forecast value and that the contribution to system LOLE is negligible when loads are less than the forecast value by more than ½ a standard deviation. These assumptions result in weighting factors of 0.383, 0.242, and 0.067 for the three results obtained using the base, 4.6 percent increased, and 9.2 percent increased load models respectively.

The results of the LFU evaluation as indicated in Table 4 and Figure 2 demonstrate that the Maritimes Area system meets the NPCC resource adequacy criterion of no more than 0.1 days/year from 2017 to 2021.

Table 4: LOLE days/year – Base Case with Load Forecast Uncertainty

Calendar Year	Expected Number of Firm Load Disconnections days/year
2017	0.003
2018	0.003
2019	0.003
2020	0.003
2021	0.004




Figure 2: LOLE (days/year) – Base Case with Load Forecast Uncertainty

2.7 Intra-Area Transmission Capacity Limits


Within the Maritimes Area, the areas of Nova Scotia, PEI, and Northern Maine are each connected only to New Brunswick as per Figure 3. A transmission congestion issue of consequence to the LOLE occurs for only one of these three interconnections, the tie between New Brunswick and Nova Scotia.

Transmission capacity limits between Northern Maine and New Brunswick were not modeled for this analysis. These normal limits are a result of parallel operation of four lines (two 138 kV, two 69 kV) that Northern Maine keeps below thermal ratings to ensure that the trip of one of these lines doesn't overload the others. Should one or more contingencies occur in Northern Maine, the lines can be switched from parallel to radial operating modes. This effectively allows a high enough transfer limit from New Brunswick to meet the peak load in Northern Maine.

Late in 2016, PEI is installing two additional undersea cables between that province and New Brunswick. Based on a tripling of cable capacity and two additional parallel paths, the single cable contingency limiting flows from PEI to NB has been eliminated. For this review, the transmission limit for this return path was assumed to equal the transmission limit in the NB to PEI direction and as a result the PEI to NB limit was increased from 124 MW to 222 MW. This change has a negligible effect on the Maritimes Area LOLE values since there is little need for PEI capacity to supply NB

loads given the high amount of reserve capacity available to NB from other resources.





3.0 RESOURCE ADEQUACY ASSESSMENT

3.1 Comparison of Forecast and Required Reserve – Base Case

In the comparison of the forecast and required reserve, the following definitions apply. The required reserve of 20% is the reserve criterion of the Maritimes Area. The forecast reserve is the actual reserve that will occur for the load forecast and resource plan used in this study.

Table 5 and Figure 4 represent the results of the reserve comparison for the base load forecast. The forecast reserve levels reflect reserves calculated using wind generation levels at the hour of the Maritimes Area coincident peak demand. In 2017, the wind generation modeled on peak was 496 MW. Based on the wind and load shapes modeled, the minimum hourly reserve expected during 2017 is 1993 MW coinciding with a total Maritimes Area wind generation of 83 MW. In each year of the analysis, the forecast reserve is greater than the required reserve.

Table 5: Forecast, Minimum, and Required Reserve Levels – Base Case

Month Of January	Forecast Capacity	Coincident Peak Load	Inter. Load	Forecast Reserve		Minim Hour Reser	ly	Requi Resei	
Januar y	MW	MW	MW	MW	%	MW	%	MW	%
2017	7,207	5,392	268	2,083	41	1,993	41	1,025	20
2018	7,418	5,406	272	2,284	44	2,173	44	1,027	20
2019	7,299	5,416	272	2,154	42	2,021	40	1,029	20
2020	7,454	5,432	272	2,293	44	2,159	43	1,032	20
2021	7,454	5,426	272	2,300	45	2,153	43	1,031	20

Forecast Reserve (%) = [Forecast Capacity - (Peak Load - Inter. Load)]*100%(Peak Load - Inter. Load)

Minimum Reserve (%) = $\underline{\text{Min. of Hourly [Capacity - (Load - Inter. Load)]}}*100\%$ (Load - Inter. Load)

3.2 LOLE results – High Load Growth

Table 6 and Figure 4 illustrate LOLE results if the average annual growth rate is 1% higher than forecast (i.e. 1.16% per year versus 0.16% per year compounded over the 4 year period of this review). The results show that the NPCC resource adequacy criterion is met in all years.

Table 6:	Loads and LOLE Results – High Load Growth

Month Of January	High Load Growth Load	Base Case Load	Difference	High Load Growth LOLE	Base Case LOLE
	MW	MW	MW	days/year	days/year
2017	5,392	5,392	0	0.003	0.003
2018	5,454	5,406	48	0.003	0.003
2019	5,517	5,416	101	0.006	0.003
2020	5,581	5,432	149	0.010	0.003
2021	5,645	5,426	220	0.019	0.004

3.3 LOLE Results – Zero Wind

The Maritimes Area did not assign a fixed capacity credit to wind generation. Instead, simulated hourly wind capacity values were netted against corresponding hourly load values. Because there were no wind generation additions beyond 2017 and because the peak load day for the five years did not vary during the 2017 to 2021 period of this review, simulated wind capacity during peak demand was constant at 496 MW compared to an installed total of 974 MW. A sensitivity analysis was performed with the wind capacity on the system set to zero output for all hours. Table 7 and Figure 4 illustrate LOLE results for the zero wind generation scenarios. The results show that Maritimes Area is not reliant on wind capacity to meet the NPCC resource adequacy criterion.

Table 7: Capacity and LOLE Results – Zero Wind

Month Of January	Zero Wind Capacity	Base Case Capacity	Difference	Zero Wind Capacity LOLE	Base Case LOLE
	$\mathbf{M}\mathbf{W}$	MW	$\mathbf{M}\mathbf{W}$	days/year	days/year
2017	6,711	7,207	-496	0.017	0.003
2018	6,922	7,418	-496	0.012	0.003
2019	6,803	7,299	-496	0.016	0.003
2020	6,958	7,454	-496	0.019	0.003
2021	6,958	7,454	-496	0.026	0.004

3.4 LOLE Results – No Tie Benefits

Since 2011, NBSO has assumed 300 MW of tie benefits to New Brunswick in its resource adequacy assessments. These tie benefits are based on a 2011 decision by the New Brunswick Market Advisory Committee to recognize the lowest historical Firm Transmission Capacity

posted from summer peaking New England to winter peaking New Brunswick since the commissioning of the second 345 kV tie between these systems in December 2007. To the extent that future capacity purchases from New England to New Brunswick occur across this interface, these tie benefits will be reduced accordingly. Tie benefits from other neighbouring jurisdictions were not considered by the New Brunswick Market Advisory Committee because they also experience peak loads in winter.

In the CP-8 report *Review of Interconnection Assistance Reliability Benefits (December 31, 2015, Approved by RCC March 2, 2016)* the "As Is" estimated tie benefit potential for the Maritimes Area is 702 MW and 1012 MW for the years 2016 and 2020 with an export of 200 MW modeled in both test years. Based on this study, the 300 MW of tie benefits assumed for this 2016 Comprehensive Review is conservative. A sensitivity analysis performed for this review shows that the Area does not require interconnection assistance to meet the NPCC resource adequacy criterion. The results are shown in Table 8 and Figure 4.

Table 8: Capacity and LOLE Results – No Tie Benefits

Month Of January	No Tie Benefits Capacity MW	Base Case Capacity MW	Difference	No Tie Benefits LOLE	Base Case LOLE days/year
2017	6,907	7,207	-300	0.005	0.003
2018	7,118	7,418	-300	0.003	0.003
2019	6,999	7,299	-300	0.004	0.003
2020	7,154	7,454	-300	0.004	0.003
2021	7,154	7,454	-300	0.005	0.004




Figure 4: LOLE Results – All Base and Sensitivity Cases

3.5 Contingency Plans

The Maritimes Area utilities' forecast high and low load growth scenarios, and their impact on the generation dispatch is continually being evaluated to address load and resource uncertainties. In the event of a higher than expected growth in load, a number of options would be considered. These options include the purchases of capacity and/or energy, the advancement of base load generation additions, and the installation of combustion turbines.

4.0 FORECAST RESOURCE CAPACITY MIX

4.1 Forecast Resource Capacity Mix

Table 9 and Figure 5 illustrate the forecast resource capacity mix for the Maritimes Area. Appendix A, Section 1.2, Table A-2 presents a detailed list of all capacity resources for the Maritimes Area.

Month of	Oil	Coal	Hydro	Nuclear	Gas	Wind*	Gas/Oil	Tie Benefits	Biomass
January	%	%	%	%	%	%	%	%	%
2017	25	23	18	9	7	7	4	4	2
2018	25	23	17	9	7	7	4	4	3
2019	25	23	17	9	7	7	4	4	3
2020	25	23	18	9	7	7	4	4	3
2021	25	21	20	9	7	7	4	4	3

Table 9: Forecast Capacity Resource Mix

^{*} Wind capacity based on 496 MW of wind capacity (out of 974 MW installed) during coincident peak




Figure 5: Forecast Capacity Resource mix

4.2 Reliability Impact of Resource Diversification Strategy

As can be seen from Table 9 and the associated Figure 5, the Maritimes Area has a diversified mix of resources such that there is not a high degree of reliance upon any one type or source of fuel. This resource diversification also provides flexibility to respond to any future environmental issues, such as potential restrictions to greenhouse gas emissions. The Renewable Energy Standard in Nova Scotia calls for 25% of energy sales

to be supplied from renewable resources in 2016 and increases to 40% in 2020. The increase in renewable requirements in 2020 will largely be met by the import of hydro energy from Newfoundland and Labrador and will result in reduced fossil fuel generation.

2016 Maritimes Area Comprehensive Review of Resource Adequac	Page 20 of
APPENDIX A - DESCRIPTION OF RESOURCE RELIABI	ILITY MODEL

DESCRIPTION OF RESOURCE RELIABILITY MODEL

1.0 Load Model

1.1 Fiscal year 2011/12 hourly system load data for the Maritimes Area utilities was used as the load shape for this study. Demand and energy forecasts for 2017 to 2021 inclusive were prepared by each resource planner. The combined load and energy forecasts for the Maritimes Area are shown in Table A-1.

Table A-1: Maritimes Area Load Forecast

	COINCIDENT DEMAND MW												
Year	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Peak
2017	5392	5181	4821	3946	3463	3222	3228	3145	3217	3672	4412	4894	5392
2018	5406	5193	4845	3952	3471	3228	3248	3170	3235	3689	4432	4924	5406
2019	5416	5200	4863	3981	3517	3275	3266	3183	3257	3707	4456	4947	5416
2020	5432	5214	4879	3989	3517	3271	3262	3188	3254	3702	4457	4956	5432
2021	5426	5220	4883	3974	3517	3269	3270	3190	3259	3703	4452	4961	5426
						ENE	RGY						
	GWh												
Year	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
2017	3018	2719	2702	2251	2029	1859	1935	1950	1874	2085	2359	2843	27622
2018	3042	2738	2728	2279	2058	1882	1955	1969	1894	2105	2381	2866	27897
2019	3067	2762	2742	2294	2077	1900	1961	1971	1898	2111	2390	2874	28047
2020	3077	2774	2756	2306	2081	1905	1964	1978	1902	2115	2396	2884	28138
2021	3078	2775	2758	2300	2081	1906	1965	1979	1903	2118	2393	2882	28138
]	INTERI	RUPTII	BLE DE	EMAND)				
						M	W						
Year	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	On
1 Cai			iviai	Арг	iviay						1407		Peak
2017	268	258	343	342	324	352	366	360	365	344	346	266	268
2018	272	262	348	347	329	352	366	360	365	345	346	267	272
2019	272	263	348	348	329	353	366	360	365	345	346	267	272
2020	272	263	348	347	329	352	366	360	365	345	346	267	272
2021	272	263	348	347	328	352	366	360	365	344	346	267	272

Note: The forecast coincident peak demand occurs in January.

- 1.2 Load forecast uncertainty (LFU) was considered in the analysis as described in Section 2.6 of the main report.
- 1.3 Some entities within the Maritimes Area supply a portion of their own electricity demand and energy requirements. Only the portions that are supplied by the Maritimes Area utilities were included in the area forecast.
- 1.4 The load forecast in Table A-1 includes the impact of DSM and efficiency programs.

2.0 Generator Resource Representation

Generator data for the four members of the Maritimes Area are presented in Table A-2. Table A-3 presents a summary of changes in resource data for the period 2017–2021 inclusive. The following sections document the tabulated data.

2.1 Generator Ratings

2.1.1 Definition

The generator capacity ratings represented in Table A-2 are the Dependable Maximum Net Capability (DMNC) winter ratings. These are evaluated periodically to establish each generator's sustained maximum net output over a two consecutive hour period.

2.1.2 Procedure for Verifying Ratings

Ratings of NB Power generators are tested annually, reaching a minimum of 95% of their declared capabilities for at least 1 full hour. This conforms to NPCC unit testing standard Directory #9 Verification of Generator Gross and Net Real Power Capability. Nova Scotia Power, Inc. (NSPI) reviews generator capability ratings at three year intervals and assumes successful verification at a minimum 98% of the declared value for at least one consecutive hour. This also conforms to the requirements outlined in NPCC Directory #9.

Table A-2: Maritimes Area Resources

		New Bru	nswick Reso	ources
Plant	Unit	Туре	Capacity MW	Notes
Point Lepreau	1	Nuclear	660	
		Diesel	5	
Belledune	2	Coal	466	
Coleson Cove	1	Oil	324	
	2	Oil	324	
	3	Oil	324	
Bayside	6	Natural Gas	290	Capacity (Combined Cycle Operation)
Grand Manan	3	Diesel	28	
Millbank	1	Diesel	99	Summer Capacity = 90 MW
	2	Diesel	99	Summer Capacity = 90 MW
	3	Diesel	99	Summer Capacity = 90 MW
	4	Diesel	99	Summer Capacity = 90 MW
Ste Rose	1	Diesel	99	Summer Capacity = 90 MW
Grandview	1	Natural Gas	49	Summer Capacity = 43 MW
	2	Natural Gas	49	Summer Capacity = 43 MW
NUG Purchases		Biomass	38	1 3
		Hydro	15	
Mactaquac	1	Hydro	109	
•	2	Hydro	109	
	3	Hydro	109	
	4	Hydro	115	
	5	Hydro	112	
	6	Hydro	112	
Beechwood	1	Hydro	36	
	2	Hydro	36	
	3	Hydro	41	
Grand Falls	1	Hydro	16	
	2	Hydro	16	
	3	Hydro	16	
	4	Hydro	16	
Tobique	1	Hydro	10	
1	2	Hydro	10	
Nepisiguit Falls	1	Hydro	11	
Sisson	1	Hydro	9	
Milltown	1	Hydro	4	
Purchases/Sales (+/-)	-	,	-200	Firm Sale for January 2017
Tie Benefits			300	
NB Wind	All	Wind	120	Expected during peak (294 MW installed)
TOTAL CAPACITY		,,,,,,,,	4174	Total Capacity as of January 2017

Table A-2: Maritimes Area Resources (cont'd)

Nova Scotia Resources							
Plant	Unit	Туре	Capacity MW	Notes			
Lingan	1	Coal	153				
	2	Coal	153	Assumed retirement mid-2020			
	3	Coal	153				
	4	Coal	153				
Trenton	5	Coal	150	Summer Capacity = 135 MW			
	6	Coal	157				
Pt. Tupper	2	Coal	152				
Tufts Cove	1	Gas/Oil	81				
	2	Gas/Oil	93				
	3	Gas/Oil	147				
	4	Natural Gas	49	Summer Capacity = 47 MW			
	5	Natural Gas	49	Summer capacity = 47 MW			
	6	Natural Gas	49				
Pt. Aconi	1	Coal	171				
Burnside	1	Lt Oil	33	Summer Capacity = 25 MW			
	2	Lt Oil	33	Summer Capacity = 25 MW			
	3	Lt Oil	33	Summer Capacity = 25 MW			
	4	Lt Oil	33	Summer Capacity = 25 MW			
Victoria Junction	1	Lt. Oil	33	Summer Capacity = 25 MW			
v recerra e arrector	2	Lt. Oil	33	Summer Capacity = 25 MW			
Tusket	1	Lt. Oil	24	Summer Capacity = 21 MW			
NUG Purchases	All	Biomass/hydro	27.8	Summer Supurity 21 112 W			
PH Biomass	7 111	Biomass	0	Energy only during 2017			
COMFIT Biomass	All	Biomass	25	Energy only during 2017			
Wreck Cove	1	Hydro	105				
Wieck Cove	2	Hydro	105				
Annapolis	_	Hydro	4				
Avon		Hydro	7				
Black River		Hydro	23				
Nictuax		Hydro	8				
Lequille		Hydro	13				
Paradise		Hydro	5				
Mersey		Hydro	43				
Sissiboo		Hydro	27				
Bear River		Hydro	11				
Tusket		Hydro	2				
St. Margarets		Hydro	11				
Sheet Harbour		Hydro	11				
Dickie Brook		Hydro	2				
Fall River		Hydro	1				
Other small hydro	All	Hydro	0.7				
NALCOR Firm Contract	All	Hydro	0.7	Expected mid-2020			
NALCOK FITH COMTACT		пушо		Expected mid-2020 Expected during peak (434 MW installed			
NS Wind	All	Wind	238	excluding 164 MW of energy only resources)			
TOTAL CAPACITY			2601.5	Total Capacity as of January 2017			

Table A-2 Maritimes Area Resources (cont'd)

	Prince Edward Island Resources								
Plant	Unit	Type	Capacity MW	Notes					
Charlottetown	7	Oil	7						
	8	Oil	10						
	9	Oil	19						
	10	Oil	19						
	11	Diesel	49						
Borden	1	Diesel	15	Summer Capacity = 12 MW					
	2	Diesel	25	Summer Capacity = 20 MW					
Summerside	1	Diesel	2	Owned by the City of Summerside					
	2	Diesel	2						
	3	Diesel	2						
	5	Diesel	2						
	6	Diesel	1						
	7	Diesel	1						
	8	Diesel	4						
PEI Wind	All	Wind	103	Expected during peak (204 MW installed)					
TOTAL CAPACITY			261	Total Capacity as of January 2014					

Table A-2 Maritimes Area Resources (cont'd)

Northern Maine Resources							
Plant	Unit	Type	Capacity	Notes			
			$\mathbf{M}\mathbf{W}$				
Tinker	1-5	Hydro	35				
		Diesel	1				
Fort Fairfield		Wood	33				
Ashland		Wood	37				
Caribou		Hydro	1				
		Diesel	7				
Squa Pan		Hydro	1				
_		Black					
EMEC		Liquor/	20				
EMIEC		Biomass/	20				
		Natural Gas					
NMISA Wind	All	Wind	35	Expected during peak (42 MW installed)			
TOTAL CAPACITY			170	Total Capacity as of January 2014			

Table A-3: Summary of Changes in Modeled Capacity

Year	Capacity in January MW	Capacity in December MW	January to January Capacity Change MW	January to December Capacity Change MW	Explanation -Total Capacities include tie benefits (MW) and the impact of firm purchases and/or sales and planned maintenance
2017	7,207	7,407	0	+200	Removal of 200 MW sale after January,
2018	7,418	7,340	+211	-78	For January; -36 MW removal of generator for maintenance until April, +45 MW of formerly transmission constrained biomass capacity, and +2 MW of biomass capacity. For December; +36 MW for return of unit under maintenance in April, -114 MW sale in December
2019	7,299	7,454	-119	-155	For January; -41 MW removal of generator for maintenance until April. For December; +114 MW removal of sale after January +41 MW for return of unit under maintenance in April
2020	7,454	7,454	+155	0	-153 MW of coal capacity in mid- 2020 offset by +153 MW of hydro based capacity purchases
2021	7,454	7,454	0	0	No changes

2.2 Generator Unavailability Factors

2.2.1 Types of Unavailability Factors Represented

The types of unavailability factors represented in this reliability assessment are forced outages and planned outages. Forced outages include unplanned maintenance outages, deferrable forced outages, starting failure outages and generator derating adjustments. All except planned outages are included in the Forced Outage Rates (FORs) presented in Table A-4. Planned outages are scheduled manually for the reliability program based upon projected maintenance schedules.

New Brunswick forced outage rates are three year calculations using the Derating Adjusted Forced Outage Rate (DAFOR) methodology in IEEE Standard 762-2006, Section 8.17.4.

NSPI also uses three year average DAFOR calculations for forced outage rates consistent with IEEE Standard 762-2006, Section 8.17.4. NSPI maintains a database of combustion turbine and fossil generator reliability and performance data and is a contributing utility to the Canadian Electricity Association Equipment Reliability Information System (CEA-ERIS). The CEA-ERIS also calculates DAFOR using the industry standard definition as per IEEE 762-2006.

The forced outage rates for the smaller PEI and Northern Maine systems are modeled using forced outage rates for generators of similar size and fuel type in New Brunswick and Nova Scotia. Most of the small diesel and oil fuelled generators in these systems operate less than 100 hours per year, and statistics necessary for calculating their DAFOR values are not available. The modeled FOR values for generators in these systems are between $5-10\,\%$.

2.2.2 Source of Unavailability Factors

Forced Outage Rates for existing generators are based on actual outage data as well as on data of similar sized generators as compiled by the Canadian Electricity Association (CEA).

FORs for new generators are based upon the utilities' experience with similar generators in conjunction with averages compiled by the Canadian Electricity Association (CEA).

2.2.3 Maturity Considerations

Immature FORs were not used in this evaluation.

2.2.4 Tabulation of Forced Outage Rates

The ranges of FORs used in the assessment are tabulated in Table A-4. These values are consistent with those used in the business plans of the Maritimes Area utilities and reflect the results of maintenance and operational strategies.

Forced Outage Rate (%) Unit Type 2016 Review 2013 Review Oil 0 - 101 - 10Coal 1 - 10*2 - 16*Hydro 0 - 5 1 - 11**Nuclear 7 6 Natural Gas 0 - 71 - 7Wind 0 0 6 - 8Oil/Gas 6 - 9 Biomass 2 - 8 1 - 8

Table A-4: Maritimes Area Forced Outage Rates

2.3 Purchase and Sale Representation

Purchases and sales are represented as an adjustment to the capacity or load as appropriate.

2.4 Retirements

Retirements were considered by removing the generators from the model at their retirement date. The only known retirement assumed during the 2017 to 2021 period of this review is the mid-2020 retirement of the Lingan 2 unit in Nova Scotia. Reliability impacts will be negligible as the retirement is to be simultaneously offset by a similar sized hydro based firm capacity purchase.

3.0 Representation of Interconnected Systems

Since 2011, NB Power has assumed 300 MW of tie benefits to New Brunswick in its resource adequacy assessments. These tie benefits are based on a 2011 decision by the New Brunswick Market Advisory Committee to recognize the lowest historical Firm Transmission Capacity posted from summer peaking New England to winter peaking New Brunswick since the commissioning of the second 345 kV tie between these systems in December 2007. To the extent that future capacity purchases from New England to New Brunswick occur across this interface, these tie benefits will be reduced accordingly. Tie benefits from other neighbouring jurisdictions that are also winter peaking are not considered.

In the CP-8 report Review of Interconnection Assistance Reliability Benefits (December 31, 2015, Approved by RCC March 2, 2016) the "As Is" estimated tie

^{*} A single coal unit dropped from 16 % to 10 % during the period 2013 to 2016. The remaining coal units were less than 4% for the 2016 review and 7% for the 2013 review.

^{**} One hydro plant had a forced outage rate as high as 11%. Its power house was flooded during an extreme weather event in 2011. All other hydro generators had forced outage rates of 1%.

benefit potential for the Maritimes Area is 702 MW to 1012 MW for the years 2016 and 2020 with an export of 200 MW modeled in both test years. Based on this study, the 300 MW of tie benefits assumed for this 2016 Comprehensive Review is conservative.

4.0 Modeling of Variable and Limited Energy Sources

Wind resources are modeled as simulated hourly values that are netted out against the hourly loads. The hourly wind shapes are based upon historical hourly wind generation values for the 2011-2012 fiscal year. New wind capacity forecast for a Maritimes Area jurisdiction is modeled by scaling the historical wind generation in that jurisdiction.

Under normal operating conditions, the hydro system is operated considerably below its DMNC rating due to economics. However, if required to maintain customer load, it would be operating at full capacity by utilizing the headponds and other existing storage reservoirs. This is one of the options documented in the Emergency Operating Procedures (Section 2.2 of the main report). Therefore, in the evaluation, hydro generators are considered available for all hours during which the generator is not on forced outage or maintenance. There are no seasonal adjustments to the DMNC ratings of the hydro generators.

5.0 Modeling of Demand Side Management

The expected monthly demand and energy reduction due to Demand Side Management programs for each sub-area is included in their respective forecasts and in the combined Maritimes Area forecast in Table A-1.

6.0 Modeling of Non-Utility Generation

Certain small non-utility generators are aggregated into single units with operating characteristics and FORs equivalent to other Maritimes Area generators of similar size. These are tabulated in Table A-2 and are identified by type NUG. In addition to these NUG units, a Nova Scotia's Community Fit (COMFIT) program generators are also non-utility generators. Some larger non-utility generators, such as Bayside 6, are shown separately because their size is comparable to the larger utility generators on the system.

7.0 Other Assumptions

The study assumed that there would be no generator slippages or deratings due to environmental constraints within the five-year timeframe of this review. Current emission limits are specified as annual system volumes rather than generator specific volumes, providing flexibility in the operation of the fleet.

Future regulations limiting greenhouse gas emissions and air pollutants are in place for the 2020-2030 timeframe in Nova Scotia. These regulations specify multi-year hard caps rather than annual limits which provide for some flexibility in the operation of the fleet over the specified compliance periods. System Operators in the Maritimes Area will be tracking such standards as they are implemented and may conduct analyses in the future regarding their impact on resource adequacy.

2016 Maritimes Area Comprehensive Review of Resource Adequacy

APPENDIX B - DESCRIPTION OF RELIABILITY PROGRAM

DESCRIPTION OF RELIABILITY PROGRAM

The program used for this assessment, LOLP, was originally developed at NB Power in 1984 to complete the Triennial Review of Resource Adequacy. Since that time the program has been improved, and its capabilities expanded, with the most recent modifications being completed during summer 2016.

The original program was a single area program that performed the classical LOLP analysis based upon the weekday peak hour load, as well as an LOLH and EENS analysis which is based upon all of the hourly loads. The results of the program were benchmarked against the results of the IEEE reliability test system, as well as against the results of the PICES program used by NSPI for the 1991 Triennial Review. The program was further benchmarked by evaluating its results against those documented in the 1992 CIGRE Task Force 38-03-10 report "Composite Power System Reliability Analysis Application to the New Brunswick Power Corporation System". In all cases, excellent agreement of results was observed.

In the fall of 2007, modifications to the original program allowed it to perform a Monte Carlo analysis of a multi-area system with intra-area tie limits. This Monte Carlo simulation was written using MATLAB® software for programming and random number generation, and it performs as follows:

- For each daily coincident peak load, generation is simulated in each jurisdiction of the Maritimes. In the case of wind generation, hourly wind generation generation projections for the time of the Area coincident peak are netted against the loads. This simulation uses random numbers against a generator's Forced Outage Rate to determine the status of each generator. Planned generator maintenance is also enforced.
- Generation surpluses or deficits are determined for each intra-area jurisdiction. Because each jurisdiction other than New Brunswick (NB) is only connected to NB, these surpluses and deficits can be transferred to New Brunswick.
- Surpluses transferred to NB from another intra-area jurisdiction are limited by the export limit of the jurisdiction.
- Deficits in an intra-area jurisdiction other than NB that exceed the import capability from NB results in a loss of load event. Otherwise, the deficit is transferred to NB.
- With all transfer-limited intra-area surpluses and deficits transferred to NB, it is
 determined whether or not the simulated generation in NB plus transferred
 surpluses is adequate to supply both the NB load and any transferred deficits. If
 not, then a loss of load event occurs.
- The Monte Carlo simulation is performed for each daily peak hour of the year, and the yearly simulation is repeated 100,000 times to calculate the average LOLE in days/year.

The base load shape for the program is system hourly net loads for each jurisdiction comprising the Area. Monthly load shapes for the individual jurisdictions are created by scaling the hourly loads to match the load forecast values of both demand and energy.

This method preserves the effects of load chronology as well as load coincidence between the jurisdictions. This method is also identical between the new program and the old program. A separate monthly load shape comprising only the peak load of each day is created for the LOLE analysis.

2017 Reliability Improvements

August 4, 2017

A Report to the Board of Commissioners of Public Utilities



Table of Contents

Introduction	. 3
Scope of Studies	. 3
Transmission Planning Criteria	. 4
Stage I - Addition of the Maritime Link	. 6
Stage II - Addition of Soldiers Pond Synchronous Condensers	. 6
Stage III - Addition of Labrador-Island Link and Labrador Transmission Asset	. 7
Stage IV - Addition of Muskrat Falls Generation	. 7
Conclusion	ç

Introduction

- 2 Newfoundland and Labrador Hydro (Hydro) and TransGrid Solutions (TGS) are undertaking
- 3 operational studies in preparation for the interconnection of assets into the Newfoundland and
- 4 Labrador Transmission System. The objective of the studies is to identify system impacts and
- 5 operating limits to allow for the development of Operating Instructions to be used by operators
- 6 in Hydro's Energy Control Centre (ECC).

7

1

- 8 Steady state and dynamic analyses are to be performed to assess contingencies within the
- 9 provincial transmission system. The results of the studies are to be analysed to ensure that
- steady state and dynamic responses met the system performance requirements in accordance
- with Transmission Planning Criteria. Where criteria violations are discovered, system operating
- 12 limits and/or mitigations are to be determined to avoid violations.
- 13 Operational studies have been staged to match the anticipated in service date of new assets
- 14 and are summarized as follows: 1
- 15 STAGE I Addition of the Maritime Link;
- 16 STAGE II Addition of the Soldiers Pond Synchronous Condensers;
- 17 STAGE III Addition of the Labrador-Island Link and Labrador Transmission Asset; and
- 18 STAGE IV Addition of Muskrat Falls Generation.

19

20

- All studies shall be performed using Version 32 of PSS ®E software from Siemens PTI. The
- 21 studies are summarized in the sections below.

22

23

26

Scope of Studies

- 24 For the purposes of this investigation, operational reviews shall be limited to the definition of
- 25 system operating limits and assessment of contingencies in high voltage systems including:
 - 230 kV transmission system on the Island of Newfoundland;

¹ Hydro has also performed internal analyses in preparation for other ac system additions including TL269 from Bottom Brook Terminal Station to Granite Canal Terminal Station. This line is to be placed in service in advance of the Maritime Link and operating instructions have been developed. Power flows in this transmission line corridor are not significant in advance of Maritime Link operation and the detailed specification of System Operating Limits will be included as part of the Stage I study.

- 138 kV transmission system from Deer Lake to Stony Brook;²
- Labrador-Island HVdc Link;
 - Maritime HVdc Link; and
- 315 kV and 735 kV systems in Labrador.

5

6

3

Transmission Planning Criteria

- 7 The following Transmission Planning Criteria are to be applied in the analysis:
- 8 Steady State Analysis Criteria:
- With a transmission element (line, transformer, synchronous condenser, shunt or series
 compensation device) is out of service, power flow in all other elements of the power
 system should be at or below normal rating;
 - For normal operations all voltages be maintained between 95% and 105%;
- For contingency or emergency situations all voltages be maintained between 90% and 110%; and
 - Analysis will be conducted with one high inertia synchronous condenser out of service at Soldiers Pond (for studies where the units are included).

17

19

21

15

16

- 18 Transient Analysis Criteria:
 - System response shall be stable and well damped following a disturbance
- System disturbances include:
 - Successful single pole reclosing on line to ground faults;
- 22 o Unsuccessful single pole reclosing on line to ground faults;
- o Three phase faults;³
- o Loss of the largest generator on line on the Island System with and without fault;
- o Line to ground or three phase fault with tripping of a synchronous condenser;
- o Fault and tripping of a transmission line;

² Other 138 kV loops including the Western Avalon-Holyrood Loop and the Stony Brook-Sunnyside Loop serve primarily to serve network load and were not considered as part of the operational reviews.

³ System responses following a three-phase fault at Bay d'Espoir coinciding with high power flows over the Labrador Island Link and peak loading conditions will be re-examined in Stage IV.

 Temporary pole fault; 1 2 Permanent pole fault; and 3 Temporary bipole fault; 4 Post fault recovery voltages on the ac system shall be as follows: 5 Transient under voltages following fault clearing should not drop below 70%; The duration of the voltage below 80% following fault clearing should not exceed 6 7 20 cycles; and There shall be no commutation failures of the Labrador-Island Link during post fault 8 recovery;4 9 10 Low Power Operation (Pre-Muskrat Falls Generation); Post fault system frequencies shall not drop below 58 Hz and shall not rise above 11 12 62 Hz; 13 o Controlled underfrequency load shedding shall be permitted for loss of 14 generation or loss of a pole/bipole; 15 The existing underfrequency load shedding scheme shall remain unchanged; and High Power Operation (Includes Muskrat Falls Generation); 16 17 Post fault system frequencies shall not drop below 59 Hz; 18 Underfrequency load shedding: shall not occur for loss of on-island generation with the HVdc link in 19 20 service; 21 shall not occur for permanent loss of HVdc pole; 22 shall not occur for a temporary bipole outage; and 23 shall be controlled for a permanent bipole outage.

⁴ For low power operation, consideration will be given to the operation of the Labrador-Island Link in conditions with reduced short circuit levels (i.e., without Muskrat Falls Generation). Analysis will be performed to identify and assess any conditions that may cause the link to trip or experience commutation failures. System operating limits will be defined accordingly.

1 Stage I - Addition of the Maritime Link

- 2 Study Start Date February 20, 2017
- 3 Expected Completion Date September 30, 2017
- 4 Maritime Link In-Service Date Q4, 2017

5

- 6 This study shall assess the addition of the Maritime Link and its impacts on the Island
- 7 Interconnected Transmission System and shall include the following considerations:
- Identification of Maritime Link import and export limits;
- Identification of transfer limits in transmission corridors for n-0 and n-1 operating
- 10 conditions;
- Impacts of the Maritime Link frequency controller; and
- Review of underfrequency load shedding with the existing scheme in place.

13

14 Stage II - Addition of Soldiers Pond Synchronous Condensers

- 15 Study Start Date July 17, 2017
- 16 Expected Completion Date October 31, 2017
- 17 Soldiers Pond Synchronous Condensers In-Service Date Q2, 2018

18

22

- 19 This study shall assess the addition of the Soldiers Pond synchronous condensers and relevant
- 20 impacts on the Island Interconnected Transmission System and shall include the following
- 21 considerations:
 - Update of Maritime Link import and export limits;
- Update of transfer limits in transmission corridors for n-0 and n-1 operating conditions;
- 24 and
- Review of underfrequency load shedding with the existing scheme in place.

1 Stage III - Addition of Labrador-Island Link and Labrador Transmission Asset

- 2 Study Start Date July 3, 2017
- 3 Expected Completion Date December 31, 2017
- 4 Labrador-Island Link In-Service Date Q2, 2018

5

- 6 This study shall assess the addition of the Labrador-Island Link and Labrador Transmission
- 7 Asset⁵ and relevant impacts on the Newfoundland and Labrador Transmission System. The
- 8 study shall assess low power operation of the HVdc link (i.e., without Muskrat Falls generation)
- 9 and shall include the following considerations:
- Identification of Labrador-Island Link import and export limits in monopole and bipole
 modes of operation;
- Update of Maritime Link import and export limits;
- Identification of transfer limits in Labrador transmission corridors for n-0 and n-1
 operating conditions;
- Update of transfer limits in Newfoundland transmission corridors for n-0 and n-1
 operating conditions;
 - Review of underfrequency load shedding with the existing scheme in place;
 - Impacts of the Labrador-Island Link frequency controller and coordination with the
 Maritime Link frequency controller;

20

21

17

18

19

Stage IV - Addition of Muskrat Falls Generation

- 22 Study Start Date January 1, 2018
- 23 Expected Completion Date September 30, 2018
- 24 Muskrat Falls Generation In-Service Date Q3 2019-Q2 2020

⁵ Hydro has also performed internal analyses in preparation for the energization of the Labrador Transmission Asset for the commissioning of the 315 kV terminal station at Muskrat Falls. Power flows in this transmission line corridor are not significant in advance of Labrador-Island Link operation and the detailed specification of System Operating Limits will be included as part of the Stage III study.

- 1 This study shall assess the addition of the Muskrat Falls Generation and operation of HVdc links
- 2 up to rated capacities. The investigation of impacts on the Newfoundland and Labrador
- 3 Transmission System shall include the following considerations:
 - Update of Labrador-Island Link import and export limits;
- Update of Maritime Link import and export limits;
- Update of transfer limits in Labrador transmission corridors for n-0 and n-1 operating
 conditions;
- Update of transfer limits in Newfoundland transmission corridors for n-0 and n-1
 operating conditions;
- Development of a new underfrequency load shedding scheme;
- Review of Power System Stabilizer applications for generators and HVdc links for
 improved system damping;
- Update to coordination of the Labrador-Island Link frequency controller and the
 Maritime Link frequency controller;
 - Review of coordinated runbacks of HVdc links and operating restrictions with links out of service;
- Consideration of re-strikes on the Labrador Island HVdc Link;
 - Review of power requirements for high power transfer on the Labrador-Island Link and evaluation of dynamic reactive additions at Soldiers Pond and Holyrood; and
 - Review of Bay d'Espoir instabilities under a three-phase fault condition.

22 **Conclusion**

4

15

16

18

19

20

- 23 Work is underway with respect to operational studies associated with the Integration of assets
- into the Newfoundland and Labrador transmission system. With the support of TGS, Hydro has
- 25 established a plan for the completion of operational studies sufficiently in advance of
- equipment in-service dates. Analysis associated with the integration of the Maritime Link is
- 27 nearing completion and studies relating to the integration of Soldiers Pond synchronous
- 28 condensers, the Labrador Transmission Asset, and the Labrador-Island Link are on pace for on
- 29 time completion.

- 1 The plan, as specified above, has been communicated to Newfoundland Power by Hydro as
- 2 part of the mandate of the Inter-Utility Integration Subcommittee, which was established in
- 3 2016. Hydro is committed to working with Newfoundland Power and all of its customers to
- 4 ensure safe and reliable operation through the stages of asset integration and beyond. This
- 5 cooperation is critical, particularly in consideration of aspects such as the modification of
- 6 underfrequency load schemes in advance of high power operation.

- 8 Hydro is committed to providing the Newfoundland and Labrador Board of Commissioners of
- 9 Public Utilities with updates pertaining to operational studies and submitting all completed
- 10 reports upon receipt. It is Hydro's objective that all outcomes the operational studies be
- incorporated to ensure the safe and reliable operation of the transmission system.

	% Com	plete			Baselin	e Dates	Actual/	orecast			
					2436111		بر. بر				
	GREEN				Ę	0	ecas (Q)	Forecast e (Q)	_	vice	_
Se	GR	~			Stari	En	ore te (Fore ie (Q	at the second se	_ <u></u>	N people/
rice Tice	<u> </u>	cted	722	4	g in	ine (Q)	II/F Dat	al/F Date		(2) Se	β process/
los	Actual UPDATE %'s	bec	WBS I	$oldsymbol{B}$	3aseline Date (Q)	sel	tua			CP In	te system/
Re	\	ŭ		<u> </u>	B B	Ba	St. Ac	Actu End	: ပ်	2 6	은 delivery
	38.0%	44.2%	RFI SCOPE		• • • •			22.42			
DELMan	30.8% 26.7%	30.8%		nce & Oversight	Q4 16	Q4 18	Q2 16	Q3 19			
RFI Mgr RFI Studies Lead		26.7% 39.4%		er @ 25% (Mtgs, Reporting, Interfaces, Dependencies, Risks) 9 40% (Mtgs, Misc Study Reviews/Inputs/ Updates)	Q1 17 Q4 16	Q4 18 Q3 18	Q1 17 Q4 16	Q4 18 Q3 19			
RFI Admin		20.3%		Support @25% (Admin, Interface Management)	Q4 10 Q1 17	Q3 18 Q4 18	Q4 10 Q1 17	Q3 13 Q4 18			
iii i / taiiiii	20.370	20.570	/ tallilli	Support @25% (Namm, interruce Management)	QI I7	Q110	QI II	Q110			
	74.1%	77.6%	RFI SYSTEM	1 STUDIES - FIRST POWER PREPARDNESS							
	91.8%	98.5%	GE Grid (A	Alstom) Studies Support & Review	Q1 15	Q4 17	Q1 15	Q3 17 P	Q3 18 LIL In Service Minus 3 mths	Q3 18	181 Delivery
RFI Studies Lead	100.0%	100.0%	Commo	on - Main Scheme Parameter Design Report	Q3 15	Q3 15	Q3 15	Q3 15			
RFI Studies Lead	100.0%	100.0%		on - Circuit Current Requirement - Report	Q3 15	Q3 15	Q3 15	Q3 15			
RFI Studies Lead		100.0%		on - Basic Insulation Coordination - Design Report	Q4 15	Q4 15	Q4 15	Q4 15			
RFI Studies Lead		100.0%		on - DC Filter Transient Overvoltage Study	Q3 16	Q4 16	Q3 16	Q3 17			
RFI Studies Lead				on - Converter Station Radiated interference - Design Report	Q1 16	Q1 16	Q1 16	Q1 16			
RFI Studies Lead				on - Reactive Power Management Design Report	Q3 15	Q3 15	Q3 15	Q3 15			
RFI Studies Lead RFI Studies Lead		100.0%		on - Equivalent AC Network Derivation - Outline Report on - Equivalent AC Network Derivation Report	Q3 15 Q2 16	Q4 15 Q2 16	Q3 15 Q2 16	Q4 15 Q2 16			
RFI Studies Lead				on - Harmonic Impedence Study - Report	Q2 10 Q1 15	Q2 10 Q1 15	Q2 10 Q1 15	Q2 10 Q1 15			
RFI Studies Lead		100.0%		on - Transient Stability, Dynamic Multi Interaction, GSE and FFTOV - Outline Report	Q1 15 Q1 15	Q2 15	Q1 15 Q1 15	Q2 15			
RFI Studies Lead				on - Reactive Power Capacity - Study Report	Q1 15	Q2 15	Q1 15	Q2 15			
RFI Studies Lead				on - PSCAD™ Dynamic Performance Outline Report	Q2 15	Q2 15	Q2 15	Q2 15			
RFI Studies Lead	100.0%	100.0%		on - Subsynchronous Oscillation - Outline Report	Q2 15	Q2 15	Q2 15	Q2 15			
RFI Studies Lead	100.0%	100.0%	Commo	on - Sub-Synchronous Oscillation Study Report	Q3 15	Q3 15	Q3 15	Q3 15			
RFI Studies Lead		100.0%	Commo	on - System Studies Summary Report	Q2 15	Q2 15	Q2 15	Q2 15			
RFI Studies Lead				on - Harmonic Impedance Sectors Study Report	Q1 15	Q2 15	Q1 15	Q2 15			
RFI Studies Lead				on - Assessment of the impact of AC Lines in Parallel with DC Lines Study Report	Q3 15	Q3 15	Q3 15	Q3 15			
RFI Studies Lead				on - Block / De-block Sequence Strategy Report	Q2 16	Q3 16	Q2 16	Q3 16			
RFI Studies Lead				on - Thyristor Valve Design Description - Design Report	Q4 15	Q4 15	Q4 15	Q4 15			
RFI Studies Lead RFI Studies Lead		100.0% 100.0%		on - DC Smoothing Reactor Study Report	Q1 16	Q2 16	Q1 16 Q1 16	Q2 16 Q3 17			
Kri Studies Lead	98.0%	100.0%		on - Transient Stability, Dynamic Multi Interaction, GSE and FFTOV Study Report nal Base Cases (4) for Bipole	Q1 16 Q1 16	Q4 16 Q4 16	Q1 16 Q1 16	Q3 17 Q3 17			
	75.0%			/Intermediate "Phased Approach Cases	Q1 10 Q1 17	Q4 10 Q3 17	Q1 10 Q1 17	Q3 17 Q3 17			
	50.0%			Load "Phased Approach Case"	Q1 17	Q3 17	Q1 17 Q1 17	Q3 17			
RFI Studies Lead		100.0%		on - PSCAD™ Dynamic Performance Study Report	Q4 16	Q1 17	Q4 16	Q3 17			
RFI Studies Lead				on - RTDS™ Dynamic Performance Study Outline Report	Q1 16	Q1 16	Q1 16	Q1 16			
RFI Studies Lead	0.0%	67.7%	Commo	on - RTDS™ Dynamic Performance Study Report	Q4 16	Q4 17	Q4 16	Q3 17			
RFI Studies Lead	100.0%	100.0%	Commo	on - Transient Overvoltage Study Outline Report	Q1 16	Q2 16	Q1 16	Q2 16			
RFI Studies Lead				on - Transient Overvoltage Study - Report	Q2 16	Q2 16	Q2 16	Q2 16			
RFI Studies Lead		100.0%		on - Converter Station -AC Circuit Breaker - TRV study	Q1 16	Q2 16	Q1 16	Q2 16			
RFI Studies Lead				on - AC Filter Rating Report	Q4 15	Q4 15	Q4 15	Q4 15			
RFI Studies Lead		100.0%		on - AC Filter Performance Report	Q3 15	Q3 15	Q3 15	Q3 15			
RFI Studies Lead				on - Load Flow & Short Circuit Level Studies - Outline Report	Q3 16	Q3 15	Q3 16	Q3 15			
RFI Studies Lead RFI Studies Lead		100.0%		on - Load Flow & Short Circuit Level Studies Report on - Equivalent AC Network Derivation Report	Q3 15 Q2 16	Q3 15 Q2 16	Q3 15 Q2 16	Q3 15 Q2 16			
RFI Studies Lead				on - HVDC Models For Use In PSS®E - Report	Q2 16 Q3 15	Q2 16 Q3 15	Q2 16 Q3 15	Q2 16 Q3 15			
in i otadies Lead	0.0%	0.0%		Alstom) Studies Support & Review Post Commissioning	Q3 13 Q3 18	Q3 13 Q3 18	Q3 13 Q3 18	Q3 13 Q3 18 P	2		
RFI Studies Lead		0.0%		on - Predicted Noise Study Report	Q3 18	Q3 18	Q3 18	Q3 18			
RFI Studies Lead		0.0%		on - Converter Station Losses Report	Q3 18	Q3 18	Q3 18	Q3 18			
	100.0%			lies Support & Review	Q3 14	Q3 17	Q3 14	Q3 17 P	Q4 17 ML In Service Minus 3 mths	Q4 17	60 Delivery
RFI Studies Lead		100.0%		ain Circuit Parameters Study Outline	Q4 14	Q4 14	Q4 14	Q4 14			
RFI Studies Lead				sulation Coordination Study Outline	Q4 14	Q4 14	Q4 14	Q4 14			
RFI Studies Lead				ansient Currents Study Outline	Q4 14	Q4 14	Q4 14	Q4 14			
RFI Studies Lead	100.0%	100.0%	ARR MC	odels of Operation Study Outline	Q4 14	Q4 14	Q4 14	Q4 14			

RF1 Studies Lead 100,00% 100,00% ABB AC Filter Performance Study Outline 0,114 0,114 0,114 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,115 0,1	system/ delivery
RFI Studies Lead 10.00% 100.00% ABB DC Harmonic Performance Study Outline Q4 14 Q4 15 Q4	
RFI Studies Lead 10.0% 10.0% 10.0% ABB Insulation Coordination for HVdc System - Technical Report Q4 14 Q4 14 Q4 14 Q4 14 Q4 14 Q4 14 Q4 15	
RFI Studies Lead 100.0% 100.0% ABB Main Circuit Parameters Technical Report Q4 14 Q1 15 Q4 14 Q1 15 Q4 15 Q4 15 Q4 16 Q2	
RFI Studies Lead 100.0% 100.0% ABB Fransient Currents	
RFI Studies Lead 100.0% 100.0% ABB Black Start Study, Study Outline Q2 16 Q2 1	
RFI Studies Lead 100.0% 100.0% ABB Emergency Power Control Study, Study Outline Q2 16 Q2 15 Q2 1	
RFI Studies Lead 100.0% 100.0% ABB Load Flow and Stability Study, Study Outline Q1 15 Q1 1	
RFI Studies Lead 100.0% 100.0% ABB Dynamic Performance Study, Study Outline 20 1 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15 20 15	
RFI Studies Lead 100.0% ABB Multi-Infeed Screening Study, Study Outline Q1 15 Q2 15	
RFI Studies Lead 100.0% 100.0% ABB Multi-Infeed Screening Study Q2 15	
RFI Studies Lead 100.0% 100.0% ABB Frequency Control Study (Includes Plots) Q1 15	
RFI Studies Lead 100.0% 100.0% ABB SSTI Screening Study Q2 15 Q2 15 Q2 15 Q2 15 RFI Studies Lead 100.0% 100.0% ABB Network Data Summary Q1 15 Q1 15 Q1 15 Q1 15 RFI Studies Lead 100.0% 100.0% ABB SSTI Screening Study, Study Outline Q1 15 Q2 15 Q2 15 RFI Studies Lead 100.0% 100.0% ABB Transient Overvoltage Study Q3 15 Q4 15 Q1 15 Q1 15 RFI Studies Lead 100.0% 100.0% ABB PreInsertion Resistor Study Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB PreInsertion Resistor Study, Study Outline Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages, Study Outline Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% ABB AC Filter Rating, Study Outline Q3 15 Q4 15 Q3 15 Q4 15	
RFI Studies Lead 100.0% 100.0% ABB Network Data Summary Q1 15 Q2 15 RFI Studies Lead 100.0% 100.0% ABB Transient Overvoltage Study Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB PreInsertion Resistor Study Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages, Study Outline Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages, Study Outline Q1 15 Q1 15 Q1 15 Q1 15 RFI Studies Lead 100.0% 100.0% ABB AC Filter Rating, Study Outline Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% ABB Influence of Parallel AC Lines, Study Outline	
RFI Studies Lead 100.0% 100.0% 100.0% ABB SSTI Screening Study, Study Outline Q1 15 Q2 15 Q1 15 Q2 15 RFI Studies Lead 100.0% 100.0% ABB Transient Overvoltage Study Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB PreInsertion Resistor Study Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages Q3 15 Q4 15 Q2 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages, Study Outline Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages, Study Outline Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB AC Filter Rating, Study Outline Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB Influence of Parallel AC Lines, Study Outline Q3 15 Q4 15 Q2 15 Q2 15	
RFI Studies Lead 100.0% 100.0% ABB Transient Overvoltage Study Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% 100.0% ABB PreInsertion Resistor Study Q3 15 Q4 15 Q1 15 Q1 15 RFI Studies Lead 100.0% 100.0% ABB PreInsertion Resistor Study, Study Outline Q2 15 Q2 15 Q2 15 Q2 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages, Study Outline Q1 15 Q1 15 Q1 15 Q1 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages, Study Outline Q1 15 Q1 15 Q1 15 Q1 15 RFI Studies Lead 100.0% 100.0% ABB AC Filter Rating, Study Outline Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB Influence of Parallel AC Lines, Study Outline Q2 15 Q2 15 Q2 15 Q2 15 Q2 15	
RFI Studies Lead 100.0% 100.0% 100.0% ABB Transient Overvoltage Study Study Outline Q1 15 Q2 15 <td></td>	
RFI Studies Lead 100.0% 100.0% ABB PreInsertion Resistor Study Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB FreInsertion Resistor Study, Study Outline Q2 15 Q2 15 Q2 15 Q2 15 RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB AC Filter Rating, Study Outline Q3 15 Q4 15 Q3 15 Q4 15 RFI Studies Lead 100.0% 100.0% ABB Influence of Parallel AC Lines, Study Outline Q2 15 Q2 15 Q2 15 Q2 15	
RFI Studies Lead 100.0% 100.0% ABB PreInsertion Resistor Study, Study Outline RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages, Study Outline RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages, Study Outline RFI Studies Lead 100.0% 100.0% ABB AC Filter Rating, Study Outline ABB AC Filter Rating, Study Outline ABB Influence of Parallel AC Lines, Study Outline Q2 15	
RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages Q3 15 Q4 15 Q4 15 Q1	
RFI Studies Lead 100.0% 100.0% ABB Fundamental Frequency Overvoltages, Study Outline RFI Studies Lead 100.0% 100.0% ABB AC Filter Rating, Study Outline RFI Studies Lead 100.0% 100.0% ABB Influence of Parallel AC Lines, Study Outline Q1 15 Q1 15 Q1 15 Q1 15 Q3 15 Q4 15 Q2 15 Q2 15 ABB Influence of Parallel AC Lines, Study Outline	
RFI Studies Lead 100.0% ABB AC Filter Rating, Study Outline Q3 15 Q4 15 RFI Studies Lead 100.0% ABB Influence of Parallel AC Lines, Study Outline Q2 15 Q2 15 Q2 15	
RFI Studies Lead 100.0% 100.0% ABB Influence of Parallel AC Lines, Study Outline Q2 15 Q2 15 Q2 15	
7. 25 Q. 25	
RFI Studies Lead 100.0% 96.2% ABB DC Harmonic Performance Q2 16 Q3 17 Q2 16 Q3 17	
RFI Studies Lead 100.0% 100.0% ABB SSTI Study, Study Outline Q2 16 Q2 16 Q2 16	
RFI Studies Lead 100.0% 100.0% ABB General requirements for main circuit apparatus Q3 14 Q3 14 Q3 14 Q3 14	
RFI Studies Lead 100.0% 100.0% ABB HVDC Switches, Study Outline Q1 15 Q1 15 Q1 15	
70.0% 70.8% ABB Studies Ongoing Support & Review as required Q2 16 Q4 17 Q2 16 Q4 17	
76.5% 82.2% Operational System Studies & Support of Operating Limits/Instructions Q1 16 Q4 17 Q1 16 Q4 17 P3	
RFI Studies Lead 100.0% 100.0% Sync Relay Check for MFA prior to LIL Q1 17 Q1 17 Q1 17 Q1 17 Q1 17 Q3 18 LIL In Service Minus 3 mths Q3 18	Delivery
RFI Studies Lead 100.0% 100.0% Minimum Equipment Study including cases for 0, 1 or 2 Sync Condensors at SOP Q1 17 Q1 17 Q1 17 Q1 17 Q1 18 SOPSC Energize Minus 3 mths Q1 18	Delivery
	L51 Delivery
NLH 100.0% 100.0% MATPC Reserve and Emergency Sharing Q2 16 Q1 17 Q2 16 Q1 17 Q3 18 LIL In Service Minus 3 mths Q3 18	Delivery
	22 Delivery
100.0% Deliver models inputs to HQT Q1 16 Q2 16 Q1 16 Q1 17 90.0% HQT to Deliver Final Report Q1 16 Q2 17 Q1 16 Q3 17	
	16 Delivery
TGS 90.0% 100.0% Identification of Maritime Link Import Export Limits Q4 17	to belivery
TCS 00.0% 100.0% Identification of transfer limits in transmission corridors for n 0 and n 1 exercting conditions	
TGS 90.0% 100.0% Identification of transfer limits in transmission corridors for n-0 and n-1 operating conditions Q4 16 Q1 17 Q1 17 Q3 17 TGS 90.0% 100.0% Impacts of the Maritime Link frequency controller Q4 16 Q1 17 Q1 17 Q3 17	
TGS 90.0% 100.0% Review of underfrequency load shedding with the existing scheme in place Q4 16 Q1 17 Q1 17 Q3 17	
	45 Delivery
TGS 11.5% Update of Maritime Link import and export limits Q3 17 Q4 17 Q3 17 Q4 17	io Delitery
TGS 11.5% Update of transfer limits in transmission corridors for n-0 and n-1 operating conditions Q3 17 Q4 17 Q3 17 Q4 17	
TGS 11.5% Update of transfer limits in transmission corridors for n-0 and n-1 operating conditions Q3 17 Q4 17 Q3 17 Q4 17 TGS 11.5% Review of underfrequency load shedding with the existing scheme in place Q3 17 Q4 17 Q3 17 Q4 17	
TGS 65.0% 72.7% Identification of Labrador Island Link import and export limits Q3 18	31 Delivery
TGS 65.0% 72.7% Update of Maritime Link import and export limits Q4 17 Q3 17 Q4 17 Q4 16 Q4 17 Q3 17 Q4 17	91 Delivery

Resources	Actual UPDATE GREEN %'s	Expected	WBS L1 WBS L2 WBS L4	Baseline Start Date (Q)	Baseline End Date (Q)	Actual/Forecast Start Date (Q)	Actual/Forecast End Date (Q) Project Priority	Critical Path	LCP In Service Date (Q)	at Wa	people/ process/ system/ delivery
TGS	65.0%	72.7%	Identification of transfer limits in Labrador transmission corridors for n-0 and n-1 operating conditions	Q4 16	Q4 17	Q3 17	Q4 17				
TGS TGS	65.0% 65.0%	72.7% 72.7%	Update of transfer limits in Newfoundland transmission corridors for n-0 and n-1 operating conditions Review of underfrequency load shedding with the existing scheme in place Impacts of the Labrador Island Link frequency controller and coordination with the Maritime Link	Q4 16 Q4 16	Q4 17 Q4 17	Q3 17 Q3 17	Q4 17 Q4 17				
TGS	65.0%	72.7%	frequency controller	Q4 16	Q4 17	Q3 17	Q4 17				
TGS TGS	76.9% 90.0% 0.0%	74.1% 86.8% 0.0%	Energization System Studies LTA and LIL GEP's (Original GEP 1 to 8) GEP 13 Study (Integrated Tests Low Power w/LIL monpole and ML bipole)	Q2 17 Q2 17 Q3 17	Q4 17 Q3 17 Q4 17	Q2 17 Q2 17 Q3 17	Q4 17 P3 Q3 17 Q4 17	Q3 18 LIL In Service Minus 3 mths Q3 18 LIL In Service Minus 3 mths	-		Delivery Delivery
RFI Studies Lead RFI Studies Lead	0.0% 0.0% 0.0% 0.0%	0.0% 0.0% 0.0% 0.0%	RFI SYSTEM STUDIES - FULL POWER PREPARDNESS GE Grid (Alstom) Studies Support & Review Common - Transient Stability, Dynamic Multi Interaction, GSE and FFTOV Study Report Update to Bipole design studies - Reduced LIL import to monitor frequency controller action	Q1 18 Q1 18 Q1 18	Q3 18 Q3 18 Q3 18	Q1 18 Q1 18 Q1 18	Q3 18 P4 Q3 18 Q3 18	Q3 19 MFG First Power Minus 6 mths	Q4 19	270	Delivery
TGS	0.0%	0.0%	Operational System Studies Stage IV High Power Study - Addition of Muskrat Falls Generation (ML+LIL+LTA Study) Update of Labrador Island Link import and export limits	Q1 18 Q1 18 Q1 18	Q3 18 Q3 18 Q3 18	Q1 18 Q1 18 Q1 18	Q3 18 P4 Q3 18 Q3 18	Q3 19 MFG First Power Minus 6 mths	Q4 19	270	Delivery
TGS		0.0%	Update of Maritime Link import and export limits	Q1 18	Q3 18	Q1 18	Q3 18				
TGS		0.0%	Update of transfer limits in Labrador transmission corridors for n-0 and n-1 operating conditions	Q1 18	Q3 18	Q1 18	Q3 18				
TGS TGS		0.0%	Update of transfer limits in Newfoundland transmission corridors for n-0 and n-1 operating conditions Development of a new underfrequency load shedding scheme Review of Power System Stabilizer applications for generators and HVdc links for improved system	Q1 18 Q1 18	Q3 18 Q3 18	Q1 18 Q1 18	Q3 18 Q3 18				
TGS		0.0%	damping Update to coordination of the Labrador Island Link frequency controller and the Maritime Link frequency controller	Q1 18 Q1 18	Q3 18 Q3 18	Q1 18 Q1 18	Q3 18 Q3 18				
TGS		0.0%	Review of coordinated runbacks of HVdc links and operating restrictions with links out of service	Q1 18	Q3 18	Q1 18	Q3 18				
TGS		0.0%	Consideration of re-strikes on the Labrador Island HVdc Link Review of reactive power requirements for high power transfer on the Labrador Island Link and	Q1 18	Q3 18	Q1 18	Q3 18				
TGS TGS		0.0%	Review of reactive power requirements for high power transfer on the Labrador Island Link and evaluation of dynamic reactive additions at Soldiers Pond and Holyrood Review of Bay d'Espoir instabilities under a three-phase fault condition	Q1 18 Q1 18	Q3 18 Q3 18	Q1 18 Q1 18	Q3 18 Q3 18				
TGS TGS TGS TGS TGS	0.0%	0.0% 0.0% 0.0% 0.0% 0.0%	Energization System Studies GEP 9 Study (Muskrat Falls G1) GEP 10 Study (Muskrat Falls G2) GEP 11 Study (Muskrat Falls G3) GEP 12 Study (Muskrat Falls G4) GEP 14 Study (Integrated Tests - fullpower performance tests)	Q2 18 Q2 18 Q3 18 Q4 18 Q1 19 Q4 18	Q3 19 Q3 18 Q4 18 Q2 19 Q3 19 Q2 19	Q2 18 Q2 18 Q3 18 Q4 18 Q1 19 Q4 18	Q3 19 P4 Q3 18 Q4 18 Q2 19 Q3 19 Q2 19	Q3 19 MFG First Power Minus 6 mths	Q4 19	-9	Delivery
RFI Studies Lead RFI Studies Lead RFI Studies Lead	100.0% 100.0% 100.0%	100.0% 100.0% 100.0% 100.0%	RFI OTHER ITEMS - FIRST POWER PREPARDNESS NLH Equipment Tagging and Single Line Diagrams CHFTS Extension CHFTS2 (735/315 kV station) MFATS2 (315 kV station)	Q1 15 Q1 15 Q1 15 Q1 15	Q2 17 Q1 15 Q1 15 Q3 15	Q1 15 Q1 15 Q1 15 Q1 15	Q1 20 P3 Q1 15 Q1 15 Q3 15	Q4 17 CFTS Energize Minus 6 mths Q4 17 CFTS Energize Minus 6 mths Q4 17 MFTS Energize Minus 6 mths	Q4 17 Q4 17 Q4 17		Delivery Delivery Delivery
RFI Studies Lead RFI Studies Lead RFI Studies Lead	100.0%	100.0%	MFAGS (Generating station) MFACS (Muskrat Converter station) FPTCABLE (Forteau Point Transition Compound)	Q1 15 Q1 15 Q1 15	Q2 15 Q3 15 Q4 15	Q1 15 Q1 15 Q1 15	Q2 15 Q3 15 Q4 15	Q3 19 MFG First Power Minus 6 mths Q1 18 MFCS Energize Minus 6 mths Q4 17 LTA In Service Minus 6 mths	Q4 19 Q1 18 Q4 17		Delivery Delivery Delivery

Resources	∢ ⊃ %	Expected	WBS L1 WBS L2 WBS L4	Baseline Start Date (Q)	Baseline End Date (Q)	Actual/Forecast Start Date (Q)	Actual/Forecast End Date (Q) Project Priority	Critical Path	LCP In Service Date (Q)	Float Watch	people/ process/ system/ delivery
RFI Studies Lead			SOCCABLE (Shoal Cove Transition Compound)	Q1 15	Q3 16	Q1 15	Q3 16	Q4 17 LTA In Service Minus 6 mths	Q4 17		Delivery
RFI Studies Lead		100.0%	SOPCS (Soldiers Pond Converter station)	Q1 15	Q1 15	Q1 15	Q1 15	Q1 18 SOPCS Energize Minus 6 mths	Q1 18		Delivery
RFI Studies Lead			SOPSC (Soldiers Pond Synchronous Condenser station)	Q1 15	Q3 15	Q1 15	Q3 15	Q1 18 SOPSC Energize Minus 6 mths	Q1 18		Delivery
RFI Studies Lead			SOPTS (230 kV station)	Q1 15	Q3 15	Q1 15	Q3 15	Q1 18 SOPTS Energize Minus 6 mths	Q1 18		Delivery
RFI Studies Lead		100.0%	BBKCS (Bottom Brook Converter station) BBKTS1 (existing Bottom Brook 230 kV station)	Q1 15	Q2 15	Q1 15	Q2 15	Q4 17 ML In Service Minus 6 mths	Q4 17		Delivery
RFI Studies Lead RFI Studies Lead		100.0%	BBKTS1 (existing Bottom Brook 230 kV station) BBKTS2 (new ENL Bottom Brook 230 kV station)	Q1 15 Q1 15	Q2 15 Q2 15	Q1 15 Q1 15	Q2 15 Q2 15	Q4 17 ML In Service Minus 6 mths Q4 17 ML In Service Minus 6 mths	Q4 17 Q4 17		Delivery Delivery
RFI Studies Lead			GCTTS (Granite Canal Tap 230 kV station)	Q1 15 Q1 15	Q2 15 Q3 15	Q1 15 Q1 15	Q2 15 Q3 15	Q4 17 ML In Service Minus 6 mths	Q4 17 Q4 17		Delivery
NLH			USLTS (Upper Salmon 230 kV station breaker addition)	Q1 17	Q2 16	Q1 17	Q2 16	Q1 18 SOPTS Energize Minus 6 mths	Q1 18		Delivery
NLH		100.0%	BDETS1 & 2 (Bay d'Espir 230 kV line re-termination and TL267)	Q1 17	Q2 16	Q1 17	Q2 16	Q1 18 SOPTS Energize Minus 6 mths	Q1 18		Delivery
NLH			WAVTS (Western Avalon 230 kV station, TL267 addition)	Q1 17	Q2 16	Q1 17	Q2 16	Q1 18 SOPTS Energize Minus 6 mths	Q1 18		Delivery
NLH	100.0%		MFATS2 for 315 kV shunt reactor	Q3 16	Q2 17	Q3 16	Q2 17	Q4 17 MFTS Energize Minus 6 mths	Q4 17		Delivery
	86.3%	100.0%	Support Delivery of Final Points Lists (ECC Control & Monitoring)	Q1 16	Q2 17	Q1 16	Q4 17 P3				
RFI Mgr	100.0%	100.0%	SOPTS	Q1 16	Q4 16	Q1 16	Q2 17	Q1 18 SOPTS Energize Minus 2 mths	Q1 18		Delivery
RFI Mgr	50.0%	100.0%	SOPCS	Q1 16	Q2 17	Q1 16	Q4 17	Q1 18 SOPCS Energize Minus 2 mths	Q1 18	22	Delivery
RFI Mgr	70.0%	100.0%	SOPSC	Q1 16	Q1 17	Q1 16	Q4 17	Q1 18 SOPSC Energize Minus 2 mths	Q1 18	75	Delivery
RFI Mgr	95.0%	100.0%	FPTCABLE	Q1 16	Q1 17	Q1 16	Q3 17	Q4 17 LTA In Service Minus 2 mths	Q4 17	51	Delivery
RFI Mgr	95.0%	100.0%	SOCCABLE	Q1 16	Q1 17	Q1 16	Q3 17	Q4 17 LTA In Service Minus 2 mths	Q4 17	51	Delivery
RFI Mgr	95.0%		CHFTS2	Q1 16	Q4 16	Q1 16	Q4 17	Q4 17 CFTS Energize Minus 2 mths	Q4 17	-31	Delivery
RFI Mgr			CHF	Q1 16	Q4 16	Q1 16	Q2 17	Q4 17 CFTS Energize Minus 2 mths	Q4 17		Delivery
RFI Mgr	50.0%	100.0%	MFACS	Q1 16	Q2 17	Q1 16	Q4 17	Q1 18 MFCS Energize Minus 2 mths	Q1 18	52	Delivery
RFI Mgr			MFATS2	Q1 16	Q4 16	Q1 16	Q4 17	Q4 17 MFTS Energize Minus 2 mths	Q4 17	-5	Delivery
RFI Mgr RFI Mgr			BBKCS	Q1 16	Q2 16	Q1 16	Q3 17	Q4 17 ML In Service Minus 4 mths	Q4 17	U	Delivery
RFI Mgr		100.0% 100.0%	BBKTS2 GCTTS	Q1 16 Q1 16	Q4 16 Q2 16	Q1 16 Q1 16	Q2 17 Q2 17	Q4 17 ML In Service Minus 6 mths Q4 17 ML In Service Minus 6 mths	Q4 17 Q4 17		Delivery Delivery
	45.8%	56.4%	Support Delivery of Grid Energization Procedures	Q2 16	Q3 19	Q2 16	Q3 19 P2				
RFI Mgr	100.0%	100.0%	GEP Overview	Q2 16	Q4 16	Q2 16 Q2 16	Q3 13 F2 Q4 16				Delivery
RFI Mgr		100.0%	GEP1: Churchhill Falls TS and TS Ext	Q2 10 Q4 16	Q2 17	Q4 16	Q 4 10 Q2 17	Q4 17 CFTS Energize Minus 1 mth	Q4 17		Delivery
RFI Mgr			GEP2: Muskrat Falls TS	Q4 16	Q2 17	Q4 16	Q3 17	Q4 17 MFTS Energize Minus 1 mth	Q4 17	56	Delivery
RFI Mgr	0.0%	55.7%	GEP3: MF Converters & Filters	Q1 17	Q4 17	Q3 17	Q4 17	Q1 18 MFCS Energize Minus 1 mth	Q1 18	82	Delivery
RFI Mgr	0.0%	55.7%	GEP4: FT Pt TC, Subsea Cable & LAD Electrode	Q1 17	Q4 17	Q3 17	Q4 17	Q1 18 MFCS Energize Minus 1 mth	Q1 18	82	Delivery
RFI Mgr	0.0%	36.4%	GEP5: SC TC, Subsea Cable & DP Electrode	Q2 17	Q3 17	Q3 17	Q3 17	Q1 18 MFCS Energize Minus 1 mth	Q1 18	112	Delivery
RFI Mgr	0.0%	36.4%	GEP6: Soldiers Pond CS	Q2 17	Q3 17	Q3 17	Q3 17	Q1 18 SOPCS Energize Minus 1 mth	Q1 18	82	Delivery
RFI Mgr	100.0%	100.0%	GEP7: Soldiers Pond TS	Q4 16	Q2 17	Q4 16	Q2 17	Q1 18 SOPTS Energize Minus 1 mth	Q1 18		Delivery
RFI Mgr	25.0%	36.4%	GEP8: Soldiers Pond SC	Q2 17	Q3 17	Q3 17	Q3 17	Q1 18 SOPSC Energize Minus 1 mth	Q1 18	135	Delivery
RFI Mgr	0.0%	0.0%	GEP9: MFG Unit1	Q2 18	Q4 18	Q2 18	Q4 18	Q4 19 MFG First Power Minus 1 mth	Q4 19	360	Delivery
RFI Mgr	0.0%	0.0%	GEP10: MFG Unit2	Q3 18	Q1 19	Q3 18	Q1 19	Q4 19 MFG First Power Minus 1 mth	Q4 19	270	Delivery
RFI Mgr	0.0%	0.0%	GEP11: MFG Unit3	Q4 18	Q2 19	Q4 18	Q2 19	Q4 19 MFG First Power Minus 1 mth	Q4 19	180	•
RFI Mgr	0.0%	0.0% 7.7%	GEP12: MFG Unit4 GEP13: Low Power Transfer	Q1 19	Q3 19	Q1 19	Q3 19 Q4 17	Q4 19 MFG First Power Minus 1 mth	Q4 19	90 151	Delivery
RFI Mgr RFI Mgr	0.0% 0.0%	0.0%	GEP13: Low Power Transfer GEP14: High Power Transfer	Q3 17 Q4 18	Q4 17 Q3 19	Q3 17 Q4 18	Q4 17 Q3 19	Q3 18 LIL In Service Minus 1 mths Q3 20 MFG In Service Minus 1 mth	Q3 18 Q3 20	151 358	Delivery Delivery
	0.007	10.60/	Command DTDC Tasking and Contant Commissioning and Mark and the	00.17	03.40	03.47	03.40 53				
RFI Studies Lead	0.0%	18.6%	Support RTDS Testing and System Commissioning and Witnessing	Q2 17	Q2 18	Q3 17	Q2 18 P3	O2 19 III In Comica Minus 10 withs	02.10	20	Doliver
RFI Studies Lead	0.0%	48.4% 0.0%	RTDS Simulation Testing (Stafford) SOP SC1 Testing	Q2 17 Q4 17	Q3 17 Q4 17	Q3 17 Q4 17	Q3 17 Q4 17	Q3 18 LIL In Service Minus 10 mths	Q3 18	-29	Delivery
RFI Studies Lead		0.0%	SOP SC2 Testing	Q4 17 Q1 18	Q4 17 Q1 18	Q4 17 Q1 18	Q4 17 Q1 18				
RFI Studies Lead		0.0%	SOP SC3 Testing	Q2 18	Q1 18 Q2 18	Q1 18 Q2 18	Q1 18 Q2 18				
RFI Studies Lead		0.0%	LIL - Witness and verify filter bank switching tests SOP	Q2 18 Q3 17	Q2 18 Q4 17	Q2 18 Q3 17	Q2 18 Q4 17				
RFI Studies Lead		0.0%	LIL - Witness and verify filter bank switching tests MFA	Q3 17	Q4 17	Q3 17 Q3 17	Q4 17 Q4 17				
RFI Studies Lead		0.0%	LIL - Witness and verify performance of low power tests	Q1 18	Q2 18	Q1 18	Q4 17 Q2 18				
RFI Studies Lead		0.0%	ML - Witness and verify performance of low power tests	Q3 17	Q4 17	Q3 17	Q4 17				
					-	•	-				

ces E GREEN	cted		e Start	ine End (Q)	Il/Forecast Date (Q)	Actual/Forecast End Date (Q) Project Priority	Path	Service Q)	M people/
Resource Actual UPDATE %'s	ect	WBS L4 WBS L7 WBS L7	aseline ate (Q)	seline te (Q)	ctual/Fo tart Date	ual/l d Dat ject	ritical	e (C	system/
Res Act UPI	Exp		Basel Date	Bas Dat	Actua Start	Actu End Proj	Crit	LCP Dat	<mark>호</mark> delivery
0.0%		RFI OTHER ITEMS - FULL POWER PREPARDNESS							
0.0%	0.0%	Support Delivery of Final Points Lists	Q1 18	Q3 19	Q1 18	Q3 19 P4			"
RFI Mgr		MFAGS	Q1 18	Q3 19	Q1 18	Q3 19	Q4 19 MFG First Power Minus 2 mths	Q4 19	62 Delivery
0.0%	0.0%	RTDS Testing and System Commissioning and Witnessing	Q1 19	Q1 20	Q1 19	Q1 20 P3			
RFI Studies Lead	0.0%	LIL - Witness and verify performance of high power tests	Q1 19	Q2 19	Q1 19	Q2 19			
RFI Studies Lead	0.0%	ML - Witness and verify performance of high power tests	Q1 19	Q2 19	Q1 19	Q2 19			
RFI Studies Lead	0.0%	MFAG1 - Muskrat Falls Generator G1 Testing	Q2 19	Q2 19	Q2 19	Q2 19			
RFI Studies Lead	0.0%	MFAG2 - Muskrat Falls Generator G2 Testing	Q3 19	Q3 19	Q3 19	Q3 19			
RFI Studies Lead	0.0%	MFAG3 - Muskrat Falls Generator G2 Testing	Q4 19	Q4 19	Q4 19	Q4 19			
RFI Studies Lead	0.0%	MFAG4 - Muskrat Falls Generator G2 Testing	Q1 20	Q1 20	Q1 20	Q1 20			
45.00	67.50								
46.8% 46.8%		RFI NERC - FIRST POWER PREPARDNESS Key NERC Reliability Standards (Assess, Define and Develop Voluntary Standards)	Q1 15	Q1 18	01.15	Q1 18 P4	Q3 18 LIL In Service Minus 3 mths	Q3 18	56 Delivery
RFI NERC Lead 100.0%		External Validation of NLH Reliability Standards	Q1 15 Q1 15	Q1 16 Q4 16	Q1 15 Q1 15	Q1 16 P4 Q4 16	Q3 18 LIL III Service Willius 3 IIItiis	Q3 18	36 Delivery
RFI NERC Lead 100.0%		Complete Gap Analysis of Reliability Standards	Q3 15	Q4 10 Q1 17	Q1 15 Q3 15	Q4 10 Q1 17			
RFI NERC Lead 100.0%		Assist with Legislative Change, market structure, service request design	Q1 15	Q3 16	Q1 15	Q3 16			
RFI NERC Lead 80.0%		Define Bulk Electric System for application of standards	Q3 16	Q4 17	Q3 16	Q4 17			
RFI NERC Lead 100.0%		Develop Phase 1 Reliability Standard adoption criteria	Q3 16	Q4 17	Q3 16	Q4 17			
RFI NERC Lead 100.0%	100.0%	Assess NERC Reliability Standards for immediate voluntary adoption	Q4 16	Q2 17	Q4 16	Q2 17			
RFI NERC Lead 25.0%	100.0%	Rationalization of existing operations and planning practices with selected voluntary standards	Q1 17	Q2 17	Q1 17	Q2 17			
RFI NERC Lead 100.0%	100.0%	Document NLH standards, guidelines and criteria for non-BES elements	Q1 17	Q2 17	Q1 17	Q2 17			
RFI NERC Lead 100.0%	100.0%	Develop implementation plan for Phase 1 voluntary NLH Reliability Standards	Q2 17	Q2 17	Q2 17	Q2 17			
		Complete Phase 1 implementation of voluntary Reliability Standards	Q1 17	Q1 18	Q3 17	Q1 18			
RFI NERC Lead 100.0%		AESI - KickOff	Q1 17	Q2 17	Q3 17	Q3 17			
RFI NERC Lead	100.0%	AESI - Site Visits & Assessment	Q1 17	Q1 17	Q3 17	Q3 17			
RFI NERC Lead	38.3%	AESI - Issue Batch1 Draft Documents (20 Documents)	Q2 17	Q4 17	Q3 17	Q3 17			
RFI NERC Lead	38.3%	AESI - Issue Batch1 Final Dcouments (20 Documents)	Q2 17	Q4 17	Q3 17	Q4 17			
RFI NERC Lead	38.3%	AESI - Issue Batch2 Draft Documents (9 Documents)	Q2 17	Q4 17	Q3 17	Q4 17			
RFI NERC Lead	38.3%	AESI - Issue Batch2 Final Documents (9 Documents)	Q2 17	Q4 17	Q4 17	Q4 17			
RFI NERC Lead RFI NERC Lead	38.3%	AESI - Issue Batch3 Draft Documents (10 Documents)	Q2 17	Q4 17	Q3 17	Q4 17			
RFI NERC Lead	38.3%	AESI - Issue Batch3 Final Documents (10 Documents) AESI - Issue Batch4 of Optional Draft Documents (6 Documents)	Q2 17 Q4 17	Q4 17 Q4 17	Q4 17 Q4 17	Q4 17 Q4 17			
RFI NERC Lead	0.0%	AESI - Issue Batch4 of Optional Draft Documents (6 Documents) AESI - Issue Batch4 of Optional Final Documents (6 Documents)	Q4 17 Q4 17	Q4 17 Q1 18	Q4 17 Q4 17	Q4 17 Q1 18			
RFI NERC Lead	0.0%	AESI - Issue Batch of Optional Trial Documents (5 Documents) AESI - Issue Batch of Optional Draft Documents (5 Documents)	Q4 17 Q4 17	Q1 18 Q1 18	Q4 17 Q4 17	Q1 18 Q1 18			
RFI NERC Lead	0.0%	AESI - Issue Batch5 of Optional Final Documents (5 Documents)	Q1 18	Q1 18	Q1 18	Q1 18			
0.0%	0.0%	RFI NERC - FULL POWER PREPARDNESS							
0.0%	0.0%	Reliability Standards	Q4 17	Q4 19	Q4 17	Q4 19 P4	Q4 19 MFG First Power Minus 6 mths	Q3 20	Delivery
RFI NERC Lead	0.0%	Develop Phase 2 Reliability Standard adoption criteria	Q4 17	Q4 17	Q4 17	Q4 17			
RFI NERC Lead	0.0%	Assess NERC Reliability Standards for Phase 2 voluntary adoption	Q4 17	Q1 18	Q4 17	Q1 18			
RFI NERC Lead	0.0%	Rationalzation of existing operations and planning practices with selected Phase 2 voluntary standards	Q1 18	Q2 18	Q1 18	Q2 18			
RFI NERC Lead	0.0%	Develop implementation plan for Phase 2 voluntary NLH Reliability Standards	Q2 18	Q3 18	Q2 18	Q3 18			
RFI NERC Lead	0.0%	Complete Phase 2 implementation of voluntary Reliability Standards	Q3 18	Q4 19	Q3 18	Q4 19			

% Co	mplete		Basel	ne Dates	Actual/	Forecast					
Resources Actual UPDATE GREEN	% s Expected	WBS L4	Baseline Start Date (Q)	Baseline End Date (Q)	Actual/Forecast Start Date (Q)	Actual/Forecast End Date (Q)	Project Priority	critical Path	LCP In Service Date (Q)	Float Watch	people/ process/ system/ delivery
19.89	% 20.4 %	BTPO SCOPE									
34.29		Governance & Oversight - Workstream Manager	Q1 16		Q2 16	Q2 20					
BTPO Mgr 34.29		Mgmt, Mtgs, Reporting, Review (50% for BTPO Manager)	Q1 16	Q2 20	Q1 16	Q2 20					
45.59		BTPO: PEOPLE SCOPE									
33.09		Team Lead - People	Q1 16		Q2 16	Q2 20					
People Lead 34.29			Q1 16	Q2 20	Q1 16	Q2 20					
People Lead 30.39	% 30.3%	Labor Agreement/Committment Administration (7% for People Lead)	Q2 16	Q2 20	Q2 16	Q2 20					
56.89	% 58.7%	BTPO: PEOPLE - FIRST POWER PREPARDNESS	_								_
100.09	6 100.0%	Labour Negotiations & Agreements	Q1 15	Q1 17	Q1 15	Q1 17	P2	Q3 18 LIL In Service Minus 12 mths	Q3 18		People
People Lead 100.09	<mark>6</mark> 100.0%	CBA - Initial FY17 Collective Bargaining Agreement, Negotiations & Mtgs	Q4 16	Q1 17	Q4 16	Q1 17					
People Lead 100.09	<mark>6</mark> 100.0%	ELAC Considerations - Negotiations, Meetings, Documents	Q1 15	Q4 16	Q1 15	Q4 16					
People Lead 100.09	<mark>6</mark> 100.0%	IBA LTA Considerations - Roles, Strategy, MOU, HROE Support, Priorities	Q1 16	Q4 16	Q1 16	Q4 16					
People Lead 100.09	<mark>%</mark> 100.0%	IBA MFG Considerations - Roles, Strategy, MOU, HROE Support, Priorities	Q1 16	Q4 16	Q1 16	Q4 16					
62.79	% 68.8%	Staffing Strategy and Recruitment									
71.29		Strategy & Planning	Q1 16	Q1 18	Q1 16	Q1 18	P2				People
People Lead 100.09	<mark>6</mark> 100.0%	Plant Operations Support Considerations	Q1 16	Q4 16	Q1 16	Q4 16					
People Lead 100.09	<mark>6</mark> 100.0%		Q1 16	Q4 16	Q1 16	Q4 16					
People Lead 65.09	68.4%	LCP Staff Transition Considerations	Q1 16	Q1 18	Q1 16	Q1 18					
BTPO Mgr 80.09	<mark>6</mark> 80.5%	GE GRID & ATCO Operations Support Strategy	Q3 16	Q3 17	Q3 16	Q3 17					
People Lead 40.09	<mark>6</mark> 44.6%	Recruitinng Approach, Marketing, Planning	Q1 17	Q4 17	Q1 17	Q4 17					
People Lead 100.09	<mark>6</mark> 100.0%	Develop & Present HR Plan	Q1 16	Q4 16	Q1 16	Q4 16					
66.29	% 82.1 %	BTPO - Secure Team Resourcing	Q1 16	Q3 17	Q1 16	Q4 17	P2	Q3 18 LIL In Service Minus 6 mths	Q3 18	60	People
People Lead 100.09	<mark>6</mark> 100.0%	Requirements, Strategy, Job Scopes & Org Charts	Q1 16	Q4 16	Q1 16	Q4 16					
People Lead 100.09	<mark>6</mark> 100.0%	Review & Seek Approval for BTPO Staffing Plan	Q1 17	Q1 17	Q1 17	Q1 17					
People Lead 100.09	<mark>6</mark> 100.0%	Post Requisitions	Q1 17	Q1 17	Q1 17	Q2 17					
People Lead 46.29	<mark>69.1%</mark>	Recruit, Screen, Interview and Select Candidates	Q2 17	Q3 17	Q2 17	Q3 17					
People Lead 38.59	<mark>69.1%</mark>	Offers Finalized	Q2 17	Q3 17	Q2 17	Q4 17					
People Lead 30.89	<mark>69.1</mark> %	Onboarding & Coordination	Q2 17	Q3 17	Q2 17	Q4 17					
42.09	% 51.7 %	CFLCo - Secure O&M Resourcing	Q4 16	Q1 18	Q4 16	Q1 18	P2	Q4 17 LTA In Service Plus 3 mths	Q4 17	-8	People
People Lead 100.09	<mark>6</mark> 100.0%	Requirements, Strategy, Job Scopes & Org Charts	Q4 16	Q4 16	Q4 16	Q3 17					
People Lead 100.09	<mark>6</mark> 100.0%	Review & Seek Approval for LTA & LIL O&M Staffing Plan	Q4 16	Q1 17	Q4 16	Q3 17					
Rec Coord 0.09	<mark>6</mark> 41.0%	Post Requisitions	Q2 17	Q4 17	Q2 17	Q4 17					
Rec Coord 0.09	<mark>%</mark> 14.5%	Recruit, Screen, Interview and Select Candidates	Q2 17	Q1 18	Q2 17	Q1 18					
Rec Coord 0.09	<mark>6</mark> 14.5%	Offers Finalized	Q2 17	Q1 18	Q2 17	Q1 18					
Rec Coord 0.09	<mark>%</mark> 14.5%	Onboarding & Coordination	Q2 17	Q1 18	Q2 17	Q1 18					
52.39	% 64.1 %	LTA & LIL - Secure O&M Team Resourcing (Supervisor, Operator, Maintaine	r) Q1 16	Q1 18	Q1 16	Q1 18	P2	Q3 18 LIL In Service Minus 3 mths	Q3 18	1	People
People Lead 100.09	<mark>%</mark> 100.0%	Requirements, Strategy, Job Scopes & Org Charts	Q1 16	Q4 16	Q1 16	Q3 17					

Resources		Expected	WBS L1 WBS L2 WBS L3 WBS L4	Baseline Start Date (Q)	Baseline End Date (Q)	Actual/Forecast Start Date (Q)	Actual/Forecast End Date (Q)	Project Priority	Critical Path	LCP In Service Date (Q)	Float Watch	people/ process/ system/ delivery
		100.0%	Review & Seek Approval for LTA & LIL O&M Staffing Plan	Q4 16	Q1 17	Q4 16	Q3 17					
Rec Coord	75.9%	77.8%	Post Requisitions	Q1 17	Q3 17	Q1 17	Q3 17					
Rec Coord	13.8%	34.4%	Recruit, Screen, Interview and Select Candidates	Q1 17	Q1 18	Q1 17	Q1 18					
Rec Coord	13.8%	34.4%	Offers Finalized	Q1 17	Q1 18	Q1 17	Q1 18					
Rec Coord	0.0%	34.4%	Onboarding & Coordination	Q1 17	Q1 18	Q1 17	Q1 18					
	68.0%	57.2%	Contractor (ATCO & GE Grid) - Secure O&M Supports	Q2 16	Q4 17	Q2 16	Q4 17	P2	Q3 18 LIL In Service Minus 3 mths	Q3 18	91	People
BTPO Mgr	90.0%	89.7%	Requirements, Strategy, Job Scopes & Org Charts	Q2 16	Q3 17	Q2 16	Q3 17					
BTPO Mgr	60.0%	16.3%	Review & Seek Approval for Contractor Supports	Q2 17	Q3 17	Q2 17	Q3 17					
BTPO Mgr	50.0%	9.2%	Contract Negotiations	Q3 17	Q4 17	Q3 17	Q4 17					
BTPO Mgr		0.0%	Contracting Signing	Q3 17	Q4 17	Q3 17	Q4 17					
BTPO Mgr		0.0%	Onboarding & Coordination	Q4 17	Q4 17	Q4 17	Q4 17					
	19.0%	11.1%	Training Assessment, Schedule and Execution									
	22.5%	11.3%	CFLCo - Deliver O&M Training Requirements	Q1 17	Q4 19	Q1 17	Q4 19	P2				People
Trg Coord	80.0%	43.0%	CFLCo - Assess training requirements for equipment	Q1 17	Q1 18	Q1 17	Q1 18					
Trg Coord	70.0%	28.8%	CFLCo - Develop training strategy, plan, schedule & cost	Q2 17	Q1 18	Q2 17	Q1 18					
Trg Coord		5.1%	CFLCo - Assess training requirements for individuals	Q3 17	Q1 18	Q3 17	Q1 18					
Trg Coord		0.0%	CFLCo - Coordinate custom courses, vendor offerings	Q3 17	Q4 19	Q3 17	Q4 19					
TBD		0.0%	CFLCo - Deliver Training to Resources	Q3 17	Q4 19	Q3 17	Q4 19					
	22.5%	11.3%	LTA & LIL - Deliver O&M Training Requirements	Q1 17	Q4 19	Q1 17	Q4 19	P2				People
Trg Coord	80.0%	43.0%	LTA & LIL - Assess training requirements for equipment	Q1 17	Q1 18	Q1 17	Q1 18					
Trg Coord	70.0%	28.8%	LTA & LIL - Develop training strategy, plan, schedule & cost	Q2 17	Q1 18	Q2 17	Q1 18					
Trg Coord		5.1%	LTA & LIL - Assess training requirements for individuals	Q3 17	Q1 18	Q3 17	Q1 18					
Trg Coord		0.0%	LTA & LIL - Coordinate custom courses, vendor offerings	Q3 17	Q4 19	Q3 17	Q4 19					
TBD		0.0%	LTA & LIL - Deliver Training to Resources	Q3 17	Q4 19	Q3 17	Q4 19					
	12.0%	10.8%	CORPORATE - Deliver Standard Corporate Training Requirements	Q1 17	Q4 18	Q1 17	Q4 18	P2				People
Trg Coord	50.0%	43.0%	CORP - Assess training requirements	Q1 17	Q1 18	Q1 17	Q1 18					
Trg Coord	30.0%	28.8%	CORP - Develop training strategy, plan, schedule & cost	Q2 17	Q1 18	Q2 17	Q1 18					
Trg Coord		0.0%	CORP - Coordinate custom courses, vendor offerings	Q3 17	Q4 18	Q3 17	Q4 18					
TBD		0.0%	CORP - Deliver Training to O&M Resources	Q3 17	Q4 18	Q3 17	Q4 18					
	27.1%	17.6%	BTPO: PEOPLE - FULL POWER PREPARDNESS									
	28.9%	22.3%	Staffing Strategy and Recruitment									
	34.8%	28.4%	Recruiting - MFG O&M	Q2 16	Q2 19	Q2 16	Q2 19	P2	Q4 19 MFG First Power Minus 3 mths	Q4 19	90	People
People Lead	85.0%	73.6%	Requirements, Strategy, Job Scopes & Org Charts	Q2 16	Q4 17	Q2 16	Q1 18					
People Lead	50.0%	26.3%	Review & Seek Approval for MFG O&M Staffing Plan	Q1 17	Q3 18	Q1 17	Q3 18					
Rec Coord		0.0%	Post Requisitions	Q3 18	Q4 18	Q3 18	Q4 18					
Rec Coord		0.0%	Recruit, Screen, Interview and Select Candidates	Q3 18	Q2 19	Q3 18	Q2 19					
Rec Coord		0.0%	Offers Finalized	Q3 18	Q2 19	Q3 18	Q2 19					
Rec Coord		0.0%	Onboarding & Coordination	Q3 18	Q2 19	Q3 18	Q2 19					

Resources	Actual UPDATE GREEN %'s	Expected	WBS L1 WBS L2 WBS L3	Baseline Start Date (Q)	Baseline End Date (Q)	Actual/Forecast Start Date (Q)	Actual/Forecast End Date (Q)	Project Priority	Critical Path	LCP In Service Date (Q)	Float Watch	people/ process/ system/ delivery
	22.0%	15.2%	Recruiting - Corporate Supports	Q1 17	Q4 19	Q1 17	Q4 19	D2	Q3 20 MFG In Service	Q3 20	228	People
People Lead	50.0%	44.6%	Requirements, Strategy, Job Scopes & Org Charts	Q1 17 Q1 17	Q4 13 Q4 17	Q1 17 Q1 17	Q4 13 Q3 17	F Z	Q3 20 WFG III Service	Q3 20	236	reopie
People Lead	50.0%	0.0%	Review & Seek Approval for Corporate Staffing Plan	Q4 17	Q1 18	Q4 17	Q3 17					
Rec Coord	2.9%	11.2%	Post Requisitions	Q2 17	Q2 18	Q2 17	Q2 18					
Rec Coord	2.9%	1.5%	Recruit, Screen, Interview and Select Candidates	Q3 17	Q4 19	Q3 17	Q4 19					
Rec Coord	2.9%	1.5%	Offers Finalized	Q3 17	Q4 19	Q3 17	Q4 19					
Rec Coord	0.0%	1.5%	Onboarding & Coordination	Q3 17	Q4 19	Q3 17	Q4 19					
	22.5%	4.9%	Training Assessment, Schedule and Execution									
	22.5%	4.9%	MFG - Deliver O&M Training Requirements	Q2 17	Q4 19	Q2 17	Q4 19	P2	Q3 20 MFG In Service	Q3 20	238	People
Trg Coord	80.0%	14.5%	Assess training requirements for equipment	Q2 17	Q1 18	Q2 17	Q3 19					
Trg Coord	70.0%	14.5%	Develop training strategy, plan, schedule & cost	Q2 17	Q1 18	Q2 17	Q3 19					
Trg Coord		5.1%	Assess training requirements for individuals	Q3 17	Q1 18	Q3 17	Q3 19					
Trg Coord		0.0%	Coordinate custom courses, vendor offerings	Q1 18	Q4 19	Q1 18	Q4 19					
TBD		0.0%	Deliver Training to MFG O&M Resources	Q2 18	Q4 19	Q2 18	Q4 19			_	_	
	4.4%	5.8%	BTPO: ASSET MANAGEMENT SCOPE									
	18.9%	26.9%	Team Lead - Assets	Q2 16	Q2 20	Q2 16	Q2 20					
Rel Engineer	28.9%	28.9%	Mgmt, Mtgs, Reporting, Review	Q2 16	Q2 20	Q2 16	Q2 20					
Rel Engineer	10.0%	28.8%	Support Finance with asset value breakdown	Q2 17	Q1 18	Q1 17	Q3 18					
Rel Engineer	5.0%	22.5%	Critical Failure Modes & Effects Analysis (FMEA)	Q2 17	Q1 18	Q1 17	Q3 18					
	20.3%		BTPO: ASSETS - FIRST POWER PREPARDNESS									
	8.8%	11.0%	HVac TERMINAL STATION ASSETS									
	8.8%	11.0%	Soldiers Pond TS (Hierachies, Criticality, Spares & Program)	Q2 16	Q1 18	Q2 16	Q1 18	P3				
Rel Engineer	95.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16	Q3 16	Q2 16	Q2 17					
IBS	0.0%	55.7%	Extract Data & Compile Contractor Documentation	Q1 17	Q4 17	Q2 16	Q4 17		04.40.00000 1000001 0	04.40		
TC Constallat		15 40/	Leverage OEM Maintenance Program	Q3 17	Q4 17	Q3 17	Q4 17		Q1 18 SOPTS and SOPCS In Service	Q1 18	82	Processes
TS Specialist		15.4%	Identify & Review Applicable OEM Maintenance Routines & Procedures	Q3 17	Q3 17	Q3 17	Q3 17					
TS Specialist		0.0%	Implement Interim Weekly/Monthly OEM Maintenance Routines & Procedures	Q3 17	Q4 17	Q3 17	Q4 17		O2 10 LH In Comice	03.10	01	Dua
TC Consciolist		11 50/	Build Out Corporate Maintenance Program	Q3 17	Q1 18	Q3 17	Q1 18		Q3 18 LIL In Service	Q3 18	91	Processes
TS Specialist TS Specialist	25.0%	11.5% 0.0%	Perform Full Asset Criticality Assessment & Prioritize For Priority Assets Perform Critical Spaces & Speciality Tools Analysis	Q3 17	Q4 17	Q3 17 Q4 17	Q4 17 Q4 17					
TS Specialist	23.0%	0.0%	For Priority Assets Perform Critical Spares & Speciality Tools Analysis For Priority Assets Complete JDE Load Sheets (Assets, Maintenance)	Q4 17 Q4 17	Q4 17 Q1 18	Q4 17 Q4 17	Q4 17 Q1 18					
TS Specialist		0.0%	For Priority Assets Develop Asset Maintenance Program	Q4 17 Q4 17	Q1 18 Q1 18	Q4 17 Q4 17	Q1 18 Q1 18					
	8.8%	11.0%	Churchill Falls & Muskrat Falls TS (Hierachies, Criticality, Spares & Program)	Q2 16	Q1 18	Q2 16	Q1 18	D2				
Rel Engineer	95.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16 Q2 16	Q1 18 Q3 16	Q2 16 Q2 16	Q1 13 Q2 17	1 4				
IBS	0.0%	55.7%	Extract Data & Compile Contractor Documentation	Q2 10 Q1 17	Q3 10 Q4 17	Q2 16 Q2 16	Q2 17 Q4 17					
TS Specialist	0.070	33.770	Leverage OEM Maintenance Program	QI I/	Q+ 17	Q2 10	Q+ 17		Q4 17 CFTS and MFTS In Service	Q4 17	26	Processes
TS Specialist			Build Out Corporate Maintenance Program						Q3 18 LIL In Service	Q3 18	91	

Resources	Actual UPDATE GREEN %'s	Expected	WBS L1 WBS L2 WBS L3	Baseline Start Date (Q)	Baseline End Date (Q)	Actual/Forecast Start Date (Q)	Actual/Forecast End Date (Q)	Project Priority	Critical Path	LCP In Service Date (Q)	Float Watch	people/ process/ system/ delivery
	8.6%	8.9%	TRANSMISSION ASSETS									
	8.8%	9.7%	AC Transmission Labrador (Hierachies, Criticality, Spares & Program)	Q2 16	Q1 18	Q2 16	Q1 18	Р3				
Rel Engineer	95.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16	Q3 16	Q2 16	Q2 17					
IBS	0.0%	55.7%	Extract Data & Compile Contractor Documentation	Q1 17	Q4 17	Q2 16	Q4 17					
Trans Specialist			Leverage Existing Nalcor/NLH/CFLCo/NSP Maintenance Program	Q3 17	Q4 17	Q3 17	Q4 17		Q4 17 LTA In Service	Q4 17	-8	Processes
Trans Specialist			Build Out Corporate Maintenance Program	Q3 17	Q1 18	Q3 17	Q1 18		Q3 18 LIL In Service	Q3 18	91	Processes
	0.00/	0.20/	DC Cohora Tura anciesia a Charicht of Bellinia (Nicarchica Caiticality Corona & Barrana	02.46	04.40	03.46	04.40	D2				
Rel Engineer	8.8% 95.0%	9.3% 100.0%	DC Subsea Transmission - Straight of Bell Isle (Hierachies, Criticality, Spares & Program Develop High Level Asset Hierarchies		Q1 18 Q3 16	Q2 16 Q2 16	Q1 18 Q2 17	P3				
Trans Specialist	0.0%	55.7%	Extract Data & Compile Contractor Documentation	Q2 16 Q1 17	Q3 10 Q4 17	Q2 16 Q2 16	Q2 17 Q4 17					
Trans Specialist	0.076	33.770	Leverage Existing SOBI Team Recommendations for Maintenance Program	Q1 17 Q3 17	Q4 17 Q1 18	Q2 10 Q3 17	Q4 17 Q1 18		Q3 18 LIL In Service	Q3 18	91	Processes
Trans Specialist			Build Out Corporate Maintenance Program	Q3 17 Q3 17	Q1 18 Q1 18	Q3 17 Q3 17	Q1 18		Q3 18 LIL In Service	Q3 18 Q3 18		Processes
Trails specialist			Build Out Corporate Maintenance Program	Q3 17	QI IO	Q3 17	QI IO		Q3 10 LIE III SCIVICE	Q3 10	31	110003503
	8.2%	7.9%	DC Overland Transmission - Muskrat Falls to Soldiers Pond (Hierachies, Criticality, Spa	Q2 16	Q1 18	Q2 16	Q1 18	P3				
Rel Engineer	95.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16	Q3 16	Q2 16	Q2 17					
Trans Specialist	0.0%	55.7%	Extract Data & Compile Contractor Documentation	Q1 17	Q4 17	Q2 16	Q4 17					
Trans Specialist			Leverage Existing Nalcor/NLH/CFLCo Maintenance Program	Q3 17	Q1 18	Q3 17	Q1 18		Q3 18 LIL In Service	Q3 18	91	Processes
Trans Specialist			Build Out Corporate Maintenance Program	Q3 17	Q1 18	Q3 17	Q1 18		Q3 18 LIL In Service	Q3 18	91	Processes
	9.1%	9.1%	HVdc TRANSITION COMPOUND AND CONVERTER ASSETS									
_	8.8%	9.3%	Transition Compounds (Hierachies, Criticality, Spares & Program)	Q2 16	Q1 18	Q2 16	Q1 18	P3				
Rel Engineer	95.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16	Q3 16	Q2 16	Q2 17					
TS Specialist	0.0%	55.7%	Extract Data & Compile Contractor Documentation	Q1 17	Q4 17	Q2 16	Q4 17					_
TS Specialist			Leverage OEM Maintenance Program	Q3 17	Q1 18	Q3 17	Q1 18		Q3 18 LIL In Service			Processes
TS Specialist			Build Out Corporate Maintenance Program	Q3 17	Q1 18	Q3 17	Q1 18		Q3 18 LIL In Service	Q3 18	91	Processes
	9.5%	8.8%	Converter Stations - Muskrat Falls & Soldiers Pond (Hierachies, Criticality, Spares & Pro	Q2 16	Q1 18	Q2 16	Q1 18	Р3				
CS Specialist	95.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16	Q3 16	Q2 16	Q2 17					
CS Specialist	20.0%	55.7%	Extract Data & Compile Contractor Documentation	Q1 17	Q4 17	Q2 16	Q4 17					
CS Specialist			Leverage OEM Maintenance Program	Q3 17	Q4 17	Q3 17	Q4 17		Q1 18 MFCS and SOPCS In Service	Q1 18	22	Processes
CS Specialist			Build Out Corporate Maintenance Program	Q3 17	Q1 18	Q2 17	Q1 18		Q3 18 LIL In Service	Q3 18	91	Processes
	8.8%	9.3%	DC Transmission Yards & Grounding Stations - Muskrat Falls & Soldiers Pond (Hierachi		Q1 18	Q2 16	Q1 18	P3				
Rel Engineer	95.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16	Q3 16	Q2 16	Q2 17					
TS Specialist	0.0%	55.7%	Extract Data & Compile Contractor Documentation	Q1 17	Q4 17	Q2 16	Q4 17				_	_
TS Specialist			Leverage OEM Maintenance Program	Q3 17	Q1 18	Q3 17	Q1 18		Q3 18 LIL In Service	Q3 18		Processes
TS Specialist			Build Out Corporate Maintenance Program	Q3 17	Q1 18	Q3 17	Q1 18		Q3 18 LIL In Service	Q3 18	91	Processes
	8.8%	10.2%	OTHER ASSETS									
	8.8%	10.2%	Synchronous Condenser Plant at Soldiers Pond	Q2 16	Q1 18	Q2 16	Q1 18	Р3				
Rel Engineer	95.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16	Q3 16	Q2 16	Q2 17	. •				
TS Specialist	0.0%	72.2%	Extract Data & Compile Contractor Documentation	Q2 16	Q4 17	Q2 16	Q4 17					
- Specialist	3.073	, =.=,		~	~	~	~/					

(esources	DATE GREEN	ted	<u> </u>	eline Start :e (Q)	eline End e (Q)	ctual/Forecast tart Date (Q)	ial/Forecast Date (Q)	ect Priority	al Path	Service (Q)	Watch	people/ process/
esor	UPDA %'s	Expected	MW881 WBS 1 WBS 1	Baseli Date (aseli ate (ctua tart	Actua End D	Proje	Critical	LCP In Date (loat	system/ delivery
TS Specialist		iii	Leverage OEM Maintenance Program	Q3 17	Q1 18	Q3 17	Q1 18	<u></u>	Q1 18 SOPSC In Service	Q1 18	15	Processes
TS Specialist			Build Out Corporate Maintenance Program	Q3 17	Q1 18	Q3 17	Q1 18		Q3 18 LIL In Service	Q3 18		Processes
	70.0%	72.3%	HYDRO GENERATION ASSETS									
	70.0%	72.3%	MF Intake & Spillway Hydraulic Structures (Hierachies)	Q2 16	Q4 17	Q2 16	Q4 17	P2	Q4 19 MFG First Power	Q4 19	690	Processes
Rel Engineer	100.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16	Q1 17	Q2 16	Q2 17					
IBS	40.0%	44.6%	Extract Data & Compile Contractor Documentation	Q1 17	Q4 17	Q2 16	Q4 17					
	70.0%	72.3%	MF Equipment (Hierachies)	Q2 16	Q4 17	Q2 16	Q4 17	P4	Q4 19 MFG First Power	Q4 19	690	Processes
Rel Engineer	100.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16	Q1 17	Q2 16	Q2 17					
IBS	40.0%	44.6%	Extract Data & Compile Contractor Documentation	Q1 17	Q4 17	Q2 16	Q4 17					
	70.0%	72.3%	MF Balance of Plant (Hierachies)	Q2 16	Q4 17	Q2 16	Q4 17	P4	Q4 19 MFG First Power	Q4 19	690	Processes
Rel Engineer	100.0%	100.0%	Develop High Level Asset Hierarchies	Q2 16	Q1 17	Q2 16	Q2 17					
IBS	40.0%	44.6%	Extract Data & Compile Contractor Documentation	Q1 17	Q4 17	Q2 16	Q4 17					
	0.3%	0.0%	JDE DATA IMPORT & SETUP									
	0.3%	0.0%	JDE Data Migration & Linkage (Critical BOM's, Drawings, Spares, Methods Linkages)	Q4 17	Q2 18	Q4 17	Q2 18	Р3				Systems
Rel Engineer	1.0%	0.0%	Priority BOM's created	Q4 17	Q2 18	Q4 17	Q2 18					-
Rel Engineer		0.0%	Priority Assembly drawings linked	Q4 17	Q2 18	Q4 17	Q2 18					
Rel Engineer		0.0%	Priority Maintenance Tactics linked	Q4 17	Q2 18	Q4 17	Q2 18					
Rel Engineer		0.0%	Priority Critical spares linked	Q4 17	Q2 18	Q4 17	Q2 18					
Rel Engineer		0.0%	Priority Work Methods linked	Q4 17	Q2 18	Q4 17	Q2 18					
Rel Engineer		0.0%	Priority Mapped to Nalcor Asset Management Methodologies	Q4 17	Q2 18	Q4 17	Q2 18					
	0.0%	0.0%	BTPO: ASSETS - FULL POWER PREPARDNESS		-	-	-	-				
	0.0%	0.0%	HVac TERMINAL STATION ASSETS									
	0.0%	0.0%	Soldiers Pond TS (Detailed Hierachies, Criticality, REMAINING Spares & Program)	Q1 18	Q4 19	Q1 18	Q4 19	Р3				
TS Specialist		0.0%	Develop Detailed Level Asset Hierarchies	Q1 18	Q1 18	Q1 18	Q1 18					
TS Specialist		0.0%	Remaining Critical Spares Analysis	Q2 18	Q3 18	Q2 18	Q3 18					
TS Specialist		0.0%	Critical Spares Review & Spares Stocking	Q3 18	Q1 19	Q3 18	Q1 19					
TS Specialist		0.0%	Remaining Load Sheets (Assets, Maintenance)	Q3 18	Q4 19	Q3 18	Q4 19					
TS Specialist		0.0%	Remaining Asset Maintenance Program	Q3 18	Q4 19	Q3 18	Q4 19					
	0.0%	0.0%	Churchill Falls & Muskrat Falls TS (Detailed Hierachies, Criticality, REMAINING Spares 8	Q1 18	Q4 19	Q1 18	Q4 19	P2				
	0.0%	0.0%	TRANSMISSION ASSETS									
	0.0%	0.0%	AC Transmission Labrador (Detailed Hierachies, Criticality, REMAINING Spares & Progra	Q1 18	Q4 19	Q1 18	Q4 19	P2				
	0.0%	0.0%	DC Subsea Transmission - Straight of Bell Isle (Detailed Hierachies, Criticality, REMAINI	•	Q4 19	Q1 18	Q4 19					
	0.0%	0.0%	DC Overland Transmission - Muskrat Falls to Soldiers Pond (Detailed Hierachies, Critica		Q4 19	Q1 18	Q4 19					
	0.3%	0.0%	HVdc TRANSITION COMPOUND AND CONVERTER ASSETS									
	0.0%	0.0%	Transition Compounds (Detailed Hierachies, Criticality, REMAINING Spares & Program)	Q1 18	Q4 19	Q1 18	Q4 19	Р3				
		0.0%	Transition Compounds (Detailed Hierachies, Criticality, REMAINING Spares & Program) Converter Stations - Muskrat Falls & Soldiers Pond (Detailed Hierachies, Criticality, REN	-	Q4 19 Q4 19	Q1 18 Q1 18	Q4 19 Q4 19					

Resources Actual	UPDATE GREEN %'s	Expected	WBS L1 WBS L2 WBS L3	Baseline Start Date (Q)	Baseline End Date (Q)	Actual/Forecast Start Date (Q)	Actual/Forecast End Date (Q)	Project Priority	Critical Path	LCP In Service Date (Q)	Float Watch	people/ process/ system/ delivery
	0.0%	0.0%	OTHER ASSETS									
	0.0%	0.0%	Sync Plant (Detailed Hierachies, Criticality, REMAINING Spares & Program)	Q1 18	Q4 19	Q1 18	Q4 19	Р3				
	0.0%	0.0%	Communication Equipment - Churchill Falls to ECC, A and B paths (Detailed Hierachies	-	Q4 19	Q2 16	Q4 19					
	0.0%	0.0%	HYDRO GENERATION ASSETS									
	0.0%	0.0%	MF Intake & Spillway Hydraulic Structures (Detailed Hierachies, Criticality, Spares & Pr	Q1 18	Q4 19	Q1 18	Q4 19	P4				
	0.0%	0.0%	MF Equipment (Detailed Hierachies, Criticality, Spares & Program)	Q1 18	Q4 19	Q1 18	Q4 19					
	0.0%	0.0%	MF Balance of Plant (Detailed Hierachies, Criticality, Spares & Program)	Q4 17	Q4 19	Q4 17	Q4 19					
	0.0%	0.0%	JDE DATA IMPORT & SETUP									
	0.0%	0.0%	JDE Data Migration & Linkage (REMAINING BOM's, Drawings, Spares, Methods Linkage	Q4 18	Q2 19	Q4 18	Q2 19	Р4				
Rel Engineer		0.0%	Remaining BOM's created	Q4 18	Q2 19	Q4 18	Q2 19					
Rel Engineer		0.0%	Remaining Assembly drawings linked	Q4 18	Q2 19	Q4 18	Q2 19					
Rel Engineer		0.0%	Remaining Maintenance Tactics linked	Q4 18	Q2 19	Q4 18	Q2 19					
Rel Engineer		0.0%	Remaining Critical spares linked	Q4 18	Q2 19	Q4 18	Q2 19					
Rel Engineer		0.0%	Remaining Work Methods linked	Q4 18	Q2 19	Q4 18	Q2 19					
Rel Engineer		0.0%	Remaining Mapped to Nalcor Asset Management Methodologies	Q4 18	Q2 19	Q4 18	Q2 19					
Kei Eligilieer		0.070	Nemaming Mapped to Nation 763et Management Methodologies	Q4 10	Q2 13	Q4 18	Q2 13					
1	18.4% 28.9%	20.1%	BTPO: FINANCE SCOPE									
1 2	18.4% 28.9% 30.5%	20.1% 28.9%		Q2 16	Q2 20	Q2 16	Q2 20					
1 2 3	28.9% 30.5%	20.1% 28.9% 39.5%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS	Q2 16	Q2 20	Q2 16	Q2 20	P2	Q3 18 LIL In Service Minus 1 mth	Q3 18	61	Process
1 2 3 3	28.9% 30.5% 30.6%	20.1% 28.9% 39.5% 39.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup)	Q2 16 Q2 16	Q2 20 Q1 18	Q2 16 Q2 16	Q2 20 Q1 18		Q3 18 LIL In Service Minus 1 mth Q3 18 LIL In Service Minus 1 mth	Q3 18 Q3 18		Process Process
1 2 3 3 3	28.9% 30.5% 30.6% 30.6%	20.1% 28.9% 39.5% 39.0% 39.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup)	Q2 16 Q2 16 Q2 16	Q2 20 Q1 18 Q1 18	Q2 16 Q2 16 Q2 16	Q2 20 Q1 18 Q1 18	Р3	Q3 18 LIL In Service Minus 1 mth	Q3 18	61	Process
1 2 3 3 3 3 2	28.9% 30.5% 30.6% 30.6% 25.0%	20.1% 28.9% 39.5% 39.0% 39.0% 57.3%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup)	Q2 16 Q2 16	Q2 20 Q1 18	Q2 16 Q2 16	Q2 20 Q1 18	Р3	-		61	
1 2 3 3 3 2	28.9% 30.5% 30.6% 30.6%	20.1% 28.9% 39.5% 39.0% 39.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets)	Q2 16 Q2 16 Q2 16	Q2 20 Q1 18 Q1 18 Q4 17	Q2 16 Q2 16 Q2 16 Q2 16	Q2 20 Q1 18 Q1 18	P3 P4	Q3 18 LIL In Service Minus 1 mth	Q3 18	61	Process
1 2 3 3 3 2	28.9% 30.5% 30.6% 30.6% 25.0%	20.1% 28.9% 39.5% 39.0% 39.0% 57.3% 3.5%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS	Q2 16 Q2 16 Q2 16 Q4 16	Q2 20 Q1 18 Q1 18	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17	Q2 20 Q1 18 Q1 18 Q3 17	P3 P4 P2	Q3 18 LIL In Service Minus 1 mth	Q3 18	61	Process Process
1 2 3 3 3 2	28.9% 30.5% 30.6% 30.6% 25.0% 1.8% 6.3%	20.1% 28.9% 39.5% 39.0% 39.0% 57.3% 3.5% 12.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCo	Q2 16 Q2 16 Q2 16 Q4 16 Q2 17	Q2 20 Q1 18 Q1 18 Q4 17	Q2 16 Q2 16 Q2 16 Q2 16	Q2 20 Q1 18 Q1 18 Q3 17	P3 P4 P2 P3	Q3 18 LIL In Service Minus 1 mth	Q3 18	61	Process Process
1 2 3 3 3 2	28.9% 30.5% 30.6% 30.6% 25.0% 1.8% 6.3% 0.0%	20.1% 28.9% 39.5% 39.0% 57.3% 3.5% 12.0% 0.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCo LILGPCo	Q2 16 Q2 16 Q2 16 Q4 16 Q2 17 Q3 17	Q2 20 Q1 18 Q1 18 Q4 17 Q2 18 Q3 18	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17 Q3 17	Q2 20 Q1 18 Q1 18 Q3 17 Q2 18 Q3 18	P3 P4 P2 P3	Q3 18 LIL In Service Minus 1 mth	Q3 18	61	Process Process Process
1 2 3 3 3 2	28.9% 30.5% 30.6% 30.6% 25.0% 1.8% 6.3%	20.1% 28.9% 39.5% 39.0% 57.3% 3.5% 12.0% 0.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCo LILGPCo MFCo	Q2 16 Q2 16 Q2 16 Q4 16 Q2 17 Q3 17	Q2 20 Q1 18 Q1 18 Q4 17 Q2 18 Q3 18	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17 Q3 17	Q2 20 Q1 18 Q1 18 Q3 17 Q2 18 Q3 18	P3 P4 P2 P3	Q3 18 LIL In Service Minus 1 mth	Q3 18	61	Process Process Process
1 2 3 3 3 2	28.9% 30.5% 30.6% 30.6% 25.0% 1.8% 6.3% 0.0%	20.1% 28.9% 39.5% 39.0% 57.3% 3.5% 12.0% 0.0% 2.0% 6.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCO LILGPCO MFCO BTPO: EMERGENCY RESPONSE AND RESTORATION SCOPE BTPO: EMERGENCY RESPONSE & RESTORATION - FIRST POWER PREPARDNESS	Q2 16 Q2 16 Q2 16 Q4 16 Q2 17 Q3 17	Q2 20 Q1 18 Q1 18 Q4 17 Q2 18 Q3 18 Q1 19	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17 Q3 17 Q1 18	Q2 20 Q1 18 Q1 18 Q3 17 Q2 18 Q3 18	P3 P4 P2 P3 P4	Q3 18 LIL In Service Minus 1 mth	Q3 18	61 241	Process Process Process Process Process
1 2 3 3 3 2	28.9% 30.5% 30.6% 25.0% 1.8% 6.3% 0.0% 2.4% 7.0%	20.1% 28.9% 39.5% 39.0% 57.3% 3.5% 12.0% 0.0% 2.0% 6.0% 0.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCo LILGPCo MFCo BTPO: EMERGENCY RESPONSE AND RESTORATION SCOPE	Q2 16 Q2 16 Q2 16 Q4 16 Q2 17 Q3 17 Q1 18	Q2 20 Q1 18 Q1 18 Q4 17 Q2 18 Q3 18	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17 Q3 17	Q2 20 Q1 18 Q1 18 Q3 17 Q2 18 Q3 18 Q1 19	P3 P4 P2 P3 P4	Q3 18 LIL In Service Minus 1 mth Q3 18 LIL In Service Minus 1 mth	Q3 18 Q3 18	61 241	Process Process Process
1 2 3 3 3 2	28.9% 30.5% 30.6% 25.0% 1.8% 6.3% 0.0% 2.4% 7.0%	20.1% 28.9% 39.5% 39.0% 57.3% 3.5% 12.0% 0.0% 0.0% 0.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCo LILGPCo MFCo BTPO: EMERGENCY RESPONSE AND RESTORATION SCOPE BTPO: EMERGENCY RESPONSE & RESTORATION - FIRST POWER PREPARDNESS Soldier's Pond (Risk Assessment & Response Strategy) Identify operational risks	Q2 16 Q2 16 Q2 16 Q4 16 Q2 17 Q3 17 Q1 18	Q2 20 Q1 18 Q1 18 Q4 17 Q2 18 Q3 18 Q1 19 Q1 18 Q4 17	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17 Q3 17 Q1 18 Q3 17 Q3 17	Q2 20 Q1 18 Q1 18 Q3 17 Q2 18 Q3 18 Q1 19 Q1 18 Q4 17	P3 P4 P2 P3 P4	Q3 18 LIL In Service Minus 1 mth Q3 18 LIL In Service Minus 1 mth	Q3 18 Q3 18	61 241	Process Process Process Process Process
1 2 3 3 3 3 2 2 ERR Lead	28.9% 30.5% 30.6% 25.0% 1.8% 6.3% 0.0% 2.4% 7.0%	20.1% 28.9% 39.5% 39.0% 57.3% 3.5% 12.0% 0.0% 2.0% 6.0% 0.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCo LILGPCo MFCo BTPO: EMERGENCY RESPONSE AND RESTORATION SCOPE BTPO: EMERGENCY RESPONSE & RESTORATION - FIRST POWER PREPARDNESS Soldier's Pond (Risk Assessment & Response Strategy)	Q2 16 Q2 16 Q2 16 Q4 16 Q2 17 Q3 17 Q1 18	Q2 20 Q1 18 Q1 18 Q4 17 Q2 18 Q3 18 Q1 19	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17 Q3 17 Q1 18	Q2 20 Q1 18 Q1 18 Q3 17 Q2 18 Q3 18 Q1 19	P3 P4 P2 P3 P4	Q3 18 LIL In Service Minus 1 mth Q3 18 LIL In Service Minus 1 mth	Q3 18 Q3 18	61 241	Process Process Process Process Process
ERR Lead ERR Lead ERR Lead ERR Lead	28.9% 30.5% 30.6% 25.0% 1.8% 6.3% 0.0% 2.4% 7.0% 1.1% 5%	20.1% 28.9% 39.5% 39.0% 57.3% 3.5% 12.0% 0.0% 0.0% 0.0% 0.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCo LILGPCo MFCO BTPO: EMERGENCY RESPONSE AND RESTORATION SCOPE BTPO: EMERGENCY RESPONSE & RESTORATION - FIRST POWER PREPARDNESS Soldier's Pond (Risk Assessment & Response Strategy) Identify operational risks Determine and secure options to leverage Hydro & GE Construction Team Develop & Document the Response Strategy	Q2 16 Q2 16 Q2 16 Q4 16 Q2 17 Q3 17 Q1 18 Q3 17 Q3 17 Q3 17 Q4 17	Q2 20 Q1 18 Q1 18 Q4 17 Q2 18 Q3 18 Q1 19 Q1 18 Q4 17 Q4 17 Q1 18	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17 Q3 17 Q1 18 Q3 17 Q3 17 Q3 17 Q4 17	Q2 20 Q1 18 Q1 18 Q3 17 Q2 18 Q3 18 Q1 19 Q1 18 Q4 17 Q4 17 Q1 18	P3 P4 P2 P3 P4	Q3 18 LIL In Service Minus 1 mth Q3 18 LIL In Service Minus 1 mth	Q3 18 Q3 18	-8	Process Process Process Process Process
ERR Lead ERR Lead ERR Lead ERR Lead	28.9% 30.5% 30.6% 25.0% 1.8% 6.3% 0.0% 2.4% 7.0% 1.1% 5%	20.1% 28.9% 39.5% 39.0% 57.3% 3.5% 12.0% 0.0% 0.0% 0.0% 11.3%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCO LILGPCO MFCO BTPO: EMERGENCY RESPONSE AND RESTORATION SCOPE BTPO: EMERGENCY RESPONSE & RESTORATION - FIRST POWER PREPARDNESS Soldier's Pond (Risk Assessment & Response Strategy) Identify operational risks Determine and secure options to leverage Hydro & GE Construction Team Develop & Document the Response Strategy Overland Transmission (Risk Assessment & Response Strategy)	Q2 16 Q2 16 Q2 16 Q4 16 Q4 16 Q2 17 Q3 17 Q1 18 Q3 17 Q3 17 Q3 17 Q4 17	Q2 20 Q1 18 Q1 18 Q4 17 Q2 18 Q3 18 Q1 19 Q1 18 Q4 17 Q4 17 Q4 17 Q1 18 Q1 18	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17 Q3 17 Q1 18 Q3 17 Q3 17 Q3 17 Q4 17	Q2 20 Q1 18 Q1 18 Q3 17 Q2 18 Q3 18 Q1 19 Q1 18 Q4 17 Q4 17 Q1 18 Q1 18	P3 P4 P2 P3 P4	Q3 18 LIL In Service Minus 1 mth Q3 18 LIL In Service Minus 1 mth Q1 18 SOPTS & SOPCS In Service	Q3 18 Q3 18	-8	Process Process Process Process Process
ERR Lead ERR Lead ERR Lead ERR Lead	28.9% 30.5% 30.6% 25.0% 1.8% 6.3% 0.0% 2.4% 7.0% 1.1% 5%	20.1% 28.9% 39.5% 39.0% 57.3% 3.5% 12.0% 0.0% 0.0% 0.0% 0.0%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCO LILGPCO MFCO BTPO: EMERGENCY RESPONSE AND RESTORATION SCOPE BTPO: EMERGENCY RESPONSE & RESTORATION - FIRST POWER PREPARDNESS Soldier's Pond (Risk Assessment & Response Strategy) Identify operational risks Determine and secure options to leverage Hydro & GE Construction Team Develop & Document the Response Strategy Overland Transmission (Risk Assessment & Response Strategy) Develop, release and award contract to preferred contractor	Q2 16 Q2 16 Q2 16 Q4 16 Q2 17 Q3 17 Q1 18 Q3 17 Q3 17 Q3 17 Q4 17 Q2 17 Q2 17	Q2 20 Q1 18 Q1 18 Q4 17 Q2 18 Q3 18 Q1 19 Q1 18 Q4 17 Q4 17 Q1 18 Q1 18 Q1 18	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17 Q3 17 Q1 18 Q3 17 Q3 17 Q4 17 Q2 17	Q2 20 Q1 18 Q1 18 Q3 17 Q2 18 Q3 18 Q1 19 Q1 18 Q4 17 Q4 17 Q1 18 Q1 18 Q3 17	P3 P4 P2 P3 P4	Q3 18 LIL In Service Minus 1 mth Q3 18 LIL In Service Minus 1 mth Q1 18 SOPTS & SOPCS In Service	Q3 18 Q3 18	-8	Process Process Process Process Process
ERR Lead ERR Lead ERR Lead ERR Lead	28.9% 30.5% 30.6% 25.0% 1.8% 6.3% 0.0% 2.4% 7.0% 1.1% 5%	20.1% 28.9% 39.5% 39.0% 57.3% 3.5% 12.0% 0.0% 0.0% 0.0% 11.3%	BTPO: FINANCE SCOPE Team Lead - Finance FINANCE - FIRST POWER PREPARDNESS LTCo (Budgets, Asset Records, Operational Structures & Setup) LILGPCo (Budgets, Asset Records, Operational Structures & Setup) MFCo (Budgets) BTPO: FINANCE - FULL POWER PREPARDNESS LTCO LILGPCO MFCO BTPO: EMERGENCY RESPONSE AND RESTORATION SCOPE BTPO: EMERGENCY RESPONSE & RESTORATION - FIRST POWER PREPARDNESS Soldier's Pond (Risk Assessment & Response Strategy) Identify operational risks Determine and secure options to leverage Hydro & GE Construction Team Develop & Document the Response Strategy Overland Transmission (Risk Assessment & Response Strategy)	Q2 16 Q2 16 Q2 16 Q4 16 Q4 16 Q2 17 Q3 17 Q1 18 Q3 17 Q3 17 Q3 17 Q4 17	Q2 20 Q1 18 Q1 18 Q4 17 Q2 18 Q3 18 Q1 19 Q1 18 Q4 17 Q4 17 Q4 17 Q1 18 Q1 18	Q2 16 Q2 16 Q2 16 Q2 16 Q2 17 Q3 17 Q1 18 Q3 17 Q3 17 Q3 17 Q4 17	Q2 20 Q1 18 Q1 18 Q3 17 Q2 18 Q3 18 Q1 19 Q1 18 Q4 17 Q4 17 Q1 18 Q1 18	P3 P4 P2 P3 P4	Q3 18 LIL In Service Minus 1 mth Q3 18 LIL In Service Minus 1 mth Q1 18 SOPTS & SOPCS In Service	Q3 18 Q3 18	-8	Process Process Process Process Process

Resources Actual UPDATE GREEN		WBS L1 WBS L2 WBS L3 WBS L4	Baseline Start Date (Q)	Baseline End Date (Q)	Actual/Forecast Start Date (Q)	Actual/Forecast End Date (Q)	Project Priority	Critical Path	LCP In Service Date (Q)	Float Watch	people/ process/ system/ delivery
EPLA	0.0%	EPLA - Deliver Risk Severity Matrix	Q3 17	Q3 17	Q3 17	Q3 17					
EPLA	0.0%	EPLA - Design Solutions & Present/Select Repair Approach	Q3 17	Q4 17	Q3 17	Q4 17					
EPLA	0.0%	EPLA - Develop and Deliver ERP and Incident Response Plan	Q4 17	Q1 18	Q4 17	Q1 18					
1.1	1% 0.0%	SOBI-Marine Cable (Risk Assessment & Response Strategy)	Q3 17	Q1 18	Q3 17	Q1 18	P3	Q3 18 LIL In Service	Q3 18	121	Processes
ERR Lead 5	5 <mark>%</mark> 0.0%	Identify operational risks	Q3 17	Q4 17	Q3 17	Q4 17					
ERR Lead	0.0%	Develop & Document the Response Strategy	Q4 17	Q1 18	Q4 17	Q1 18					
0.0	0.0%	BTPO: EMERGENCY RESPONSE & RESTORATION - FULL POWER PREPARDNESS / POST C	ONSTRUCTI	ON	-	-	-				
0.0	0.0%	Soldier's Pond (Switchyard, Converter Station & Sync Plant)	Q2 18	Q4 18	Q2 18	Q4 18	Р3				Processes
ERR Lead	0.0%	Develop overall ERM for SOP (site-specific)	Q2 18	Q4 18	Q2 18	Q4 18					
ERR Lead	0.0%	Determine Fire/Emergency Response capability (contract/internal)	Q2 18	Q4 18	Q2 18	Q4 18					
ERR Lead	0.0%	Contract for provision of fire suppression/fire alarm maintenance	Q2 18	Q4 18	Q2 18	Q4 18					
ERR Lead	0.0%	Emergency services tested and validated	Q2 18	Q4 18	Q2 18	Q4 18					
0.0	0.0%	Overland Transmission	Q1 18	Q3 18	Q1 18	Q3 18	P3				Processes
ERR Lead	0.0%	Develop overall ERM for HVDC (site-specific)	Q1 18	Q3 18	Q1 18	Q3 18					
ERR Lead	0.0%	Emergency work at the crew level	Q1 18	Q3 18	Q1 18	Q3 18					
0.0	0.0%	SOBI-Marine Cable	Q1 18	Q3 18	Q1 18	Q3 18	P3				Processes
ERR Lead	0.0%	Spare cable, storage identified, vessels requirements etc	Q1 18	Q3 18	Q1 18	Q3 18					
ERR Lead	0.0%	Develop overall ERM document for SOBI (site-specific)	Q1 18	Q3 18	Q1 18	Q3 18					
0.0	0.0%	MF Generation	Q3 18	Q4 19	Q3 18	Q4 19	P4				Processes
ERR Lead	0.0%	Identify operational risks	Q3 18	Q4 18	Q3 18	Q4 18					
ERR Lead	0.0%	Develop overall ERM document for MF (site-specific)	Q4 18	Q3 19	Q4 18	Q3 19					
ERR Lead	0.0%	Fire/Emergency Response capability determined (contract/internal)	Q3 19	Q4 19	Q3 19	Q4 19					
ERR Lead	0.0%	Contract for provision of fire suppression/fire alarm maintenance	Q3 19	Q4 19	Q3 19	Q4 19					
0.0		Emergency Response Plans - Post Construction Demobilization	Q2 18	Q1 19	Q2 18	Q1 19	Р3				Processes
ERR Lead	0.0%	ERMs written and communicated	Q2 18	Q1 19	Q2 18	Q1 19					
ERR Lead	0.0%	Support agencies "engaged"/contractors	Q2 18	Q1 19	Q2 18	Q1 19					
ERR Lead	0.0%	Incorporated with Corporate Emergency Response Plan (CERP)	Q2 18	Q1 19	Q2 18	Q1 19					
ERR Lead	0.0%	Have tested highest exposure(s)	Q2 18	Q1 19	Q2 18	Q1 19					
ERR Lead ERR Lead	0.0%	Permits issued from NL agencies (where applicable) Supporting resources/equipment acquired	Q2 18	Q1 19	Q2 18	Q1 19					
EKK Leau	0.0%	Supporting resources/equipment acquired	Q2 18	Q1 19	Q2 18	Q1 19					
36.7	7% 37.2%	BTPO: O&M CONTRACTS SCOPE									
58.8		BTPO: O&M CONTRACTS - FIRST POWER PREPARDNESS									
65.3		Operational & Maintenance Contracts (HVdc Expertise, NLH/CF Service Contracts)	Q4 16	Q4 17	Q3 16	Q4 17	P3				Systems
	5% 65.0%	O&M GE GRID (Converter Stations, GIS, Sync Plant)	Q4 16	Q4 17	Q3 16	Q4 17		Q3 18 LIL In Service	Q3 18		Systems
	<mark>0%</mark> 65.0%	O&M ATCO (Operations, Maintenance, Support, Mentoring)	Q4 16	Q4 17	Q1 17	Q4 17		Q3 18 LIL In Service	Q3 18		Systems

Resources	UPDATE GREEN %'s	Expected	WBS L1 WBS L2 WBS L3	Baseline Start Date (Q)	Baseline End Date (Q)	Actual/Forecast Start Date (Q)	Actual/Forecast End Date (Q) Project Priority	Critical Path	LCP In Service Date (Q)	Float Watch	people/ process/ system/ delivery
BTPO Mgr	65%	80.6%	Service Contract NLH	Q1 17	Q3 17	Q1 17	Q4 17 P3	Q1 18 SOPTS & SOPCS In Service	Q1 18	22	Systems
BTPO Mgr	50%	58.6%	Service Contract CF	Q1 17	Q4 17	Q1 17	Q4 17 P3	Q4 17 LTA In Service	Q4 17	-8	Systems
	27.0%	26.1%	Maintenance Support Contracts (Key Maintenance Contracts)	Q3 16	Q1 18	Q3 16	Q1 18 P3	Q3 18 LIL In Service	Q3 18	91	Systems
BTPO Mgr		100.0%	SOBI Cable Storage	Q3 16	Q2 17	Q3 16	Q2 17 P3	Q3 10 L12 III 3C1 116C	Q3 13	31	Systems
ontacts Lead	20070	0.0%	Fibre Repair & Splice	Q3 17	Q1 18	Q3 17	Q1 18 P3				Systems
BTPO Mgr	80%	74.3%	Gases	Q1 17	Q3 17	Q1 17	Q3 17 P3				Systems
ontacts Lead		0.0%	Trash Removal	Q3 17	Q1 18	Q3 17	Q1 18 P3				Systems
ontacts Lead		0.0%	Fire Panels, Alarms, Supression	Q3 17	Q1 18	Q3 17	Q1 18 P3				Systems
Contacts Lead		0.0%	Snow Clearing	Q3 17	Q1 18	Q3 17	Q1 18 P3				Systems
ontacts Lead		0.0%	Janitorial	Q3 17	Q1 18	Q3 17	Q1 18 P3				Systems
	0.00/	0.09/	BTPO: O&M CONTRACTS - FULL POWER PREPARDNESS								
	0.0% 0.0%	0.0%	Maintenance Support Contracts	Q3 17	Q2 20	Q3 17	Q2 20 P3				Systems
ontacts Lead	0.070	0.0%	Diesel Generators	Q3 17 Q3 17	Q1 18	Q3 17 Q3 17	Q1 18 P3				Systems
ontacts Lead		0.0%	Communications & Security	Q3 17	Q1 18	Q3 17	Q1 18 P3				Systems
ontacts Lead		0.0%	Site Manned Security	Q3 17	Q2 18	Q3 17	Q2 18 P3				Systems
ontacts Lead		0.0%	Road Mtn (Access Roads)	Q3 17	Q2 18	Q3 17	Q2 18 P3				Systems
ontacts Lead		0.0%	Road Mtn (Right of Way)	Q3 17	Q1 19	Q3 17	Q1 19 P4				Systems
ontacts Lead		0.0%	Pest Control	Q3 17	Q2 18	Q3 17	Q2 18 P3				Systems
ontacts Lead		0.0%	Trucking & Transportation	Q3 17	Q2 18	Q3 17	Q2 18 P3				Systems
ontacts Lead		0.0%	SOBI Cable (ROV, Diving)	Q3 17	Q2 18	Q3 17	Q2 18 P3				Systems
ontacts Lead		0.0%	SOBI Cable (Storage Equipment)	Q3 17	Q2 19	Q3 17	Q2 19 P4				Systems
ontacts Lead		0.0%	Elevator	Q3 17	Q4 18	Q3 17	Q4 18 P4				Systems
ontacts Lead		0.0%	Inventory	Q3 17	Q2 18	Q3 17	Q2 18 P4				Systems
Contacts Lead		0.0%	Crane & Hoist	Q3 17	Q2 18	Q3 17	Q2 18 P3				Systems
ontacts Lead		0.0%	HVAC	Q3 17	Q1 18	Q3 17	Q1 18 P3				Systems
ontacts Lead		0.0%	Pressure Vessels	Q3 17	Q2 18	Q3 17	Q2 18 P3				Systems
ontacts Lead		0.0%	Oil Removal	Q3 17	Q2 18	Q3 17	Q2 18 P3				Systems
ontacts Lead		0.0%	Vehicle Maintenance	Q3 17	Q2 19	Q3 17	Q2 19 P4				Systems
ontacts Lead		0.0%	Helicopter Service	Q3 17	Q2 19	Q3 17	Q2 19 P4				Systems
ontacts Lead		0.0%	Fish Monitoring	Q3 17	Q2 19	Q3 17	Q2 19 P4				Systems
ontacts Lead		0.0%	Overhead Doors	Q3 17	Q2 20	Q3 17	Q2 20 P4				Systems
ontacts Lead		0.0%	Vegetation Management	Q3 17	Q2 20	Q3 17	Q2 20 P4				Systems
ontacts Lead		0.0%	Dams & Dykes	Q3 17	Q2 20	Q3 17	Q2 20 P4				Systems
ontacts Lead		0.0%	Office Space 33 Corp EES	Q3 17	Q1 18	Q3 17	Q1 18 P3				Systems
ontacts Lead		0.0%	Office Space 40 Eng EES	Q3 17	Q1 18	Q3 17	Q1 18 P3				Systems
ontacts Lead		0.0%	Office Space Ops Staff	Q3 17	Q1 18	Q3 17	Q1 18 P3				Systems
ontacts Lead		0.0%	Other	Q3 17	Q2 20	Q3 17	Q2 20 P3				Systems
	1.2% 3.8%	1.3% 4.0%	BTPO: INVENTORY AND SPARES SCOPE BTPO: INVENTORY - FIRST POWER PREPARDNESS								

Resources Actual	UPDATE GREEN %'s	Expected	WBS L1 WBS L2 WBS L3 WBS L4	Baseline Start Date (Q)	Baseline End Date (Q)	Actual/Forecast Start Date (Q)	Actual/Forecast End Date (Q)	Project Priority	Critical Path	LCP In Service Date (Q)	Float Watch	people/ process/ system/ delivery
	3.8%	4.0%	Interim Inventory & Spares Storage Arrangements	Q1 17	Q1 18	Q1 17	Q1 18	Р3	Q3 18 LIL In Service	Q3 18	91	Systems
BTPO Mgr	75%	80.6%	Perform Foundational Assessment for Interim Arrangements	Q1 17	Q3 17	Q1 17	Q3 17					
Spares Lead		0.0%	Review existing construction storage locations	Q3 17	Q1 18	Q3 17	Q1 18					
Spares Lead		0.0%	Catalog existing infrastructure in terms of attributes	Q1 18	Q1 18	Q1 18	Q1 18					
Spares Lead		0.0%	Secure interim storage arrangements (plans/facilities) for inventory/spares in each loc	Q1 18	Q1 18	Q1 18	Q1 18					
	3.8%	4.0%	Long Term Inventory & Spares Storage Arrangements	Q1 17	Q1 18	Q1 17	Q1 18	Р4	Q3 18 LIL In Service	Q3 18	91	Systems
Spares Lead	75%	80.6%	Perform Foundational Assessment for Long Term Arrangements	Q1 17	Q3 17	Q1 17	Q3 17					
Spares Lead		0.0%	Obtain recommendations on spares storage for SOP from GE	Q3 17	Q4 17	Q3 17	Q4 17					
Spares Lead		0.0%	Develop recommendations/options for the long term	Q4 17	Q1 18	Q4 17	Q1 18					
	0.0%	0.0%	BTPO: INVENTORY - FULL POWER PREPARDNESS									
	0.0%	0.0%	Long Term Inventory & Spares Storage Arrangements	Q1 18	Q4 19	Q1 18	Q4 19	P4				Systems
Spares Lead		0.0%	Develop & Document Storage Strategy for Churchill Falls	Q1 18	Q2 18	Q1 18	Q2 18					
Spares Lead		0.0%	Develop & Document Storage Strategy for LTA	Q1 18	Q2 18	Q1 18	Q2 18					
Spares Lead		0.0%	Develop & Document Storage Strategy for LIL (Island)	Q1 18	Q3 18	Q1 18	Q3 18					
Spares Lead		0.0%	Develop & Document Storage Strategy for LIL (Labrador)	Q1 18	Q3 18	Q1 18	Q3 18					
Spares Lead		0.0%	Develop & Document Storage Strategy for SOBI	Q1 18	Q3 18	Q1 18	Q3 18					
Spares Lead		0.0%	Develop & Document Storage Strategy for Soldiers Pond	Q1 18	Q3 18	Q1 18	Q3 18					
Spares Lead		0.0%	Develop & Document Storage Strategy for Telecom	Q1 18	Q3 18	Q1 18	Q3 18					
Spares Lead		0.0%	Analyze potential long term storage locations beyond existing locations	Q1 18	Q3 18	Q1 18	Q3 18					
Spares Lead		0.0%	Develop & Document Storage Strategy for Muskrat Falls	Q2 18	Q4 19	Q2 18	Q4 19					
Spares Lead		0.0%	Preservation routines for capital spares	Q2 18	Q4 19	Q2 18	Q4 19					
	1.8%	1.9%	BTPO: WORK PROTECTION & SAFETY SCOPE									
	1.8%	1.9%	Work Protection & Safety	Q1 17	Q4 19	Q1 17	Q4 19	P2				Process
Safety Lead	75%	80.6%	Perform Foundational Activities for Work Protection & Safety for First Power	Q1 17	Q3 17	Q1 17	Q3 17	Р3	Q1 18 SOPTS & SOPCS In Service Minus 4 mths	Q1 18	22	Process
Safety Lead	0%	0.0%	Limits of Approach	Q3 17	Q4 18	Q3 17	Q4 18	Р3				Process
Safety Lead	0%	0.0%	Live Line Work Ready	Q3 17	Q4 19	Q3 17	Q4 19	Р3				Process
Safety Lead	0%	0.0%	Electronic Work Protection	Q3 17	Q4 18	Q3 17	Q4 18	Р3				Process
Safety Lead	0%	0.0%	Haz Ops (converters, GIS stations, sync plant, +20m heights)	Q3 17	Q4 18	Q3 17	Q4 18	Р4				Process
Safety Lead	0%	0.0%	WHIMIS Standard/Labelling (Assessments for all Sites)	Q3 17	Q3 19	Q3 17	Q3 19					Process
Safety Lead	0%	0.0%	Evacuation Plans (Developed for all Sites)	Q3 17	Q4 19	Q3 17	Q4 19	P4				Process
Safety Lead	0%	0.0%	Operations First Aid Readiness (Assessment completed for all Sites)	Q3 17	Q3 19	Q3 17	Q3 19					Process
Safety Lead	0%	0.0%	Integrate Emergency Response Plans into CERP (all sites)	Q3 17	Q3 19	Q3 17	Q3 19					Process
Safety Lead	0%	0.0%	Special Safety Systems (Developed for all Sites)	Q3 17	Q3 19	Q3 17	Q3 19	DΛ				Process

	% Comp	aloto			Baseline (by Q) Forecast (by Q)						Page 15 01 19	
		piete			Daseiiii	<u>ε (by Q)</u> Ι	Foreca	at (by Q)				
Resources	Actual UPDATE GREEN %'s	Expected	WBS L1 WBS L2	WBS L3	Baseline Start Date (Q)	Baseline End Date (Q)	Forecast (by Q)	Actual/Forecast End Date (Q)	Project Priority	Critical Path	LCP In Service Date (Q)	System/ delivery
	72.5%	82.2%	RFC	I SCOPE								
	51.2%	51.2%	RI	FCI Governance & Oversight		Q4 18		Q4 18	P4			Process
RFCI Mgr	51.2%	51.2%		Mgmt, Mtgs, Reporting, Review for RFCI Lead	Q1 16	Q4 18	Q1 16	Q4 18				
	76.6%	88.0%	A	greements - Sumamry Level (Commercial, Regulatory, Open Acess, Legislative)	-	Q4 18	-	Q4 19	P4			Process
RFCI Mgr	79.3%	98.2%		Commercial - Generation Production Optimization	Q1 15	-	-	Q4 19	P4			Process
RFCI Mgr	88.7%	99.6%		Emera Agreements	Q2 15	Q4 18	-	Q4 18	P4			Process
RFCI Mgr	63.5%	60.0%		Government Legislation Support	Q1 15			Q2 18	P4	Q3 18 LIL In Service	Q3 18	1 Process
RFCI Mgr	96.8%	98.0%		Rates & Regulatory Preparation	•	Q4 17	•	Q3 17	P4	Q3 18 LIL In Service	-	271 Process
RFCI Mgr	81.4%	99.8%		Transmission Regime and Open Access	-	Q3 17	-	Q4 17	P4	Q3 18 LIL In Service	-	181 Process
RFCI Mgr	2.5%	19.0%		CF Commercial Arrangements	Q3 17	Q3 17	Q3 17	Q3 17	P4	Q3 18 LIL In Service	Q3 18	271 Process
	76.60/	00.00/		and a month listing (from DECLANCY deliverables listing)	01.15	04.10	01.15	04.10	D4			Dunana
DECL Max	76.6% 20.0%	88.0% 100.0%	A	greement Listing (from RFCI Mgr deliverables listing)	Q1 15	Q4 18 Q4 15		Q4 19 Q2 18	P4			Process
RFCI Mgr				Power Supply Power Purchase and Optimization Agreement Heads of Agreement Power Supply Power Purchase and Optimization Agreement	Q1 15			Q2 18 Q3 17				
RFCI Mgr	75.0%			Heads of Agreement - Power Supply Power Purchase and Optimization Agreement Metering and Measuring Standards - Transmission Losses	Q4 15	Q1 16		_				
RFCI Mgr	100.0%			Metering and Measuring Standards - Transmission Losses Regulation Service Agreement		Q4 15		Q3 15				
RFCI Mgr	75.0%			Regulation Service Agreement Strike Interconnection Operators Committee Interconnection Operators Com	Q2 15		Q2 15	Q4 17				
RFCI Mgr	100.0%			Strike Interconnection Operators Committee - mandate to deliver IOA related deliverables IOA - ML Transmission Procedures	Q2 15	Q1 15		Q1 16 Q3 17				
RFCI Mgr	99.0%				Q2 15	Q2 16		_				
RFCI Mgr	85.0%			IOA - Reserve Sharing Agreement / Arrangement	Q2 15	Q3 15 Q2 16		Q3 17 Q3 17				
RFCI Mgr	99.0%			IOA - Description of Interconnection Facilities		Q2 16 Q2 16		Q3 17 Q3 17				
RFCI Mgr RFCI Mgr	99.0% 70.0%			IOA - Functional Operating Relationship IOA - Operating Instructions	Q2 15 Q2 15	Q2 16 Q2 16	-	Q3 17 Q3 17				
		100.0%										
RFCI Mgr RFCI Mgr	100.0%	0.0%		IOA - Participation in Reliability Assessment Program (Transmission) IOA - Participation in Reliability Assessment Program (Generation)		Q2 10 Q4 18	Q2 15	Q3 17 Q4 18				
RFCI Mgr	95.0%			ML TSA Scheduling Process		Q2 16		Q4 18 Q3 17				
RFCI Mgr	30.0%			Develop Scheduling Protocol - MF PPA		Q1 17		Q3 17 Q3 17				
RFCI Mgr		0.0%		Determination of Service Life of LIL by PUB or Authorized Authority (per LIL Partnership Agreement)		Q1 17 Q4 18		Q3 17 Q4 18				
RFCI Mgr				Pre-Muskrat Falls Power Arrangements with Hydro		Q2 16		Q4 17				
iti Ci ivigi	75.070	100.070		Commercial arrangement to access power - Nova Scotia - for 2017 prior to in-service of Muskrat and upon in-		Q2 10	Q+ 13	Q+17				
RFCI Mgr	100.0%	100.0%		service of new transmission		Q3 16	O4 15	Q2 17				
RFCI Mgr	100.0%			Identification of Operational Accountability (RFCI Agreements)		Q1 16		Q2 16				
RFCI Mgr		100.0%		Assign Execution Accountables for RFCI Deliverables		Q2 16		Q2 16				
RFCI Mgr				Compliance Action List - MPPA, AIA and TOA	Q1 17	Q3 17		Q3 17				
RFCI Mgr	100.0%			NERC/NPCC MOU Decision	-	Q2 16		Q2 16				
RFCI Mgr		100.0%		NERC - Gap analysis and gap closure plan		Q2 15		Q2 17				
RFCI Mgr	100.0%			C.A. Energy Review of Nalcor contract package		Q2 15		Q2 17 Q2 15				
RFCI Mgr		100.0%		C.A. Energy illustration of transmission transactions		Q2 15		Q4 16				
RFCI Mgr	100.0%			Marginal Cost Study - Part 1		Q4 15		Q4 15				
RFCI Mgr				Marginal Cost Study - Part 2		Q1 16		Q1 16				
RFCI Mgr		100.0%		COS Methodology Study		Q1 16		Q1 16				
RFCI Mgr		100.0%		Rate Design Review		Q2 16		Q2 16				
RFCI Mgr		100.0%		Supply Cost Recovery Mechanisms Report		Q2 16		Q2 16				
				Taller, Taller, I manifement makes	~0	~0	~	~				

Resources	Actual UPDATE GREEN %'s	Expected	WBS L1 WBS L2 WBS L3	Baseline Start Date (Q)	Baseline End Date (Q)	Forecast (by Q)	Actual/Forecast End Date (Q)	Project Priority	Critical Path	LCP In Service Date (Q)	1 10 1	ople/ process/ stem/ delivery
RFCI Mgr	100.0%	100.0%	Modeling - postage stamp rates	Q1 15	Q2 15	Q1 15	Q2 16					
RFCI Mgr		100.0%	NL Transmission Planning Program	Q1 16	-		Q3 17					
RFCI Mgr	100.0% 100.0%	100.0% 100.0%	NL System Performance Standards	Q1 16	-	Q1 16	Q4 16 Q2 15					
RFCI Mgr RFCI Mgr		100.0%	Asset Interconnection Agreement - Emera, NLH as Transmission Owner Multi-Party Pooling Agreement	Q1 15	Q1 15 Q1 15		Q2 15 Q2 15					
RFCI Mgr	100.0%	100.0%	Letters for transmission owners to join MPPA	Q1 15 Q4 15	Q1 15 Q4 15		Q2 15 Q4 16					
RFCI Mgr	100.0%	100.0%	Confirmation of Operating Procedures - Existing Transmission System	Q4 13 Q2 15	-	Q4 13 Q2 15	Q4 10 Q4 15					
RFCI Mgr	100.0%	100.0%	Transmission Operating Agreement (NL)	Q2 13 Q1 15	Q2 13 Q1 15	-	Q4 15 Q2 15					
RFCI Mgr	90.0%	100.0%	NL Interconnection Agreement #1	Q3 15	Q1 16		Q2 13 Q3 17					
RFCI Mgr			NL Interconnection Agreement #2	Q3 15	Q1 16		Q3 17					
RFCI Mgr		100.0%	NL Interconnection Agreement #3	Q3 15			Q4 17					
RFCI Mgr	99.0%	100.0%	Transmission Service Agreement #1	Q2 15	-	Q2 15	Q3 17					
RFCI Mgr	100.0%	100.0%	Transmission Service Agreement #2	Q2 15	-	Q2 15	Q2 15					
RFCI Mgr	100.0%	100.0%	Transmission Service Agreement #3	Q2 15	Q3 15	Q2 15	Q2 15					
RFCI Mgr	99.0%	100.0%	Transmission Service Agreement #4	Q2 15	Q3 15	Q2 15	Q3 17					
RFCI Mgr	100.0%	100.0%	Letter to CF(L)Co requesting participation in the MPPA	Q4 15	Q4 15	Q4 15	Q1 16					
RFCI Mgr	70.0%	100.0%	NLH system of accounts to account for NLSO costs and establish allocators for G&A costs	Q1 16	Q2 16	Q1 16	Q3 16					
RFCI Mgr	10.0%	87.5%	Interconnection Operators Agreement - HQ and NLH	Q1 16	Q3 17	Q1 16	TBD					
RFCI Mgr	30.0%	100.0%	Execution of MPPA (Tx SPVs)	Q1 17	Q2 17	Q1 17	Q4 17					
RFCI Mgr	30.0%	100.0%	Execution of MPPA (NLH as transmission owner)	Q1 17	Q2 17	Q1 17	Q4 17					
RFCI Mgr	100.0%	100.0%	Transmission Operator Agreement	Q1 15	Q4 15	Q1 15	Q2 16					
RFCI Mgr	100.0%	100.0%	Intercompany Code of Conduct	Q2 15	Q2 16	Q2 15	Q3 17					
RFCI Mgr	60.0%	100.0%	NL System Operating Procedures	Q2 15	Q4 16	Q2 15	Q4 17					
RFCI Mgr	95.0%	100.0%	Process for Obtaining and Administering Transmission Service	Q2 15	Q2 16	-	Q3 17					
RFCI Mgr	0.0%	19.0%	Modify delivery point for recall - use of LTA wires to deliver to HVGB - commercial agreement	Q3 17	Q3 17	Q3 17	Q3 17					
			Exchange of letters between CF(L)Co and NLH - supply of construction power (recall) - new delivery point at									
RFCI Mgr	5.0%	19.0%	CF 735Kv bus	Q3 17	Q3 17	Q3 17	Q3 17					

	% Com	plete		Baselin	e Dates	Actual/	Forecast			
Resources	Actual UPDATE GREEN %'s	Expected	WBS L1 WBS L3 WBS L4	Baseline Start Date (Q)	Baseline End Date (Q)	Forecast (by Q)	Actual/Forecast End Date (Q)	Project Priority	LCP In Service Date (Q)	people/ process/ system/ delivery
	30.3%	31.4%	RFO SCOPE							
	44.9%	44.9%	RFO Governance & Oversight	Q2 15	Q1 20	Q2 16	Q1 20	P2		Delivery
RFO Mgr	44.9%	44.9%	Mgmt, Mtgs, Reporting, Review for RFO Lead	Q2 15	Q1 20	Q2 15	Q1 20			
	26.4%	27.8%	Completions & PCS Data Loading (Commissioning, Testing, As Built Drawing Records)	Q1 15	Q1 20	Q1 15	Q1 20	P2		Delivery
LCP Team	37.9%	48.4%	PCS Data Loading	Q3 15	Q4 19	Q3 15	Q4 19			
LCP Team	74.6%	79.1%	Completion Team (Plans, Personnel, Descriptions)	Q2 15	Q4 18	Q2 15	Q4 18			
LCP Team	60.0%	82.2%	Develop turnover process	Q3 15	Q4 17	Q3 15	Q4 17			
LCP Team	0.0%	91.6%	Prepare and issue Completions Implementation Plans for Components	Q1 15	Q3 17	Q1 15	Q3 17			
LCP Team	82.0%	36.0%	Revise Completions execution plan	Q4 16	Q4 18	Q4 16	Q4 18			
LCP Team	100.0%	100.0%	Roll out the Completion process to Alstom	Q3 15	Q1 17	Q3 15	Q1 17			
LCP Team	100.0%	100.0%	PCS Start of Contractor Rollout C3	Q4 15	Q1 17	Q4 15	Q1 17			
LCP Team	91.0%	84.8%	Prepare and issue RFP for Commissioning services contract	Q1 16	Q3 17	Q1 16	Q3 17			
LCP Team		77.3%	Revise & Re-issue Completions & Project RFO Execution Plan	Q3 16	Q4 17	Q3 16	Q4 17			
LCP Team	85.0%	81.5%	Roll out the Completion process to Andritz	Q3 15	Q4 17	Q3 15	Q4 17			
LCP Team	76.0%	58.2%	PCS Training	Q3 15	Q4 18	Q3 15	Q4 18			
LCP Team	0.0%	0.0%	Project acceptance scope handover complete	Q4 19	Q1 20	Q4 19	Q1 20			
LCP Team	0.0%	0.0%	Verification of all O&M information & As - built delivery	Q3 19	Q1 20	Q3 19	Q1 20			
LCP Team	0.0%	0.0%	All turnovers complete ready for project acceptance	Q3 19	Q1 20	Q3 19	Q1 20			

	Tra	ansition To Operations 2	017 Road Map		
	Q2 Objectives	Action Items	Status Notes	Overall % Complete	Q2 Delivery
	Support completion of energization pre-requisites for SOP TS (TL217/265 & TL242/268)		ation Plan Signed off; Commissioning plan P station service agreed and in progress. Interfaces response completed.	34.3%	Q2 objectives met
l ≿	Prepare and enable NLH team to maintain & operate SOPTS	initiated; GEGrid and ATCO service offering Delineation of NLH/Pwr Supply O&M r mechanical tech positions secured; NERC tr on t	esponsibilities at SOP in progress; Two aining initiated; NL Gap Closures principally rack	overall completion on plan objectives at 36.9%	Q2 objectives principally met NLSO indicates ~90-95% readiness TRO indicates ~95% readiness
าร	Deliver Remaining Q2 TTO Outcomes	lagging; BTPO principally on track but sor	terfaces and NERC standards development ne team hires lagging (5 of 13 BTPO team gression for Q2 outcomes partially met		Q2 outcomes for remaining TTO scope partially met.
	Continue to execute and deliver objectives of the FY2017 RFO plan	Complete PCS training for 'Transmission' Team and contractors	Training completion delayed - awaiting C3 & GE completions team hiring	30.5% overall completion	Overall RFO Q2 objectives met PCS training ongoing and pending team hires
~		Re-issue Completions Execution Plan	Due to project re org this item has been moved to Q3	on plan of 31.7%	Overall RFO Q2 objectives met Completions execution plan to be delivered in Q3 not Q2
	objectives of the FY2017 BTPO plan NLH ready to maintain and operate	PEOPLE: Staff BTPO Team; Ratify O&M Team & Org Chart; Staff 10% of maintenance and operations personnel	All 13 BTPO positions posted, 5 offers accepted; 2 O&M staff placed and 18 positions posted and in active recruitment	19.8% overall	Q2 objectives partially met (BTPO recruitment lagging)
	SOP AC TS	FINANCE: Advance 35yr/50yr LTAMP; Complete draft of O&M agreements between Nalcor and NLH and Nalcor and CF(L)Co	LTAMP: 50% completed (+10% over May) Contract: Nalcor-NLH sample O&M contract drafted.	completion on plan of 20.5%	Q2 objectives partially met (LTAMP completion in Q3, NLH/CFLCo O&M contract lagging)
втро		ASSETS: Complete high level asset hierarchies & sanction structure	Hierachy agreed. High Level Hierachy Completed	Plan reset for phased	Q2 objectives met
		ERR: Release RFP for Overland transmission and restoration support	OHTL RFP awarded and kick-off with contractor held	approach objectives and	Q2 objectives met
		OM&A CONTRACTS: Complete 4 of 6 contract drafts required for FY2017	One contract completed and secured, one contract principally drafted, four others at 60% draft	BTPO team start dates	Q2 objectives principally met (one contract ahead of schedule, remaining 3 for Q2 in draft)
	requirements for CF Ext, CF TS2, MF TS, MF CS	STUDIES: Complete operational system studies for ML + interconnected system, CF + LTA, CF+LTA+LIL, MATPC reserve and emergency sharing & under frequency load shedding	review. ML+ LIL study at 70% completion		Q2 objectives partially met. Operational studies moved to Q3 and Q4 completion. Under frequency load shedding study moved to FY2018.
	RFI work plan for FY2017	GEP STUDIES: Complete energization system studies for CFExt, CFTS2, MF TS & MF CS	Drafts delivered in June and currently under review	38.1% overall completion	Q2 objectives met
X	·	SOD's: Complete SOD's for BBKTS, GCTTS, USLTS and MFATS2 Shunt Reactor	Completed. Note, updates will be required to all SOD's for ECC.	on plan of 44.2%	Q2 objectives met
		NERC: Complete 3rd party review; Define development scope; Engage contractor; Complete 50% of identified NERC adoption standards for 2017 implementation	Requisition for AESI contract signed off; Project kick-off conducted (scope review, prioritization, schedule, team, next steps)		Q2 objectives partially met (standards development lagging but expected to principally recover by Q4 based on AESI schedule
p ure	·	Define: Systems, process, procedures Deliver training	On track	20.0%	Q2 objectives met and progress at 40% complete overall
Gap Closure		Other Items from Q1 (not completed)	ECC tools & reporting requirements not completed and dependant on ECC procurement/implementation	overall completion	Q2 objectives pending implementation of ECC Open Access Support Tools
	actions related to a comprehensive	Revise RFCI Deliverables Listing as required and establish 2017 % completion required for each deliverable to achieve objective			Q2 objectives met
_	οριππεαιιοπ	Complete 50% of the efforts associated with the open access initiative	Transmission regime and open access items work in progress	72.3% overall completion	Q2 objectives partially met
RFC		From Q1: Present comprehensive strategy to the Province	Meeting held June 23 to discuss preparation/schedule	on plan of 81.1%	Q2 objectives partially met.
	Achieve 50% completion of 2017 deliverables related to commercial agreements with Emera as specified in the RFCI Deliverables Listing	Complete Q2 planned deliverables	Progress being made but challenges exist to complete all requirements.		Q2 objectives partially met

TTO Assumptions

TTO Overall

Scope divided into a) critical requirements for first power preparedness and b) remaining activities for full power preparedness

RFI Assumptions

Studies

GE & ABB meet delivery schedules for submission of studies to review

Review of HQT study dependent on completion of study by HQT

Delivery of operational studies dependent on engagement with 3rd party contractor

Delivery of grid energization studies dependent on engagement with 3rd party contractor

Studies subject may require amendments for unforeseen system design changes

Point Lists

Completion of points list dependent on information provided by contractor

Grid Energization Procedures

Delivery of GEP for HVdc components subject to supply of contractor procedures

RTDS & Simulation

Completion of RTDS simulation dependent on contractor readiness (Series V, RTDS setup)

Witness and verification activities dependent on contractor delivery schedule

NERC

Delivery of NERC standards dependent on engagement with 3rd party contractor

BTPO Assumptions

Overall

Delivery of scope dependent on recruitment of BTPO Team hires/contract resources

People

O&M recruitment dependent on CBA, ELAC, IBA agreements

O&M recruitment based primarily on new market hires rather than internal hires

O&M recruitment based on interim supports from 3rd party contractors (GE Grid, ATCO)

Assets

First power preparedness scope limited to high level hierarchies, asset criticality analysis and maintenance program for priority assets only Interim maintenance program based on leveraging OEM, NALCOR/NLH/CFLCo/NSP/SOBI Team routines and procedures

Maintenance program to be executed through services contracts as an interim measure as appropriate until internal resources are hired and trained Asset Hierarchies dependent on receipt of requisite contractor documentation

Interim Maintenance program dependent on receipt of OEM materials (weekly/monthly routines & procedures)

Maintenance program dependent on availability of JDE upgrade

RFCI Assumptions

Activities managed by Nalcor/Hydro resources - dotted line reporting to TTO

RFO Assumptions

Identified scope based on functional management only