Page 1 of :	Page	1	of	•
-------------	------	---	----	---

Q. Please provide the *High Power Operational Studies* as referenced in Volume III, sec. 6.1.1
 A. Please refer to PUB-NLH-003, Attachment 1 "Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation."



Engineering Support Services for: RFI Studies

Newfoundland and Labrador Hydro

Attention: Mr. Rob Collett

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Technical Note: TN1205.62.05 **Date of issue:** November 21, 2018

Prepared By: TransGrid Solutions Inc.

100-78 Innovation Dr. Winnipeg, MB R3T 6C2 CANADA

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 2 of 49



Newfoundland and Labrador Hydro RFI Studies Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Disclaimer

This technical note was prepared by TransGrid Solutions Inc. ("TGS"), whose responsibility is limited to the scope of work as shown herein. TGS disclaims responsibility for the work of others incorporated or referenced herein. This technical note has been prepared exclusively for Newfoundland and Labrador Hydro and the project identified herein and must not be reused or modified without the prior written authorization of TGS.

Revisions

Project Name:	RFI Studies
Document Title:	Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation
Document Type:	Technical Note
Document No.:	TN1205.62.05
Last Action Date:	November 21, 2018

Rev. No.	Status	Prepared By	Checked By	Date	Comments
00	DFC	R. Ostash		May 14, 2018	Preliminary draft Issued for review by Hydro
01	DFC	R. Ostash		June 20, 2018	Draft updated based on comments received from Hydro on May 25, 2018
02	IFC	R. Ostash		June 25, 2018	Updated based on comments received on June 25, 2018. Issued for further comments from Hydro.
03	IFC	R. Ostash		August 17, 2018	Updated based on comments received from Hydro and combined with UFLS study report.
04	IFA	R. Ostash		Sept. 13, 2018	Updated based on comments received from Hydro on August 30, 2018.
05	ABC	R. Ostash		Nov. 21, 2018	Updated based on final comments received from Hydro on November 19, 2018.

i | Page

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 3 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Legend of Document Status:

Approved by Client	ABC	Issued for Approval	IFA
Draft for Comments	DFC	Issued for Information	IFI
Issued for Comments	IFC	Returned for Correction	RFC



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Table of Contents

1.	Exe	cutive Summary	1
1	.1	Introduction	1
1	.2	Conclusions	3
1	.3	Loss of the ML Bipole or Pole	6
2.	Stu	dy Models and Criteria	7
2	.1	Interconnected Island System	7
2	.2	LIL	7
2	.3	Study Criteria	8
2	.4	Contingencies	8
2	.5	PSSE Base Cases	9
3.	Rev	iew of Three-Phase Faults	. 10
3	.1	Considering a 3PF at BDE	10
3	.2	Relaxed Consideration of a 3PF at BDE	16
4.	Loss	of Largest Generator in IIS	
4	.1	LIL in-service	19
4	.2	LIL out-of-service	19
		s of a LIL Pole	
5	.1	During ML Export	
5	.2	During ML Import	22
		s of an ML Pole	
	.1	During ML Export	
	.2	During ML Import	
		of the LIL Bipole	
	.1	Permanent Loss of the LIL Bipole	
	.2	LIL Temporary Bipole Outage	
	Loss .1	of the ML Bipole During ML Export	
	.2	During ML Import	
	Con .1	clusions Conclusions	
	.2	Summary of Technical Issues	
		·	
9.	.3	Next Steps	42

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 5 of 49



Newfoundland and Labrador Hydro RFI Studies Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Appendices

Appendix 1 – Revised UFLS Scheme

List of Figures

Figure 1-1. LIL Transfer limits vs. Island Generation Blue: ML at 157 MW export Orange: ML at 0 MW	5
Figure 2-1. Interconnected Island System 230 kV grid	7
Figure 3-1. 3PF BDE on TL267, Peak load, 840 MW flow eastward out of BDE	11
Figure 3-2. 3PF at BDE on TL267, Intermediate load, 590 MW flow eastward out of BDE	12
Figure 3-3. 3PF at BDE on TL267, Intermediate load, 458 MW flow eastward out of BDE	16
Figure 3-4. 3PF at BDE on TL267, Island demand 1225 MW, LIL out of service	17
Figure 7-1. LIL Transfer limits vs. Island Generation Blue: ML @ 157 MW export Orange: ML @ 0 MW	′ 27
Figure 7-2. Loss of LIL Bipole (Case HP26 with HRD GT on)	28
Figure 7-3. Temporary Loss of LIL Bipole (Case HP27), restart in 300 ms, 59 Hz (no UFLS)	31
Figure 7-4. Temporary Loss of LIL Bipole (Case HP27), restart in 1 second	33
Figure 7-5. Temporary Loss of LIL Bipole (Case HP27), restart in 1 second, no LIL frequency controller	34
Figure 9-1. LIL Transfer limits vs. Island Generation Blue: ML @ 157 MW export Orange: ML @ 0 MW	′39



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Executive Summary

1.1 Introduction

Three previous operational studies were performed to determine the system operating limits of the Newfoundland and Labrador Hydro (Hydro) Island Interconnected System (IIS) for the following periods in time:

- 1. Stage 1: "ML Only" study1; when the Maritime Link (ML) is in-service, but prior to the Labrador Island Link (LIL) coming in to service. The Soldiers Pond (SOP) synchronous condensers were assumed not to be in service.
- 2. Stage 2: "ML and SOP Syncs" study; when the Maritime Link (ML) and the Soldiers Pond (SOP) synchronous condensers are in-service, but prior to the Labrador Island Link (LIL) coming in to service.
- 3. Stage 3: "ML, SOP Syncs and LIL Monopole" study; when the Maritime Link (ML), Soldiers Pond (SOP) synchronous condensers and the LIL as a 225 MW monopole (phased approach) are inservice, but prior to the Muskrat Falls generating units coming in to service.

Stage 4 is the final stage of studies and includes the 900 MW LIL bipole, the Muskrat Falls (MFA) generators, the SOP synchronous condensers and the ML. The Holyrood thermal generators, the Stephenville Gas Turbine, and the Hardwoods Gas Turbine are no longer in-service⁴. Holyrood Unit 3 is operating as a synchronous condenser.

This report addresses technical considerations⁵ identified by the Liberty Consulting Group as part of Phase 2 of the Hearing into Supply Issues and Power Outages on the Island Interconnected System. Specifically, the report addresses the technical considerations that relate to analyses being performed as part of Stage IV of the operational studies. These technical issues are summarized as follows:

- Options (e.g. operating limits) to reduce UFLS
- Re-strikes on the LIL-OHL
- ML-LIL interaction studies
- Bay d'Espoir instability issues
- ML frequency controller study

¹ TN1205.50.04, "Operational Studies: Maritime Link ONLY", TransGrid Solutions, September 8, 2017.

² TN1205.51.03, "Operational Studies: Maritime Link & Soldiers Pond Synchronous Condensers", TransGrid Solutions, November 10, 2017.

³ TN1205.54.03, "Operational Studies: Maritime Link, SOP Syncs and LIL Monopole", TransGrid Solutions, May 18, 2018.

⁴ The Stephenville Gas Turbine and the Hardwoods Gas Turbine are scheduled to be retired in in the early 2020's. This study considers long term operation after these units are no longer in service.

⁵ Second Quarterly Monitoring Report on the Integration of Power Supply Facilities to the Island Interconnected System, The Liberty Consulting Group, Section 6e, The Liberty Consulting Group, May 23, 2018.

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 7 of 49



Newfoundland and Labrador Hydro
RFI Studies

- Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation
- IIS performance with ML in and out of service
- Soldiers Pond site for 4th high inertia synchronous condenser.

This report consists of the following sections to address these items.

1. Review of Three-Phase Faults

This section includes a technical review of impacts of three-phase faults within the eastern portion of the Interconnected Island System (IIS) from Bay d'Espoir to Soldiers Pond⁶. Faults in this area, particularly at Bay d'Espoir, are of interest since they are the most sensitive to angular instability and voltage instability.⁷

2. Loss of the Largest Unit within the IIS

This section investigates loss of the largest generator within the IIS. Frequency controller coordination and LIL operating limits are investigated to ensure that the IIS frequency stays above the 59 Hz in accordance with Transmission Planning Criteria to avoid customer load interruptions.

Loss of a LIL Pole

This section reviews the coordination of frequency controllers, HVdc runbacks and spinning reserves to ensure that the IIS frequency stays above the 59 Hz limit of the Transmission Planning Criteria. LIL operating limits are defined for situations when the ML frequency controller is out of service.

4. Loss of the LIL Bipole

This section determines the modifications required to the present-day UFLS scheme to ensure that the system frequency remains above the 58 Hz limit of the Transmission Planning Criteria. LIL operating limits are defined for various IIS operating conditions.

5. Review of Temporary Bipole Outages

This section reviews the impacts of a temporary LIL bipole outage. Analysis is performed to assess the maximum duration of a LIL bipole outage with a restart that can occur while meeting the 59 Hz criteria and avoiding UFLS. Analysis is also performed to determine the maximum duration of a LIL bipole outage with a restart to ensure the system frequency remains above the 58 Hz limit, as pecified in Transmission Planning Criteria. This section addresses re-strikes on the LIL-OHL.

6. Loss of the ML Bipole or Pole

This section reviews loss of the ML bipole and loss of an ML pole when operating at the 500 MW export limit and the 325 MW import⁸ limit to ensure the Transmission Planning Criteria are met for overfrequency and underfrequency response.

⁶ A complete review of the steady state and transient stability performance of the IIS and the Labrador Transmission System will be performed as part of upcoming analyses to be performed Stage IV operational studies.

⁷ Upgrade the Transmission Line Corridor from Bay d'Espoir to Western Avalon, Hydro, April 28, 2014

⁸ Limit as per Summary of Maritime Link Transfer Capability, Maine & Atlantic Technical Planning Committee, NBP/NLH/NSPI Reserve Study Working Group, April. 2017



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

1.2 Conclusions

The results of the analysis are summarized in the sections below.

1.2.1 Three-Phase Faults near SOP, BDE and the Avalon Peninsula

The analysis included a review of three-phase faults on the 230 kV lines between Bay d'Espoir (BDE) and SOP. It was found that instability resulting from such faults is a function of power flow in this corridor. Preliminary analysis was performed to assess transfer limits, which will be confirmed during the final Stage 4 operational studies⁹. Preliminary results related to the ability to serve Island demand are discussed below for situations when the LIL is in-service and when the LIL is out-of-service.

1) LIL in-service

The preliminary analysis indicates that flow in the BDE to Avalon Peninsula corridor can be restricted to avoid instability from the three-phase faults listed above without impacting the capacity of the transmission system to meet forecasted peak loads and ML export commitments¹⁰ when the LIL is inservice as a bipole or as a monopole.

2) LIL out-of-service

If the LIL is out-of-service, peak Island demand cannot be served. With the LIL out of service, the maximum Island demand that can be served is around 1200 MW if the 3PF at BDE is considered. As noted below, the limitation of power flow from BDE to the Avalon Peninsula is also required to ensure system stability in the event of a loss of the LIL bipole.

In order to be capable of serving higher Island demand without a stability issue under a three-phase fault scenario on TL202, TL206 or TL267 with the LIL out of service, it is likely that either new generation would be required on the Avalon peninsula, that dynamic reactive power support would be required near Sunnyside, or that new AC transmission eastward out of BDE would be needed in order to transfer more generation from the west of the Island to the Avalon Peninsula.

1.2.2 Loss of Largest Unit with the IIS

After retirement of the Holyrood generating units, BDE Unit 7 at 154.4 MW is the largest generator on the Island. Frequency should remain above 59 Hz for loss of BDE Unit 7 to avoid UFLS.

Table 1-1 summarizes the LIL reserve requirements to ensure that loss of the largest generator meets the 59 Hz criteria to avoid UFLS.

Table 1-1. LIL reserve requirements for loss of largest generator

ML Frequency Controller	Reserve required on LIL
In-service	None
Out-of-service	54 MW to 130 MW, depending on system conditions

⁹ Stage 4 studies include a review of the underfrequency load shedding schemes, HVdc runback coordination and frequency controller settings, spinning reserve requirements, and the application of power system stabilizers. Operating limits will be investigated after these other system considerations have been studied.

¹⁰ ML export commitments of 157 MW are assumed to represent the Emera Export Block.

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 9 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

1.2.3 Loss of a LIL Pole

Similar to loss of the largest generator, frequency should remain above 59 Hz for loss of a LIL pole and UFLS should be avoided.

If one of the LIL poles is lost, the remaining pole has an overload rating of 2.0 pu for 10 minutes, after which the rating drops down to a 1.5 pu continuous rating. The reduction in delivered power at SOP following the transition to monopole operation depends on how much power the LIL was transferring prior to loss of the pole. In a worst case, if operating at 900 MW, this study showed that prior to converter transformer tap-changer action and due to increased DC line losses associated with the resistance of the line electrode, the remaining pole is only able to provide 633 MW at Soldiers Pond, as opposed to the 830 MW it was providing pre-contingency, resulting in the net loss of 267 MW to the IIS.

Operating restrictions to keep the IIS frequency above 59 Hz for loss of a LIL pole are summarized in Table 1-2.

Table 1-2. Operating restrictions to ensure loss of LIL pole meets 59 Hz criteria

Table I 2. Opera	ting restrictions to ensure loss of Lie pole meets 33 Hz criteria
During ML Export	At full LIL power transfer of 900 MW, loss of a LIL pole will require the ML to be runback in the range of 100 MW to 150 MW, depending on system conditions, and depending on whether or not the ML frequency controller is in- or out-of-service.
During ML Import	If the ML import is at the maximum level of 325 MW, it cannot transiently import more power from Nova Scotia via its frequency controller or via a runback, therefore it cannot not help the IIS during underfrequency events. In this case, LIL power transfer would be limited to around 400 MW to 500 MW (depending on system conditions) to avoid UFLS

1.2.4 Loss of the LIL Bipole

Per Transmission Planning Critieria, controlled underfrequency load shedding is permitted for loss of the LIL bipole, however, the IIS frequency shall not drop below 58 Hz. Additionally, if the ML is exporting, the export will be runback to 0 MW if the LIL bipole trips.

In addition to running back ML export to 0 MW, modifications to the existing UFLS scheme are needed to maintain the IIS frequency above 58 Hz for loss of the LIL bipole. Additional blocks of load were added to the UFLS scheme, and the blocks were shifted to distribute the load shedding over a frequency range of 58.9 Hz to 58.4 Hz.

Despite the newly designed UFLS scheme, it is not possible to transfer the full 900 MW on the LIL unless there is sufficient Island generation on-line to provide adequate voltage and inertial support if the LIL bipole is lost. A preliminary operating guideline is defined in Figure 1-1, which limits LIL transfer based on a minimum requirement for Island generation. The LIL transfer limits are defined for two scenarios:

- ML is exporting firm transfer of 157 MW, and is relied upon to runback these exports to 0 MW
- ML is operating at 0 MW and only frequency controller action is available



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation




Figure 1-1. LIL Transfer limits vs. Island Generation

Blue: ML at 157 MW export Orange: ML at 0 MW

In addition to the LIL transfer limits shown in Figure 1-1, other conclusions include:

- Instability can arise in cases when there is a high power flow from BDE to the Avalon Peninsula. Operation of the HRD GT during peak load conditions is required to prevent system instability if the LIL bipole is lost.
- The Come-By-Chance capacitor banks should be in-service when the power flow eastward from BDE towards SOP is high to help support the voltage if the LIL bipole is lost. Keeping the precontingency voltage near Sunnyside as high as possible (within criteria) improves the system response to the worst case contingencies, including 3PF on TL202, TL206 and TL267 that were discussed in Section 1.2.1.

1.2.5 LIL Temporary Bipole Outage

According to Transmission Planning Criteria, a temporary bipole outage should not cause the IIS frequency to drop below 59 Hz and UFLS should be avoided.

Two LIL bipole outage durations were studied under worst case system conditions¹¹:

1) Maximum outage time to ensure IIS frequency stays above 59 Hz and UFLS is avoided

¹¹ Case HP27 was found to be the worst case for loss of LIL bipole.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

2) Outage time by which all blocks of load will have been shed at 58.0 Hz.

Table 1-3 summarizes these results for the worst case system conditions.

Table 1-3. Duration of LIL Bipole Outage

Number of SOP synchronous condensers in-service	Duration to Avoid UFLS	Duration at which all blocks of load have shed
2	300 ms	680 ms
3	380 ms	780 ms

It is important to note that the LIL frequency controller must be in-service if the LIL will be automatically restarted after a bipole outage. This is to account for the runback of ML export to 0 MW and the possibility that load has shed. If the LIL frequency controller is not in-service when the LIL bipole is automatically restarted, the ML frequency controller alone cannot maintain the IIS frequency to within 62 Hz if all blocks of load are shed.

1.3 Loss of the ML Bipole or Pole

As per Tranmission Planning Criteria, the loss of an ML pole (when importing) should not result in UFLS and frequency should remain above 59 Hz. Loss of the ML bipole is allowed to result in UFLS, however the frequency should remain above 58 Hz.

If exporting, frequency should remain below 62 Hz for loss of an ML pole or bipole.

The results for loss of an ML pole or bipole are summarized in Table 1-4.

Table 1-4. Summary of results for loss of ML bipole or pole

ML Import/Export	Loss of ML Pole	Loss of ML Bipole
500 MW export	Max. frequency of 60.6 Hz (light load)	Max. frequency of 61.2 Hz (light load)
320 MW import	LIL in-service: min. frequency > 59 Hz LIL out-of-service: min. frequrency 58.9 Hz, with 26 MW of loadshed	LIL in-service: min. frequency 58.86 Hz, with 0-76 MW of loadshed LIL out-of-service: min frequency 58.24 Hz, with 273-389 MW of loadshed

7 | Page



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

2. Study Models and Criteria

The Interconnected Island System (IIS) is the area of focus for this study.

2.1 Interconnected Island System

The 230 kV network of the IIS is shown in Figure 2-1.




Figure 2-1. Interconnected Island System 230 kV grid

The system was setup as follows:

- The Holyrood thermal generators are no longer available
- The Hardwoods and Stephenville Gas Turbines are no longer available
- Holyrood Unit 3 is operating as a synchronous condenser
- Two of the three 175 MVA SOP synchronous condensers are in-service (assuming one is out for maintenance)

2.2 LIL

The following LIL reactive power elements were available in the models:

• MFA: 4x72 MVAR filters

• SOP: 5x75 MVAR filters



Newfoundland and Labrador Hydro RFI Studies Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

2.3 Study Criteria

The applicable Transmission Planning Criteria for this study is summarized below:

- Steady state voltage: 0.95 pu 1.05 pu during n-0 conditions
- Steady state voltage: 0.90 pu 1.1 pu during n-1 conditions
- Post fault recovery voltages on the ac system shall be as follows:
 - Transient undervoltages following fault clearing should not drop below 70%
 - The duration of the voltage below 80% following fault clearing should not exceed 20 cycles
- Post fault system frequencies shall not drop below 59 Hz and shall not rise above 62 Hz
- For a permanent loss of the LIL bipole, underfrequency load shedding shall be permitted, but controlled, and the system frequency shall not drop below 58 Hz

2.4 Contingencies

Table 2-1 lists the contingencies that were considered in this study.

Table 2-1. Contingencies

Line/Generator	Fault Location (230 kV)	Description
TL217	SOP WAV	3PF cleared in 100 ms
TL203	WAV SSD	3PF cleared in 100 ms
TL202	SSD BDE	3PF cleared in 100 ms
TL267	WAV BDE	3PF cleared in 100 ms
TL268	SOP	3PF cleared in 100 ms
TL242	SOP	3PF cleared in 100 ms
SOP sync	SOP	3PF cleared in 100 ms
BDE unit #7	BDE	3PF cleared in 100 ms
BDE Unit 7	BDE	3PF cleared in 100 ms
Loss of LIL pole	n/a	Permanent loss of LIL pole. Remaining LIL pole increases transfer to 2 pu (10 min overload rating) using ground return
Loss of ML pole	n/a	Permanent loss of ML pole. Remaining ML pole increases transfer power lost on faulted pole, up to its rating
Loss of LIL bipole	n/a	Permanent loss of LIL bipole
Loss of ML bipole	n/a	Permanent loss of ML bipole
Temporary loss of LIL bipole	n/a	Temporary loss of LIL bipole. Test various durations and number of restart attemps.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

2.5 PSSE Base Cases

Table 2-2 lists the base cases that were used to analyze the IIS system in this study.

Table 2-2. Base cases provided by Hydro

Number	Load Condition	Island Demand	ML Import/Export	LIL LAB to NF Flow (at	Island Generation
		(MW) ¹²	(at BBK)(MW)	MFA)(MW)	(MW)
HP1	Peak ¹³	1824.8	157 (export)	900 (import)	1147.0
HP2	Intermediate Peak	1689.3	157 (export)	900 (import)	1012.9
HP3	Intermediate	1347.5	500 (export)	900 (import)	1012.8
HP4	Peak	1832.0	157 (export)	694 (import)	1333.6
HP5	Intermediate Peak	1717.0	157 (export)	694 (import)	1218.8
HP6	Intermediate	1374.6	500 (export)	694 (import)	1218.7
HP7	Peak	1904.6	320 (import)	294.4 (import)	1296.7
HP8	Peak	1905.2	320 (import)	337 (import)	1256.7
HP9	Intermediate	1224.4	320 (import)	0	903.6
HP10	Intermediate Peak	1756.9	104.8 (export)	~675 (import)	1302.9
HP11	Peak	1833.7	104.8 (export)	~675 (import)	1380.2
HP12	Intermediate Peak	1697.7	104.8 (export)	~675 (import)	1243.8
HP13	Peak	1812.4	158 (export)	~605 (import)	1307.3
HP14	Peak	1816.6	320 (import)	~605 (import)	833.3
HP15	Intermediate	1307.2	500 (export)	~605 (import)	1142.5
HP16	Intermediate	1272.5	158 (export)	~605 (import)	765.7
HP17	Intermediate	1278.7	320 (import)	~500 (import)	478.4
HP18	Light	779.2	500 (export)	~480 (import)	817.35
HP19	Light	742.7	158 (export)	~200 (import)	703.64
HP20	Light	767.8	320 (import)	0	447.01
HP21	Extreme Light	458.1	158 (export)	~90 (import)	526.1
HP22	Extreme Light	498.75	500 (export)	~470 (import)	546.1
HP23	Peak	1632.2	500 (export)	900 (import)	1296.8
HP24	Intermediate	1123	500 (export)	900 (import)	788.9
HP25	Light	843.6	500 (export)	900 (import)	509.4
HP26	Peak	1827.7	157 (export)	900 (import)	1150.6
HP27	Intermediate	1245.3	157 (export)	900 (import)	567.7

. .

 $^{^{12}}$ Island Demaind includes load and losses. Variations in Island Demand for the same loading condition are attributed to incremental losses associated with variations in dispatch.

¹³ Peak loading conditions are based on 2027 forecasted load.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

3. Review of Three-Phase Faults

Of the three-phase ac faults (3PF) that were studied, unacceptable performance was found for 3PF located anywhere on one of the three 230 kV lines running eastward of BDE, namely TL267, TL202 and TL206. Anlysis indicates that the system response is a function of power flow in this corridor. The worst case 3PF location is at Bay d'Espoir (BDE). As noted above, a 3PF at BDE is excluded from Transmission Planning Criteria. A 3PF at Sunnyside (SSD) or Western Avalon (WAV), even if on TL267, TL202 or TL206 must meet all Transmission Planning Criteria.

Analysis was performed to assess the impacts associated with three-phase faults on the 230 kV lines in the corridor between BDE and SOP. The following scenarios were considered:

- Assess corridor power flow limit such that a 3PF at BDE does not result in transient undervoltage conditions or instability.¹⁴
- 2. Assess corridor power flow limit with relaxed consideration of 3PF at BDE. 15

3.1 Considering a 3PF at BDE

3.1.1 Violations

This preliminary study found four power flow cases in which system instability or transient undervoltage violations were observed for a 3PF at BDE. These cases are summarized in Table 3-1. The worst system response was observed for a 3PF at BDE on TL267.

Table 3-1. Performance Issues Resulting from a 3PF at BDE on TL267

Base Case	Flow Eastward out of BDE (MW)	Generators in-service at BDE	Generators in- service Avalon Peninsula	LIL power at MFA (MW)	ML power transfer (MW)	Island demand (MW)	Criteria Violation
HP7	840	All (1-7)	HRP 3 (sync), HRD GT	294	320 import	1905	System instability
HP8	840	All (1-7)	HRP 3 (sync), HWD (sync)	337	320 import	1905	System instability
HP9	590	1, 2, 4, 7	HRP 3 (sync), HRD GT	Out-of- service	320 import	1224	Transient undervoltage criteria
HP12	499	All (1-7)	HRP 3 (sync)	675 monopole	104.8 export	1698	Transient undervoltage criteria

¹⁴ Such a case would be an enhancement of Transmission Planning Criteria where faults at BDE are given the same consideration as all other faults.

¹⁵ This scenario includes cases where the 3PF at BDE is neglected, in accordance with Transmission Planning Criteria. It is also includes consideration of enhanced Transmission Planning Criteria where stability must be maintained for a 3PF at BDE, but transient undervoltage violations would be permitted.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Figure 3-1 shows the system instability observed in case HP8 for a 3PF at BDE on TL267. The second plot of machine speeds at BDE Unit 7 and Holyrood Unit 3 shows that the system west of BDE loses synchronism with the system east of BDE.




Figure 3-1. 3PF BDE on TL267, Peak load, 840 MW flow eastward out of BDE

Figure 3-2 shows an example of the transient undervoltage criteria violations observed in case HP9 for a 3PF at BDE on TL267. The system response is stable, however, the 230 kV voltage at Sunnyside is below 0.8 pu for more than 20 cycles after the fault is cleared.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation




Figure 3-2. 3PF at BDE on TL267, Intermediate load, 590 MW flow eastward out of BDE

3.1.2 Mitigation

To mitigate the instability and transient low voltage issues, the flow eastward out of BDE was reduced. Table 3-2 summarizes the maximum flow eastward out of BDE to ensure acceptable system performance. Mitigation was not achievable for case HP9 when LIL was out-of-service.

Table 3-2. Mitigation for violations for a 3PF at BDE

Base Case	Limit Flow Eastward out of BDE (MW)	LIL Power Transfer (MW) after limiting BDE Flow	System response
HP7	657	474	Within criteria
HP8	617	560	Within criteria
НР9	Flow of 590 MW could not be reduced since LIL is out of service and there was no other generation to turn on on the Avalon peninsula	LIL out-of-service	Still violates transient undervoltage criteria (as shown in Figure 3-2)
HP12	458	675 monopole	Within criteria

The following sections discuss the results of Table 3-2 in more detail.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

3.1.2.1 LIL Operating as a Bipole – Cases HP7, HP8

In order to meet criteria for cases HP7 and HP8, power flow in the BDE-SOP corridor was reduced by increasing LIL infeed and adjusting ML power transfer accordingly. In both cases, a reduction of power transfer eastward out of BDE to around 615-650MW¹⁶ (from 840 MW) mitigated the system instability, and ensured the system response met criteria. For case HP7, LIL power transfer (measured at MFA) was increased from 294 MW to 474 MW. For case HP8, LIL import was increased from 337 MW to 560 MW.

In order to see if there was any appreciable improvement in allowable power transfer on the BDE to SOP 230 kV corridor, the following system additions were added to the cases (one at a time) and tested:

- A third 230 kV ac line in parallel to TL201 and TL217 between WAV and SOP
- Holyrood Unit 1 as a synchronous condenser
- Bay d'Espoir Unit 8
- Cat Arm Unit 3
- New gas turbine on the Avalon Peninsula¹⁷ operating as a synchronous condenser

Table 3-3 summarizes the increase in power transfer eastward from BDE that can be achieved with each of these system additions. It also shows the corresponding power flow through the WAV-SOP corridor, which is limited to 322 MVA due to TL201 thermal constraints. Note that the 322 MVA thermal constraint is not the most limiting constraint, since the transient stability issues are limiting the flow to less than the 322 MVA thermal constraint.

Table 3-3. HP7 and HP8 (Peak Load)- increase in BDE power transfer with new units

Table 3-3. HF7 and HF6 (Feak Load)- III	Maximum eastward power flow (MW)				
System addition		GT in-service)	HP8 (HRD GT out-of-service)		
5,000	Out of BDE	WAV-SOP	Out of BDE	WAV-SOP	
None (Base case)	656	280	617	238	
HRD unit 1 sync	656	280	655	275	
BDE unit 8	685	307	654	273	
CAT arm 3	667	293	627	250	
New GT on Avalon Peninsula (sync. cond.)	656	280	645	270	
3 Rd ac line, in parallel with TL201 and TL217	665	301	634	266	

For case HP7, which had the HRD GT in-service, there was no additional power transfer achieved by

16

¹⁶ Case HP7 had the Holyrood GT in-service, which allowed for slightly higher power transfer than case HP8 where this unit was not in-service.

 $^{^{17}}$ Generator assumed to be equivalent to a 165.9 MVA, Brush BDAX 8-445ER unit.

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 19 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

adding a synchronous condenser on the Avalon Peninsula (HRD Unit 1 or new GT operating as a synchronous condenser). For case HP8, with the HRD GT out-of-service, there was a marginal increase in power transfer, approximately 30-40 MW, that can be achieved with a new unit on the Avalon Peninsula operating as a synchronous condenser or by using HRD Unit 1 as a synchronous condenser.

A new BDE Unit 8 off-loaded the existing BDE units and provided some additional reactive power support, which allowed a marginal increase of 30-40 MW of power transfer across the BDE to SOP corridor for both cases HP7 and HP8.

A new unit at Cat Arm had a limited impact in both cases, given its distance from the corridor of interest.

The third ac line in parallel with TL201 and TL217 had limited benefit since the bottleneck is a dynamic issue and not a thermal constraint.

It should be noted that in all cases, the dynamic performance of the system is more limiting than the thermal rating of TL201 if consideration is given to the impact of the three-phase fault at BDE. The thermal rating of TL201 (322 MVA in the winter) was flagged as the system operating limit under peak load conditions in the previous operational studies, prior to the retirement of the HRD generating units.

The final phase of Stage 4 operating studies will define an operating guideline regarding the maximum power transfer eastward out of BDE over operating conditions ranging from extreme light to peak load.

3.1.2.2 LIL out-of-service – Case HP9

Case HP9 is an intermediate load case in which the LIL is out-of-service. Since the LIL was not in-service, its power infeed could not be increased to reduce the power flow on the BDE to SOP corridor. With the HRD GT already in service, there was no additional generation available on the Avalon Peninsula that could be turned on to reduce the power flow on the BDE to SOP corridor. Therefore, the Island demand was scaled down to 1200 MW in order to meet transient undervoltage issue along the 230 kV corridor between BDE and SOP.

The following mitigation options were tested to see if they could aid in serving additional Island demand with the LIL unavailable:

- Addition of a new Holyrood gas turbine, supplying 60 MW of generation on the Avalon Peninsula
- Turning on the third SOP synchronous condenser

Table 3-4 summarizes the Island demand that can be served with the above options in place, ensuring that the transient undervoltage issue along the BDE to SOP 230 kV corridor is mitigated.

Table 3-4. Island demand that can be served with the LIL is out-of-service

N. who of COD and have a	Island Demand that can be served (MW)			
Number of SOP synchronous condensers in-service	Base Case	New HRD GT (60 MW)		
2	1200	1300		
3	1200	1300		

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 20 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

The additional synchronous condenser at SOP did not provide any benefit in terms of being able to serve additional Island demand. The new 60 MW HRD GT allowed for an additional 100 MW of Island demand to be served by off-loading the BDE to SOP corridor and serving load close to the source.

In order to make an appreciable improvement to the amount of load that can be served when the LIL is out-of-service under BDE 3-phase fault scenario, it is likely that either generation would be needed on the Avalon Peninsula, dynamic reactive support would be required near Sunnyside, or new ac transmission out of BDE would be required to allow more power to be transferred east to the Avalon Peninsula from the generation and ML import available on the west of the Island.

3.1.2.3 LIL operating as a Monopole at 1.5 pu — Case HP12

Case HP12 is an intermediate peak load case with the LIL operating as a monopole at 1.5 pu. Since the LIL monopolar infeed is already at maximum continuous rating, the only available mitigation was to turn on the Holyrood GT. Setting this generator to 40 MW was sufficient to mitigate the transient undervoltage violations. Figure 3-3 shows the system response after turning on the Holyrood GT at 40 MW. In this case, there is 458 MW flowing east of out BDE, and 139 MW flowing from WAV to SOP.

A peak load case (HP11) was tested with the LIL operating as a monopole at 1.5 pu. This case had the HRD GT operating at its full capacity of 123.5 MW. There were no steady state or dynamic issues observed with this case. Therefore, the peak Island demand can be met even if the LIL is operating as a monopole at 1.5 pu, as long as the HRD GT can be dispatched as needed.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation




Figure 3-3. 3PF at BDE on TL267, Intermediate load, 458 MW flow eastward out of BDE

3.1.2.4 Summary of System Limits

As discussed in the previous sections, further analysis will be performed in the upcoming stages of the Stage 4 operational studies to define the operating guidelines required to limit flow between BDE and SOP in order to prevent stability issues that result due to three-phase faults on the 230 kV lines running eastward out of BDE.

3.2 Relaxed Consideration of a 3PF at BDE

3.2.1.1 LIL Operating as a Bipole – Cases HP7, HP8

Increased flow in this corridor would be possible if 3PF at BDE is neglected, in accordance with Transmission Planning Criteria. Increased flow would also be possible if enhanced Transmission Planning Criteria were considered where stability must be maintained for a 3PF at BDE, but transient undervoltage violations are permitted. Cases HP7 and HP8 were revisited on this basis and the results are summarized in Table 3-5.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Table 3-5. BDE to SOP Corridor Limits - with and without considering 3PF at BDE

	Maximum eastward power flow (MW)					
Consider a 3PF at BDE?	HP7 (HRD G	T in-service)	HP8 (HRD GT out-of-service)			
	Out of BDE	WAV-SOP	Out of BDE	WAV-SOP		
Yes	656	280	617	238		
No (3PF BDE is stable but violates criteria)	709	328	690	310		
No (3PF BDE is unstable)	725	344	710	331		

3.2.1.2 LIL out-of-service — Case HP9

Analysis was also performed to assess increased power flow limits in this corridor when the LIL is not in service. Case HP9 was investigated on this basis.

As discussed in Section 3.1.2.2, if a 3PF at BDE is considered to meet all Transmission Planning Criteria, the maximum load that can be served with the LIL out of service is 1200 MW.

If the 3PF location at BDE is ignored in terms of meeting transient voltage criteria, but still required to provide a stable system response, the maximum IIS load that can be served only increases to approximately 1260 MW. However, at this level of Island demand, the 3PF at BDE on TL267 is on the verge of instability as shown in Figure 3-4.




Figure 3-4. 3PF at BDE on TL267, Island demand 1225 MW, LIL out of service

If the 3PF at BDE is neglected, as per Transmission Planning Criteria, the next worst-case contingency

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 23 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

would be a 3PF at WAV, followed by a trip of TL267. A maximum Island Demand of 1290 MW can be supported in this case.

A summary of preliminary transfer limits is provided in Table 3-6. As discussed above, limits for all transmission system corridors will be confirmed as part of the final phase of the Stage IV studies.

Table 3-6. BDE to SOP Corridor Limits with the LIL Out of Service - with and without considering 3PF at BDE

considering of Facebox							
	Maximum power flo		Island Demand that can be met (MW)				
Consider a 3PF at BDE?	н	P9					
	Out of BDE	WAV-SOP					
Yes	580	310	1200				
No (3PF BDE is stable but violates criteria)	617	334	1260				
No (3PF BDE is unstable)	645	352	1290				



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Loss of Largest Generator in IIS

After retirement of the Holyrood generating units, BDE Unit 7 at 154.4 MW is the largest generator on the IIS. For loss of largest generator, frequency should remain above 59 Hz, and UFLS should be avoided.

4.1 LIL in-service

Loss of BDE Unit 7 was tested for various Island demand levels ranging from peak load to light load with the LIL transferring rated power of 900 MW. These tests were performed with the ML frequency controller in-service, and with the ML frequency controller out-of-service.

The purpose was to determine if any reserve is needed on the LIL to keep the frequency on the IIS above 59 Hz if BDE Unit 7 trips. Table 4-1 summarizes the results.

Table 4-1, Loss of BDE Unit 7, with and without ML frequency controller in-service

Case	Load	Island Generation	Island Demand	LIL ML (MW) Export		ML Frequency Controller In-service	Co	requency ntroller of-service
	Condition	(MW)	(MW)	@ MFA	(MW)	IIS Freq (Hz)	IIS Freq (Hz)	LIL (MW) to meet 59 Hz
HP23	Peak	1296.8	1632.2	900	500	59.22	58.77	846
HP24	Intermed.	788.9	1123	900	500	59.08	58.60	810
HP25	Light	509.4	843.6	900	500	59.10	58.62	770
HP26	Peak	1150.6	1827.7	900	157	59.16	58.75	830
HP27	Intermed.	567.7	1245.3	900	157	59.18	58.62	832

With the ML frequency controller in-service, the Island frequency remained above 59 Hz for loss of BDE Unit 7. Therefore, no reserve is required on the LIL if the ML frequency controller is in-service.

With the ML frequency controller out-of-service, the frequency dropped below 59 Hz for loss of BDE unit 7, to the levels shown in Table 4-1. In order to keep the frequency above 59 Hz, the LIL will need to carry reserve varying from 54 MW to 130 MW as shown in Table 4-1, depending on Island demand and generation levels.

LIL out-of-service 4.2

If the LIL is out-of-service, the frequency remains above 59 Hz for loss of the largest generator, as long as the ML frequency controller is in-service.

If the ML frequency controller is out-of-service, however, loss of the largest generator will cause frequency to drop below 59 Hz and the UFLS scheme will be initiated as summarized in Table 4-2.

PUB-NLH-003, Attachment 1 **Reliability and Resource Adequacy Study** Page 25 of 49



Newfoundland and Labrador Hydro **RFI Studies**

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Table 4-2. Loss of Largest Generator with LIL out-of-service

Case	Load	Island Generation	Island Demand	LIL	ML Export	ML Frequency Controller In-service	Co	requency ntroller of-service
	Condition	(MW)	(MW)		(MW)	IIS Freq (Hz)	IIS Freq (Hz)	Load Shed* (MW)
HP9	Intermed.	903.6	1224.4	OUT	320	59.21	58.78	90.6
HP20 ¹⁸	Light	447.0	767.8	OUT	320	59.31	58.83	25.5

^{*}Using revised UFLS discussed in Section 7

The final Stage IV study will include an assessment to determine maximum unit loading to avoid instability and UFLS if frequency controllers are not in service.

©TransGrid Solutions Inc., 2018

 $^{^{18}}$ Loss of BDE Unit 1 at 60 MW. BDE Unit 7 is not in-service in this case.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Loss of a LIL Pole

The Transmission Planning Criteria for loss of a LIL pole states that this event should not cause the IIS frequency to drop below 59 Hz, and it should not result in UFLS.

If one of the LIL poles is lost, the remaining pole is rated to transmit 2.0 pu for 10 minutes, after which the continuous monopole rating drops down to 1.5 pu. The purpose of the 10-minute 2.0 pu overload rating is to allow operators time to quickly turn on generation to make up for the loss of infeed from the LIL pole that was lost. However, there are two issues that restrict the LIL monopole from actually providing the full overload rating during the transient stability timeframe (seconds):

- When operating as a monopole, immediately after the other LIL pole has tripped, the monopole
 will be operating in ground return. The LIL has a long electrode, which adds a significant amount
 of resistance to the link when operating in ground return. This increased resistance results in
 increased losses on the LIL DC line.
- 2. Within a transient stability timeframe (i.e. seconds), the remaining LIL pole is not necessarily able to transmit the full 2.0 pu due to the rectifier firing angle hitting its minimum limit, which keeps the DC current from getting up to the full 2.0 pu until the tap-changers on the converter transformers can operate to release the firing angle from its limit. Therefore, within this initial time period after the LIL pole is lost, there is still loss of infeed to the IIS despite the 2.0 pu 10-minute overload rating. The amount of infeed that is lost depends on how much power the LIL was transferring before the pole was lost. In a worst case, if operating at 900 MW, this study showed that without tap-changer action on the converter transformers and with hitting minimum alpha, and also due to increased DC line losses associated with the resistance of the line electrode, the remaining pole is only able to provide 633 MW to SOP, as opposed to the 830 MW it was providing pre-contingency, resulting in the net initial loss of 267 MW.

5.1 During ML Export

In order to keep the IIS frequency above 59 Hz, loss of a LIL pole will require a runback on the ML. The ML will receive a signal to runback its exports to 0 MW if the LIL experiences a loss of pole. Loss of a LIL pole was simulated for the study base cases. Table 5-1 summarizes the results for loss of a LIL pole when operating at 900 MW, for the scenarios with the ML frequency controller in-service and out-of-service.

Table 5-1. Minimum Frequency following Loss of LIL Pole with ML runback to 0 MW

		(5.63.47)		Minimum Fre	uency Dip (Hz)	
Case	Load Condition	LIL (MW) @ MFA	ML (MW)	ML frequency controller in-service	ML frequency controller out-of-service	
HP23	Peak	900	500 (export)	59.76*	58.76	
HP24	Intermediate	900	500 (export)	59.79*	59.79	
HP25	Light	900	500 (export)	59.80*	59.80	
HP26	Peak	900	157 (export)	59.11	58.94	
HP27	Intermediate	900	157 (export)	59.14	58.84	

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 27 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

If the ML frequency controller is in-service, the frequency remained above 59 Hz.

If the ML frequency controller is out of service, the cases with 157 MW of ML export (cases HP26, HP27) experience a frequency slightly less than 59 Hz, down to around 58.8 Hz.

Please note that the cases marked with (*) in Table 5-1 require the LIL frequency controller to be inservice to prevent a large overfrequency (>62 Hz) from occurring after the 500 MW ML export is runback to 0 MW. Alternatively, a more sophisticated ML runback detailing a specific amount of power to be runback would be required.

5.2 During ML Import

If the ML import is at the maximum level of 320 MW, it cannot transiently import more power from Nova Scotia via its frequency controller and it cannot be runback, therefore it cannot help the IIS during underfrequency events. In this case, LIL power transfer would have to be limited as per Table 5-2 in order to keep the IIS frequency above 59 Hz in case a LIL pole is lost.

Table 5-2. LIL Transfer Limits: Loss of LIL pole during ML 320 MW import

Case	Load Condition	LIL (MW) @ MFA	ML (MW)	IIS Minimum Frequency (Hz)	Maximum LIL Transfer to meet 59 Hz (MW)
HP7	Peak	294.4	320 (import)	59.66	-
HP8	Peak	337	320 (import)	59.44	-
HP14	Peak	704	320 (import)	58.76	488
HP17	Intermediate	500	320 (import)	58.80	395

The final Stage IV study will include an assessment to determine maximum LIL loading to ensure compliance with Transmission Planning Criteria.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

6. Loss of an ML Pole

6.1 During ML Export

If the ML is exporting and a pole is lost, the IIS will experience an overfrequency. This overfrequency should not rise above 62 Hz.

The worst case occurs when the ML is at maximum export of 500 MW. If an ML pole is lost, there will be an excess of 250 MW in the IIS. All base cases with the ML exporting 500 MW were used to simulate loss of an ML pole. These results are summarized in Table 6-1.

For this analysis, a runback of the LIL was not considered. Rather the LIL frequency controller was found to adequately limit overfrequency conditions. The highest overfrequencies were found to occur during light and extreme light load conditions, in which an overfrequency of 60.6 Hz occurred when an ML pole was lost.

Table 6-1. ML 500 MW export cases - loss of ML pole

Case	Load Condition	LIL (MW) @ MFA	ML (MW)	Frequency (Hz)
HP3	Intermediate	900	500 (export)	60.50
HP6	Intermediate	694	500 (export)	60.49
HP15	Intermediate	704	500 (export)	60.49
HP22	Extreme Light	470	500 (export)	60.56
HP23	Peak	900	500 (export)	60.49
HP24	Intermediate	900	500 (export)	60.54
HP25	Light	900	500 (export)	60.60

6.2 During ML Import

If the ML is importing and a pole is lost, the IIS will experience an underfrequency. This underfrequency should not drop below 59 Hz and UFLS should not occur.

The worst case occurs when the ML is at maximum import of 320 MW. If an ML pole is lost, the healthy pole will automatically increase its power from importing 160 MW to 250 MW (rating of the pole), resulting in a net loss of approximately 70 MW to the IIS. All base cases with the ML importing 320 MW were used to simulate loss of an ML pole. Table 6-2 summarizes these results.

- With the LIL and its frequency controller in-service, the IIS frequency remained above 59 Hz and the Transmission Planning Criteria is met.
- With the LIL out-of-service, however, loss of an ML pole resulted in the IIS frequency dropping just below 59 Hz. For the intermediate load case, the frequency drops to 58.96 Hz, however, this is not low enough to result in load shedding. For the light load case, the frequency drops to 58.86 Hz, and load is shed.

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 29 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Table 6-2. ML 320 MW import cases - Loss of ML pole

Case	Load Condition	LIL (MW) @ MFA	ML (MW)	Frequency (Hz)	Load Shed (MW)			
LIL (and frequeny controller) in-service								
HP7	Peak	294.4 (import)	320 (import)	59.69	1			
HP8	Peak	337 (import)	320 (import)	59.67	-			
HP14	Peak	704	320 (import)	59.67	-			
HP17	Intermediate	500	320 (import)	59.60	-			
LIL (and frequeny controller) out-of-service								
HP9	Intermediate	Out-of-service	320 (import)	58.96	0			
HP20	Light	Out-of-service	320 (import)	58.86	26			

The final Stage IV study will include an assessment to determine maximum ML loading to ensure compliance with Transmission Planning Criteria.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Loss of the LIL Bipole

7.1 **Permanent Loss of the LIL Bipole**

A permanent loss of the LIL bipole (i.e. without successful restart) is the contingency that defines the requirements of the UFLS scheme for the IIS. If the LIL bipole is lost, the ML (if exporting) will be runback to 0 MW19. Additionally, the UFLS scheme will operate to ensure that the system remains stable and that the IIS frequency remains above 58 Hz, as per Transmission Planning Criteria.

There are two stability issues that were found to occur when the LIL bipole is lost:

- 1. Fast decline in IIS frequency
- 2. Voltage collapse around the mid-point of the BDE-SOP 230 kV corridor (around Sunnyside)

Modifications to the existing UFLS scheme were required to keep the IIS frequency above the 58 Hz criteria. The modified scheme consists of load shed blocks over a frequency range of 58.9 Hz to 58.4 Hz. Details of the new UFLS scheme are provided in Appendix 1.

Loss of the LIL bipole was simulated for each of the study base cases using the newly defined UFLS scheme. The results are summarized in Table 7-1, including the amount of load that is shed for each case. For all cases in Table 7-1, the minimum IIS frequency was found to remain at or above 58.1 Hz, providing a 0.1 Hz margin to the 58 Hz Transmission Planning Criteria, with the exception of cases HP8, HP14, HP26 and HP27, which are discussed in further detail in Sections 7.1.1 and 7.1.2.

Table 7-1. Scenarios studied for permanent loss of LIL bipole, and corresponsding UFLS

Study Case	Load Condition	Island Demand (MW)	ML (at BBK) (MW)	LIL (at MFA) (MW)	Island Generation (MW)	Load Shed (MW)
HP1	Peak	1824.8	157 (export)	900	1147	782
HP2	Intermediate Peak	1689.3	157 (export)	900	1012.9	718
HP3	Intermediate	1347.5	500 (export)	900	1012.8	268
HP4	Peak	1832	157 (export)	694	1333.6	628
HP5	Intermediate Peak	1717	157 (export)	694	1218.8	723
HP6	Intermediate	1374.6	500 (export)	694	1218.7	55
HP7	Peak	1861.7	320 (import)	474	1084.9	780
HP8*	Peak	1849.5	320 (import)	560	994.1	782
HP10	Intermediate Peak	1756.9	104.8 (export)	675 (MP)	1302.9	576
HP11	Peak	1833.7	104.8 (export)	675 (MP)	1380.2	601

¹⁹ If the ML is not exporting, the ML response would be limited to frequency controller action.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Study Case	Load Condition	Island Demand (MW)	ML (at BBK) (MW)	LIL (at MFA) (MW)	Island Generation (MW)	Load Shed (MW)
HP12	Intermediate Peak	1697.7	104.8 (export)	675 (MP)	1243.8	716
HP13	Peak	1812.4	158 (export)	704	1307.3	653
HP14*	Peak	1830.4	320 (import)	488	1040.6	779
HP15	Intermediate	1307.2	500 (export)	704	1142.5	51
HP16	Intermediate	1272.5	158 (export)	704	765.7	539
HP17	Intermediate	1285.1	320 (import)	395	582	440
HP18	Light	779.2	500 (export)	480	817.35	0
HP19	Light	742.7	158 (export)	200	703.64	0
HP21	Extreme Light	458.1	158 (export)	90	526.1	0
HP22	Extreme Light	498.75	500 (export)	470	546.1	0
HP23	Peak	1632.2	500 (export)	900	1296.8	338
HP24	Intermediate	1123	500 (export)	900	788.9	240
HP25	Light	843.6	500 (export)	900	509.4	199
HP26*	Peak	1827.7	157 (export)	900	1150.6	782
HP27**	Intermediate	1245.3	157 (export)	900	567	512

^{*}Unstable unless HRD GT put in-service

7.1.1 Minimum Island Generation

Based on further investigation of Case HP27, it became evident that it would not be possible to transfer the full 900 MW on the LIL if there was not sufficient Island generation on-line to support the IIS frequency and voltage if the LIL bipole is lost. In the original Case HP27, the LIL is transferring 900 MW with only 567 MW of Island generation on-line. A series of simulations were performed from peak load to extreme light load conditions to determine the maximum LIL transfer that could be lost for a given amount of Island generation. This was performed by starting out at peak load, then scaling down Island demand/generation and finding out at what LIL transfer limit the IIS frequency would drop to 58 Hz if the LIL bipole was lost. Based on these series of simulations, a preliminary operating guideline was developed to define LIL transfer limits based on Island generation. In this operating guideline, the maximum LIL power transfer is tied to a minimum requirement for Island generation, as shown in Figure 7-1. The LIL transfer limits are defined for two scenarios; one, where the ML is exporting firm transfer of 157 MW (and can be relied upon to runback these exports to 0 MW), and two, where the ML is operating at 0 MW (and cannot be relied upon for runback).

Please note that the LIL transfer limits shown in Figure 7-1 are valid when the ML frequency controller is in-service. Further restrictions on LIL transfer would likely be necessary if the ML or the ML frequency controller is out-of-service. A similar graph with the ML frequency controller out-of-service will be developed during the final phase of Stage 4 operating studies.

In order for Case HP27 to result in a minimum frequency of 58.1 Hz if the LIL bipole is lost, the LIL transfer had to be reduced from 900 MW to 820 MW, and consequently the Island generation had to be

^{**}Stable but frequency < 58 Hz unless LIL reduced to 820 MW and Island generation increased to 633 MW



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

increased from 567 MW to 633 MW. This new operating point lines up well with the blue curve in Figure 7-1.




Figure 7-1. LIL Transfer limits vs. Island Generation

Blue: ML @ 157 MW export Orange: ML @ 0 MW

7.1.2 Peak Load – Need for HRD GT to be in-service

Peak load cases HP8, HP14 and HP26 are unstable even with the newly designed UFLS scheme. This is due to voltage collapse near Sunnyside Terminal Station. Case HP26 has sufficient Island generation to transfer the full 900 MW LIL rating, according to Figure 7-1, and cases HP14 and HP8 have significantly reduced LIL power transer, but yet still they are unstable.

One commonality between these three cases is that the HRD GT is not on-line. In all of the other peak load cases in Table 7-1, the HRD GT is dispatched.

These cases were investigated in further detail as described below.

7.1.2.1 Case HP26 - During 900 MW LIL, 157 MW ML Export

Case HP26, although it has sufficient Island generation to transfer the full 900 MW on the LIL according Figure 7-1, is not stable. Referring to Table 7-1, case HP26 is the same as case HP1, except case HP1 has the HRD GT dispatched. It was found that if the HRD GT is turned on in case HP26, while keeping the same spinning reserve (i.e. turning off other generators that were on while keeping a spinning reserve of 70 MW), the IIS response is stable and the frequency remains above the 58 Hz criteria. The voltage in



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

the Sunnyside area dips to around 0.6 pu, but the system recovers as shown in Figure 7-2. It is important to note that three CBC capacitor banks are in-service in this case to help support the voltage in this area.




Figure 7-2. Loss of LIL Bipole (Case HP26 with HRD GT on)

Consequently, it may be necessary to have an additional operating guideline stating that, in addition to the LIL transfer limits shown in Figure 7-1, the HRD GT and three CBC capacitor banks must be in service during peak load conditions when LIL power transfer is high.

7.1.2.2 Case HP8, Case HP14 – During 320 MW ML Import

Cases HP8 and HP14 are both cases where the ML is importing 320 MW, and therefore the ML frequency controller is not able to provide assistance when the LIL bipole is lost.

Case HP8 is one of the cases used to test high power flow eastward from BDE towards SOP.

Case HP14 is similar to case HP8. The original case HP14 as provided by Hydro had the LIL transferring 704 MW. However, loss of a LIL pole (discussed in Section 5.2) determined that the maximum LIL transfer in this case could only be 488 MW in order to satisfy the 59 Hz criteria for loss of a LIL pole. This case would therefore also require redispatch. However, when the LIL transfer is reduced to 488 MW, the power flow eastward from BDE towards SOP also becomes high, similar to case HP8.

When simulating loss of the LIL bipole at these operating points, case HP7 (HRD GT in-service) is stable and meets criteria. However, case HP8 and case HP14 (HRD GT out-of-service) are not stable. In these

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 34 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

cases, the LIL power transfer must be further increased to further restrict power flow in this corridor. Case HP8 becomes stable with LIL power transfer of 600 MW (instead of 560 MW), which corresponds to a BDE to SOP power flow of approximately 650 MW.

However, increasing LIL power beyond 488 MW will result in the 59 Hz criteria being violated if a LIL pole is lost.

Therefore, instead of reducing power flow on the BDE to SOP corridor by increasing LIL transfer, cases HP8 and HP14 also become stable if the HRD GT is turned on, which also results in reduced power flow on this corridor.

Please also note that during times of high power flow between BDE and SOP, adding pre-contingency voltage support in the Sunnyside area is necessary. It is recommended to keep the voltage in this area as high as possible (without violating steady state voltage criteria) by turning on the capacitor banks at Come-By-Chance.

The details of the operating guideline to limit power flow between BDE and SOP will be finalized during the final phase of the Stage 4 operational studies, taking into consideration all contingencies in the system including three-phase AC faults and loss of the LIL bipole. This preliminary study indicates a power flow limit in the range of 650 MW in this corridor (as measured eastward out of BDE) in order to maintain system stability following the loss of the LIL bipole.

It appears that during peak load conditions, the HRD GT should be placed online. Requirements for gas turbine operation will be defined during the final Stage 4 operational studies.

7.2 LIL Temporary Bipole Outage

An analysis of temporary LIL bipole outages of varying durations prior to successful restart was performed in order to find the maximum restart time that would ensure the IIS frequency remains above 59 Hz (in accordance with Transmission Planning Criteria to prevent an underfrequency load shed event). A further assessment was also performed to observe how much this outage time could be increased prior to all of the blocks of UFLS required for the permanent loss of the LIL bipole (assuming the new UFLS scheme required for the permanent loss of the LIL bipole is in place).

In a typical HVDC link, the time for the first restart attempt is usually in the range of 100 ms to 200 ms. Subsequent restart attempts typically add 50 ms to 100 ms for each additional restart attempt. For example, if an HVDC link has four restart attempts, an example for possible timing for restart attempts might be as follows:

First attempt: 150 ms

Second attempt: 200 ms

Third attempt: 300 ms

Fourth attempt: 400 ms

If it took all four restart attempts before successfully restarting the HVDC link, this could mean a total temporary outage time of more than 1 second. A temporary LIL bipole outage of 1 second is also simulated in this study.

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 35 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

7.2.1 To Meet 59 Hz and Avoid UFLS

The 900 MW LIL transfer cases from Table 7-1 were used to simulate the temporary LIL bipole outage with successful restart. Case HP27 was found to be the most limiting case to meet the 59 Hz criteria. As discussed in Section 7.1.1, this case was characterized by having insufficient Island generation for the full import of 900 MW over the LIL, and as such the LIL power transfer was reduced to 820 MW and the Island generation was increased to 633 MW. Even at 820 MW of LIL transfer, this case was the worst in terms of frequency dip compared to the other LIL 900 MW cases when simulated a temporary LIL bipole outage.

Assuming that the ML (if exporting) will runback to 0 MW during the LIL temporary bipole outage, the 59 Hz criteria can be met as long as the LIL is successfully restarted within:

- 300 ms if two SOP synchronous condensers in-service
- 380 ms if three SOP synchronous condensers in-service

Figure 7-3 shows the IIS response to a temporary LIL bipole outage with two SOP synchronous condensers in-service for case HP27. A successful restart after 300 ms is shown. It is noted that this case includes a runback of 157 MW and frequency controller operation.

If there is no ML export to runback and/or if the ML frequency controller is not in-service, a LIL operating restriction would be required to meet the 59 Hz criteria. The final phase of the Stage IV studies will determine limits to LIL import if the ML frequency controller is not in-service or if there is no export on the ML.

The generator additions tested earlier in this report were also tested to see if they had any impact on the allowable LIL bipole temporary outage duration. These units included:

- Holyrood Unit 1 as a synchronous condenser
- Bay d'Espoir Unit 8
- Cat Arm Unit 3
- New gas turbine on the Avalon Peninsula²⁰ operating as a synchronous condenser

The addition of these units did not have an appreciable impact on the frequency response of the system.

²⁰ Generator assumed to be equivalent to Brush BDAX 8-445ER



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation




Figure 7-3. Temporary Loss of LIL Bipole (Case HP27), restart in 300 ms, 59 Hz (no UFLS)

7.2.2 Outage Duration before all Blocks of Load are Shed

It is planned that the LIL will have multiple restart attempts. If the total outage time of the LIL bipole increases beyond the durations stated in Seciton 7.2.1, then blocks of UFLS will begin to activate once the frequency falls to 58.9 Hz.

Analysis was performed to determine the total LIL bipole outage duration by which the majority of the blocks of load will have been shed. For case HP27, the majority of the blocks of the newly designed UFLS scheme were shed within:

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 37 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

- 680 ms if two SOP synchronous condensers in-service
- 780 ms if three SOP synchronous condensers are in-service

The example of restart timings described in Section 7.2 shows that multiple restart attempts could result in a temporary LIL bipole outage of around 1 second. This scenario was simulated to show the system response to a temporary LIL bipole outage of 1 second. Note that in PSSE, multiple restart attempts are not actually simulated, but rather it is simulated as a single total outage duration of 1 second.

The system response to a temporary LIL bipole outage that is successfully restarted after 1 second is shown in Figure 7-4. Note that upon successfully restarting, the LIL frequency controller reduces the LIL power transfer power to near minimum power due to the load that was shed on the Island and due to the runback of 157 MW of ML export during the temporary outage of the LIL bipole.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation




Figure 7-4. Temporary Loss of LIL Bipole (Case HP27), restart in 1 second

If the LIL frequency controller is not in-service, the system frequency continues to rise beyond 62 Hz upon successful restart of the LIL bipole as shown in Figure 7-5. Therefore, if restart attempts are going to be made on LIL bipole outages, it is essential that the LIL frequency controller be in-service, otherwise if all blocks of load have been shed and the LIL returns to full power, the system frequency will rise far beyond 62 Hz.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation




Figure 7-5. Temporary Loss of LIL Bipole (Case HP27), restart in 1 second, no LIL frequency controller



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Loss of the ML Bipole

8.1 During ML Export

If the ML is exporting and the ML bipole is lost, the IIS will experience an overfrequency. Transmission Planning criteria states that this overfrequency should not rise above 62 Hz.

The worst case occurs when the ML is at maximum export of 500 MW. If the ML bipole is lost, there will be an excess of 500 MW in the IIS. All base cases with the ML exporting 500 MW were used to simulate loss of the ML bipole. These results are summarized in Table 8-1.

Without running back power on the LIL, the worst case system conditions occur during light and extreme light loading, which experienced an overfrequency of 61.2 Hz when the ML bipole was lost.

Table 8-1. Overfrequency due to loss of ML bipole at 500 MW export

Table 0-1. Overnequency due to 1033 of the bipole at 000 thiv				
Case	Load Condition	LIL (MW) @ MFA	ML (MW)	Frequency (Hz)
HP3	Intermediate	900	500 (export)	60.87
HP6	Intermediate	694	500 (export)	60.86
HP15	Intermediate	704	500 (export)	60.86
HP18	Light	480	500 (export)	61.20
HP22	Extreme Light	470	500 (export)	61.20
HP23	Peak	900	500 (export)	60.86
HP24	Intermediate	900	500 (export)	60.92
HP25	Light	900	500 (export)	60.87

8.2 During ML Import

If the ML bipole is lost while importing, the IIS will experience an underfrequency. Transmission Planning criteria states that frequency should remain above 58 Hz, however controlled UFLS is permitted.

The worst case underfrequency occurs when the ML is at maximum import of 320 MW. If the ML bipole is lost, there will be a deficiency of 320 MW in the IIS. All base cases with the ML importing 320 MW were used to simulate loss of the ML bipole. These results are summarized in Table 8-2. In all cases, the frequency remained well above 58 Hz.

Table 8-2. Underfrequency due to loss of ML bipole at 320 MW import

Case	Load Condition	LIL (MW) @ MFA	ML (MW)	Frequency (Hz)	Load shed (MW)
HP7	Peak	294.4	320 (import)	59.35	-
HP8	Peak	337	320 (import)	59.32	-
HP9	Intermediate	Out-of-service	320 (import)	58.48	381
HP14	Peak	704	320 (import)	58.86	76
HP17	Intermediate	500	320 (import)	59.33	ı
HP20	Light	Out-of-service	320 (import)	58.24	273

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 41 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

In the cases with the LIL in-service, only the peak load case (HP14) with the LIL operating at 704 MW experienced an UFLS event of 76 MW when the ML bipole was lost. In the rest of the cases with the LIL in-service, the IIS frequency remained above 59 Hz.

In the cases where the LIL is out-of-service (HP2, HP20), its frequency controller is not available to support the IIS frequency when the ML bipole is lost. In these cases, the frequency still remained well above the 58 Hz criteria, however UFLS in the amount of 273 MW occurred in the light load case and 381 MW occurred in the intermediate load case using the revised UFLS scheme discussed in Section 7.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

9. Conclusions

9.1 Conclusions

The results of the analysis are summarized in the sections below.

9.1.1 Three-Phase Faults near SOP, BDE and the Avalon Peninsula

The analysis included a review of three-phase faults on the 230 kV lines between Bay d'Espoir (BDE), SOP, and the Avalon Peninsula. Anlysis indicates that the system response is a function of power flow on 230 kV lines at BDE, namely TL202, TL206 and TL267. While the BDE three-phase fault is excluded from Transmission Planning Criteria, three-phase faults at Sunnyside (SSD) and Western Avalon (WAV) must meet criteria. A prelimary investigation of operating limits was performed and these limits will be confirmed during the final Stage 4 operational studies.

1) LIL in-service

The preliminary analysis indicates that flow in the BDE to Avalon Peninsula corridor can be restricted to avoid instability from a three-phase fault without impacting the capacity of the transmission system to meet forecasted peak loads when the LIL is in-service as a bipole or as a monopole.

2) LIL out-of-service

If the LIL is out-of-service, peak Island demand cannot be served. Flow in the BDE to Avalon Peninsula corridor is restricted to avoid customer impact for a 3PF on TL202, TL206 or TL267. With the LIL out of service, the maximum Island demand that can be served is around 1200 MW if the 3PF at BDE is considered. Increased transfer limits are possible if consideration of the BDE 3PF location is relaxed.

In order to be capable of serving higher Island demand without a stability issue under a three-phase fault scenario on TL202, TL206 or TL267 with the LIL out of service, it is likely that either new generation would be required on the Avalon peninsula, that dynamic reactive power support would be required near Sunnyside, or that new AC transmission eastward out of BDE would be needed in order to transfer more generation from the west of the Island to the Avalon Peninsula.

9.1.2 Loss of Largest Unit with the IIS

After retirement of the Holyrood generating units, BDE Unit 7 at 154.4 MW is the largest generator on the Island. Frequency should remain above 59 Hz for loss of BDE Unit 7 and UFLS should be avoided.

Table 9-1 summarizes the LIL reserve requirements to ensure that loss of the largest generator meets the 59 Hz criteria and avoids UFLS.

Table 9-1. LIL reserve requirements for loss of largest generator

ML Frequency Controller	Reserve required on LIL
In-service	None
Out-of-service	54 MW to 130 MW, depending on system conditions

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 43 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

9.1.3 Loss of a LIL Pole

Similar to loss of the largest generator, frequency should remain above 59 Hz for loss of a LIL pole and UFLS should be avoided.

If one of the LIL poles is lost, the remaining pole has an overload rating of 2.0 pu for 10 minutes, after which the rating drops down to 1.5 pu continuous. The amount of LIL infeed that is lost at SOP depends on how much power the LIL was transferring prior to loss of the pole. In a worst case, if operating at 900 MW, this study showed that prior to converter transformer tap-changer action, and due to increased DC line losses associated with the resistance of the line electrode, the remaining pole is only able to provide 633 MW at Soldiers Pond, as opposed to the 830 MW it was providing pre-contingency, resulting in the net loss of 267 MW to the IIS.

Operating restrictions to keep the IIS frequency above 59.1 Hz for loss of a LIL pole are summarized in Table 9-2.

Table 9-2. Operating restrictions to ensure loss of LIL pole meets 59 Hz criteria

Table 0 2: Operating restrictions to chedic loss of Lie pole meets of the criteria		
ML Export	At full LIL power transfer of 900 MW, loss of a LIL pole will require ML runback in the range of 100 MW to 150 MW, depending on system conditions, and depending on whether or not the ML frequency controller is in- or out-of-service.	
ML Import	If the ML import is at the maximum level of 320 MW, it cannot transiently import more power from Nova Scotia via its frequency controller or via a runback, therefore it cannot not help the IIS during underfrequency events. In this case, LIL power transfer should be limited to around 400 MW to 500 MW depending on system conditions.	

9.1.4 Loss of the LIL Bipole

Controlled underfrequency load shedding is permitted for loss of the LIL bipole, however, the IIS frequency shall not drop below 58 Hz. Additionally, if the ML is exporting, the export will be runback to 0 MW if the LIL bipole trips.

In addition to running back ML export to 0 MW, modifications to the existing UFLS scheme are needed to maintain the IIS frequency above 58 Hz for loss of the LIL bipole. Additional blocks of load were added to the UFLS scheme, and the blocks were shifted to distribute the load shedding over a frequency range of 58.9 Hz to 58.4 Hz.

Despite the newly designed UFLS scheme, it is not possible to transfer the full 900 MW on the LIL unless there is sufficient Island generation on-line to provide adequate voltage and inertial support if the LIL bipole is lost. A preliminary operating guideline is defined in Figure 9-1, which limits LIL transfer based on a minimum requirement for Island generation. The LIL transfer limits are defined for two scenarios:

- ML is exporting firm transfer of 157 MW, and is relied upon to runback these exports to 0 MW
- ML is operating at 0 MW, and cannot be relied upon for runback



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation




Figure 9-1. LIL Transfer limits vs. Island Generation

Blue: ML @ 157 MW export Orange: ML @ 0 MW

In addition to the LIL transfer limits shown in Figure 9-1, other conclusions include:

- Instability can arise in cases when there is a high power flow from BDE to the Avalon Peninsula. Operation of the HRD GT during peak load conditions is required to prevent system instability if the LIL bipole is lost.
- The Come-By-Chance capacitor banks should be in-service when the power flow eastward from BDE towards SOP is high to help support the voltage if the LIL bipole is lost. Keeping the precontingency voltage near Sunnyside as high as possible (within criteria) improves the system response to the worst case contingencies, including 3PF on TL202, TL206 and TL267 that were discussed in Section 1.2.1.

9.1.5 LIL Temporary Bipole Outage

According to Transmission Planning Criteria, a temporary bipole outage should not cause the IIS frequency to drop below 59 Hz and UFLS should be avoided.

Two LIL bipole outage durations were studied under worst case system conditions²¹:

- 1. Maximum outage time to ensure IIS frequency stays above 59 Hz and UFLS is avoided
- 2. Outage time by which all blocks of load will have been shed

39 | Page

²¹ Case HP27 was found to be the worst case for loss of LIL bipole.



Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

Table 9-3 summarizes these results for the worst case system conditions.

Table 9-3. Duration of LIL Bipole Outage

Table 3-3. Buration of Ele Dipole Gatage			
Number of SOP synchronous condensers in-service	Duration to Avoid UFLS	Duration at which all blocks of load have shed	
2	300 ms	680 ms	
3	380 ms	780 ms	

It is important to note that the LIL frequency controller must be in-service if the LIL will be automatically restarted after a bipole outage. This is to account for the runback of ML export and the possibility that load has shed. If the LIL frequency controller is not in-service when the LIL bipole is automatically restarted, the IIS frequency can go significantly beyond 62 Hz if all blocks of load have shed.

9.1.6 Loss of the ML Bipole or Pole

If importing, loss of an ML pole should not result in UFLS and frequency should remain above 59 Hz. Loss of the ML bipole is allowed to result in UFLS, however the frequency should remain above 58 Hz.

If exporting, frequency should remain below 62 Hz for loss of an ML pole or bipole.

The results for loss of an ML pole or bipole are summarized in Table 9-4.

Table 9-4. Summary of results for loss of ML bipole or pole

ML Import/Export	Loss of ML Pole	Loss of ML Bipole
500 MW export	Max. frequency of 60.6 Hz (light load)	Max. frequency of 61.2 Hz (light load)
320 MW import	LIL in-service: min. frequency > 59 Hz LIL out-of-service: min frequency 58.9 Hz, with 26 MW of loadshed	LIL in-service: min. frequency 58.86 Hz, with 0-76 MW of loadshed LIL out-of-service: min frequency 58.24 Hz, with 273-389 MW of loadshed

9.2 Summary of Technical Issues

As described above, the following technical issues were identified by the Liberty Consulting Group as part of Phase 2 of the Hearing into Supply Issues and Power Outages on the Island Interconnected System. Conclusions with respect to these items are summarized as follows:

- Options (e.g. operating limits) to reduce UFLS
 - Analysis has been performed to confirm that Transmission Planning Criteria are met. A
 modified UFLS scheme has been developed and it has been confirmed that load shed is
 avoided and frequencies do not drop below 59 Hz for events including the loss of

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 46 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

generating units, the permanent loss of an HVdc pole, and for the temporary loss of a bipole. Preliminary operating limits have been identified to ensure that UFLS is avoided in operating conditions when HVdc links or frequency controllers are not in service. These limits will be fully developed as part of the final phase of the operating studies.

· Re-strikes on the LIL-OHL

- As summarized in Section 7.2, an analysis was performed to assess temporary LIL bipole outages. It was found that UFLS is avoided if the LIL is restarted within 300 ms. This limitation assumes that the ML frequency controller is in place and 157 MW of ML export is being curtailed. Operating limits for the LIL will be developed to ensure that UFLS does not occur if the ML frequency controller is not in service or if export is reduced.
- o The LIL frequency controller must be in-service if the LIL will be automatically restarted after a bipole outage. This is to account for the runback of ML export and the possibility that load has shed before the LIL is successfully restarted. If the LIL frequency controller is not in-service when the LIL bipole is automatically restarted, the IIS frequency can go significantly beyond 62 Hz if all blocks of load have shed.

ML-LIL interaction studies

The coordinated runbacks of the ML for loss of a LIL pole or the LIL bipole were studied, as described above. It has been confirmed that UFLS is avoided under normal operation. Preliminary operating limits have been identified to ensure that UFLS is avoided in operating conditions when HVdc links or frequency controllers are not in service. These limits will be fully developed as part of the final phase of the operating studies.

Bay d'Espoir instability issues

Analysis was performed to assess the impact of a 3PF at BDE. It was found that
instability and transient undervoltage conditions for this event are a function of the
eastward flow from BDE to the Avalon Peninsula. With the LIL in service, instability
resulting from the 3PF at BDE can be avoided by limiting the flow in this corridor.
Analysis was also performed to identify maximum limits that may be transferred in this
corridor in the event of a LIL bipole outage.

ML frequency controller study

The analyses described above include the operation of the ML frequency controller in its current configuration. This is defined by a 0.5 Hz deadband and a capacity limit of +/- 100 MW. These settings were the basis for the analysis presented in this report and were found be acceptable for high power operation.

IIS performance with ML in and out of service

 As described above, preliminary analysis has been performed to assess operating limits to the LIL the event of an outage to the ML. Reserve requirements for the LIL have also been identified to ensure that the loss of the largest generator on the Island does not result in UFLS in the event of an ML outage.

PUB-NLH-003, Attachment 1 Reliability and Resource Adequacy Study Page 47 of 49



Newfoundland and Labrador Hydro RFI Studies

Stage 4A LIL Bipole: Preliminary Assessment of High Power Operation

- Soldiers Pond site for 4th high inertia synchronous condenser
 - o On the basis of the above, a fourth high inertia synchronous condenser at Soldiers Pond is not required in the near term. Study results indicate that instability resulting from the 3PF at BDE can be avoided by applying operational limits on the power flow from BDE to the Avalon Peninsula without impacting the ability to meet peak loads. It has also been found that the system can withstand a temporary bipole outage of up to 300 ms before the occurrence of UFLS. Further, it has been confimed that stable system operation can be achieved for a permanent bipole fault with a revised UFLS scheme. Based on the findings of this report, effective system reinforcements would involve the addition of generation on the Avalon Peninsula rather than a high inertia synchronous condenser. Such additions would help to offload power flow from BDE to the Avalon Peninsula in the event that LIL capacity is limited. This input will be considered as part of Hydro's ongoing Generation Planning review, which is expected to be completed in late 2018.

9.3 Next Steps

The following studies are the next phases of the Stage 4 LIL bipole studies being performed:

- Stage 4b PSS tuning study for all generators in the IIS
 This study is nearing completion, and will determine parameters for the power system stabilizers (PSS) for all of the generators in the IIS in order to improve the system's damping.
- Stage 4c Labrador Power Transfer study
 This study is currently underway and will include an operational review and will define the maximum power transfer limits between Muskrat Falls and Churchill Falls on the two 315 kV ac lines.
- 3. Stage 4d Full operational studies Once the boundaries of the study cases have been determined by earlier Stage 4 studies (4a through 4c), the final set of base cases can be created and the full steady state and dynamic analysis will be performed on the system to ensure the performance of the Labrador and IIS systems are within criteria, and to define any operating guidelines and/or further HVDC runbacks.

Appendix 1

Revised UFLS Scheme



```
NLH Underfrequency Load Shedding
        Burgeo load shed at 58.8 Hz
      St. Albans load shed at 58.6 Hz
        TL226 loads shed at 58.2 Hz
        TL220 loads shed at 58.1 Hz
195178, 'LDSHBL',1,58.9,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0833/
 195432, 'LDSHBL',1,58.9,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0833/
195409, 'LDSHBL',1,58.9,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0833/
195407, 'LDSHBL',1,58.9,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0833/
  195408, 'LDSHBL',1,58.9,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0833/
  195435, 'LDSHBL',1,58.9,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0833/
  195436, 'LDSHBL',1,58.9,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0833/
195437, 'LDSHBL',1,58.9,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0833/
NP Underfrequency Load Shedding
                                           -
k***************
/ 59.0 Hz 15 sec time delay block - KEN1,GLV - 54.9 + 8.9
  195135, 'LDSHBL',1,59.0,15.0167,1.000,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
/ 58.8 Hz block - BLK, GRH - 39.5 + 15.2
  196546, 'LDSHBL',1,58.9,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196221, 'LDSHBL',1,58.9,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
/ 58.6 Hz block - MDR, KBR1 - 90.2 + 39.7 (*MATCHES DFDT BLOCK)
  195624, 'LDSHBL',1,58.7,0.05,0.696,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196570, 'LDSHBL',1,58.7,0.05,0.600,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
/ 58.4 Hz block - CLV,SJM1 - 57.9 + 49.7 (*SAME AS DFDT BLOCK)
  195144, 'LDSHBL',1,58.6,0.05,0.885,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196568, 'LDSHBL',1,58.6,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
/ 58.2 Hz block - GFS,RRD - 0.6 + 40.6 (*SAME AS DFDT BLOCK)
  195126, 'LDSHBL',1,58.6,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196572, 'LDSHBL',1,58.6,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
/ 58.1 Hz block - GAN, VIR1, HWD1 - 23.4 + 70.1 + 53.3
  195132, 'LDSHBL',1,58.6,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196573, 'LDSHBL',1,58.5,0.05,0.787,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  195655, 'LDSHBL',1,58.5,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
/ 58.0 Hz block - COB, BRB, BCV, GOU, KEL, SLA - 28.6 + 24.5 + 27.7 + 27.2 + 23.6 + 56.7
  195130, 'LDSHBL',1,58.5,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  195167, 'LDSHBL',1,58.5,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/196562, 'LDSHBL',1,58.4,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196564, 'LDSHBL',1,58.4,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196560, 'LDSHBL',1,58.4,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
196567, 'LDSHBL',1,58.4,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  Additional Load Shedding - 11.1 + 38.4 + 23.5 + 17.3 + 49.1 + 63.7 + 7.0 + 10.9 + 12.4 + 6.9 + 12.5
  195654, 'LDSHBL',1,58.8,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196574, 'LDSHBL',1,58.8,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
196571, 'LDSHBL',1,58.8,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196569, 'LDSHBL',1,58.6,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196566, 'LDSHBL',1,58.6,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196563, 'LDSHBL',1,58.6,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/195450, 'LDSHBL',1,58.5,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  196559, 'LDSHBL',1,58.5,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  195173, 'LDSHBL',1,58.5,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
  195171, 'LDSHBL',1,58.4,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/195169, 'LDSHBL',1,58.4,0.05,1.0,0.0,0.0,0.0,0.0,0.0,0.0,0.0,0.1/
```